

ENVIRONMENTAL ASSESSMENT HUT burt Field, Florida October 2005













GENERAL PLAN ENVIRONMENTAL ASSESSMENT HURLBURT Field

Hurlburt Field, Florida October 2005

maintaining the data needed, and c including suggestions for reducing	ection of information is estimated to ompleting and reviewing the collect this burden, to Washington Headqu ald be aware that notwithstanding and MB control number.	ion of information. Send comment arters Services, Directorate for Inf	s regarding this burden estimate ormation Operations and Reports	or any other aspect of the property of the pro	his collection of information, Highway, Suite 1204, Arlington	
1. REPORT DATE 15 MAR 2006		2. REPORT TYPE		3. DATES COVE 00-00-2000	ERED 6 to 00-00-2006	
4. TITLE AND SUBTITLE				5a. CONTRACT	NUMBER	
General Plan Envi	conmental Assessme	ent Hurlburt Field,	Florida 5b. GRANT NUMBER			
				5c. PROGRAM I	ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NU	JMBER	
				5e. TASK NUME	BER	
				5f. WORK UNIT	NUMBER	
	ZATION NAME(S) AND AI Idea Center Blvd,D	` /	500	8. PERFORMING REPORT NUMB	G ORGANIZATION ER	
9. SPONSORING/MONITO	RING AGENCY NAME(S) A	AND ADDRESS(ES)		10. SPONSOR/M	IONITOR'S ACRONYM(S)	
				11. SPONSOR/M NUMBER(S)	IONITOR'S REPORT	
12. DISTRIBUTION/AVAIL Approved for publ		ion unlimited				
13. SUPPLEMENTARY NO	TES					
14. ABSTRACT						
15. SUBJECT TERMS						
16. SECURITY CLASSIFIC	ATION OF:		17. LIMITATION OF ABSTRACT	18. NUMBER OF PAGES	19a. NAME OF RESPONSIBLE PERSON	
a. REPORT unclassified	b. ABSTRACT unclassified	c. THIS PAGE unclassified	Same as Report (SAR)	478		

Report Documentation Page

Form Approved OMB No. 0704-0188

FINDING OF NO SIGNIFICANT IMPACT (FONSI) AND FINDING OF NO PRACTICABLE ALTERNATIVE (FONPA) GENERAL PLAN ENVIRONMENTAL ASSESSMENT HURLBURT FIELD, FLORIDA

1.0 BACKGROUND

Hurlburt Field has developed and amended its General Plan as prescribed in Air Force Instruction 32-7062 (Air Force Comprehensive Planning). The General Plan is a summary of the overall Base Comprehensive Plan (BCP), which is made up of numerous component plans created through a lengthy process involving extensive outreach with stakeholders, detailed research, review of existing installation documents, development of plan alternatives, and selection and refinement of preferred planning concepts. The General Plan, allows the recommendations developed in the detailed BCP to be communicated in a more concise and user-friendly format. In addition, the General Plan incorporates individual area development plans. The Capital Improvements Program (CIP) in the General Plan identifies future development projects to meet mission requirements.

The National Environmental Policy Act (NEPA), the Council on Environmental Quality (CEQ) regulations implementing NEPA ((40 CFR 1500-1508); and Air Force Instruction 32-7061 (Environmental Impact Analysis Process) require Air Force installations to consider the environmental consequences of major proposed actions. The environmental assessment (EA) for Hurlburt's General Plan addresses a selected group of projects currently listed in the CIP that are projected to begin construction within the timeframe of fiscal years (FY) 06 through FY 11. However, projects currently programmed for FY 12 as well as several other out-year projects are also included since there is a high probability that the priority of some of these projects may change resulting in moving them into the next five FY range. The complete list of projects addressed in the EA is given in Attachment 1 at the end of this document.

The EA was prepared in conjunction with the ongoing development of an environmental GIS database for Hurlburt Field. Beginning with the individual future projects covered under Sustainment, Restoration, and Modernization (SRM) and Military Construction (MILCON) funding sources listed in the CIP, a GIS database of individual projects was developed and combined with existing environmental data for Hurlburt Field. After completion of the base mapping process, GIS analysis tools were used to determine, where possible, quantifiable environmental impacts resulting in a detailed map for each project. For the purposes of analysis, the installation was divided into 11 previously identified storm water sub-basin areas. The cumulative impacts of proposed General Plan projects in each storm water subbasin were determined and then combined with an end result of a base-wide environmental analysis. Purpose and need for each individual project addressed in the EA is provided in project-specific DD Forms 1391, which are contained in an appendix to the EA.

2.0 DESCRIPTION OF ALTERNATIVES

The EA analyzes two build alternatives and a No-Action Alternative for the identified CIP projects. The Preferred Alternative, or Alternative 1, would involve selecting and implementing the CIP projects programmed for funding and construction over FYs 06 to 11 in the locations and with the site configurations as indicated in the General Plan as amended. General project locations and footprints of Alternative 1 projects are shown in Figure 5 of the EA and are shown in detail in Section 5.0 of the EA. These projects were analyzed as one action. Alternative 2 would involve the same identical CIP projects, but would either locate these projects on sites not selected in the actual General Plan or would structurally configure the projects differently on or near the same sites as shown in Figure 6 of the EA and detailed in Section 5.0 of the EA. As with Alternative 1, Alternative 2 projects were analyzed as one action. The No-Action Alternative would not construct any of the projects detailed in the Hurlburt Field General Plan as amended.

Existing facilities would continue to be used, and the only improvements would be related to general maintenance and upkeep. Any new missions that are expected to beddown at Hurlburt would be required to find space within existing facilities. Independently funded projects would likely continue to be constructed, and may require a separate EA-level of environmental analysis. Planned or programmed demolitions would also likely take place; however, the number of demolitions would be fewer with the No-Action Alternative than for either Alternatives 1 or 2, as any demolitions associated with this alternative would not be tied to any future construction.

3.0 ENVIRONMENTAL CONSEQUENCES

As shown in Table 1; overall, Alternative 1 would result in significantly fewer environmental impacts than would Alternative 2, with the exception of permitted wetlands (actually not an impact as they are currently permitted by the U.S. Army Corps of Engineers), Installation Restoration Program (IRP) sites, and tree removals.

impacts of	the Build Alternati	ves
Resource Area	Alternative 1 (Preferred Alternative)	Alternative 2
Unpermitted Wetlands	0.75 Acre	28.09 Acres
Permitted Wetlands	12.05 Acres	0.0 Acres
Cultural Resources	0.0 Acres	0.09 Acre
Floodplains	8.40 Acres	29.64 Acres
Trees Removed	218	67
RTE Habitat	0.0 Acres	0.72 Acre
Q/D Arc	7.04 Acres	12.13 Acres
Within the AICUZ	37 Projects	40 Projects
Within a Storm Surge Area	Categories 1, 2, 3, 4, and 5	Categories 2, 3, 4, and 5
IRP	6.29 Acres	4.46 Acres
Hazardous Materials	14 Projects	15 Projects
Air Emission Permits	Hydrant Fueling System	Hydrant Fueling System
New Impervious Surface Area	87.52 Acres	95.58 Acres
Demolitions	27.45 Acres	21.87 Acres

Alternative 1 projects would result in 87.52 total acres of new impervious surface area as opposed to 95.58 total acres of new impervious surface area created by Alternative 2 projects. There would be 27.45 acres of impervious surface removal through demolitions associated

with Alternative 1 versus. 21.87 acres of impervious surface removal through demolitions associated with Alternative 2. As a result, there would be a net increase of 60.07 acres of new impervious surface area associated with Alternative 1 and a net increase of 73.71 acres of new impervious surface area associated with Alternative 2. Therefore, potential impacts on recharge of the shallow Sand and Gravel Aquifer as well as impacts to surface water quality are less with Alternative 1 than with Alternative 2.

Impacts to floodplains are much less with Alternative 1 (8.40 total acres) than with Alternative 2 (29.64 total acres). Unpermitted wetland impacts are also far less with Alternative 1 (0.75 acre) than with Alternative 2 (28.09 acres). The 3.13 acres of permitted wetland impacts from implementation of Alternative 1 indicated in the EA along with an additional 8.92 acres north of Hurlburt's east airfield apron (total of 12.05 acres) were previously permitted by the Army Corps of Engineers under an existing longrange permit. The 12.05 acres of permitted wetland impacts accommodate the actual operational footprints plus buffer areas of two large projects associated with future mission expansion—a helicopter landing pad and SOF CV-22 aircraft parking.

Endangered species habitat would not be impacted by Alternative 1, whereas approximately 0.72 acre of such habitat would be lost (perhaps only in the short-term) by Alternative 2. Cultural resource areas would not be affected by Alternative 1, while about 0.09 acre would be affected by Alternative 2.

In comparing IRP sites, Alternative 1 would affect slightly more area (6.29 acres) than Alternative 2 (4.46 acres). However, the importance of these IRP "impacts" will need to be assessed in coordination with the IRP program manager on an individual project basis since, in many cases, project footprints appear to only overlap buffer areas adjacent to IRP sites where any potential impacts would only be on current or future monitoring efforts and not on any future cleanup operations.

There are 7.04 total acres of Q/D arc impacts with Alternative 1 versus 12.13 total acres of impact with Alternative 2. However, most of the Q/D arc area impacts are either roadway-related or are related to aircraft parking for aircraft related to the Q/D arc-generating activities.

While AICUZ is not a major issue due to either the aircraft-related mission of the proposed project or the ability to soundproof new buildings as required, 37 Alternative 1 projects occur within the 65 db or higher contours while 40 Alternative 2 projects occur within these areas.

The removal of trees having minimum trunk diameters of 6 inches and shown on GIS mapping would be approximately three times as great with Alternative 1 (218 trees) compared to Alternative 2 (67 trees). However, the vast majority of trees impacted by either build alternative occur in developed areas of the installation, and the trees involved are not considered specimen trees.

Storm surge areas for the proposed projects under Alternative 1 would include categories 1 to 5 whereas Alternative 2 would include categories 2 to 5.

The issue area of hazardous materials/wastes and solid waste is similar between the build alternatives based on the number of projects, with 14 projects for Alternative 1 and 15 projects for Alternative 2. Lastly, in regard to projected air emissions, Alternatives 1 and 2 are equivalent in the need to examine projects for impacts on maintaining Hurlburt's status as a synthetic minor source. The proposed hydrant fueling system would be of particular importance in this regard.

In summary, Alternative 1 (Preferred Alternative) projects, which comprises project sites and facility configurations as detailed in the Hurlburt Field General Plan as amended is both the environmentally and operationally preferred action alternative. In addition, Alternative 1 best meets the criteria of NEPA Section 101.

The No-Action Alternative would have minimal impacts on any of the resource/issue areas analyzed. However, this alternative would not meet the purpose and need of adequately providing for projected changes to existing and addition of new missions on Hurlburt Field.

4.0 FINDING OF NO PRACTICABLE ALTERNATIVE

Executive Order 11990, Wetlands Management, requires all Federal actions to minimize and avoid impacts to wetlands, while Executive

Order 11988, Floodplain Management, requires all Federal actions to minimize and avoid impacts to floodplains. As described under AFI 32-7061, Environmental Impact Analysis Process, a FONPA must be submitted for approval to the proper headquarters when the alternative selected is located in wetlands or floodplains. The FONPA must discuss why no other practical alternative exists to avoid impacts. In the case of the General Plan EA, implementation of Alternative 1 (the Preferred Alternative) would impact a total of 0.75 acres of previously unpermitted wetlands, 12.05 acres of previously permitted wetlands, and 8.40 acres of floodplain on Hurlburt Field despite extensive planning efforts to avoid these areas. However, in the cases of both wetlands and floodplains, overall impacts are extremely small considering the total extent of planned new facilities and the fact that almost 50 percent of Hurlburt Field is wetland and/or floodplain. In all cases, individual projects impacting wetlands or floodplains were sited in these areas because of functional, adjacency, or operational requirements. Details are given in Table 2.

5.0 MITIGATION

Although avoidance of environmental impacts was the first concern in siting and configuring Alternative 1 projects, mitigation measures for unavoidable impacts have been also been identified. These mandatory mitigation provisions are detailed in Attachment 2 at the end of this document. Hurlburt Field personnel will ensure that these measures are accomplished as necessary.

6.0 Public Involvement AND COORDINATION

The General Plan EA, Hurlburt Field, Florida was made available for the 30-day mandatory public review period from November 4, 2005 to December 4, 2005. Copies of the EA were also mailed to the Florida State Clearinghouse for distribution to appropriate state regulatory agencies. In addition, copies of the EA were sent to the U.S. Fish and Wildlife Service and to the U.S. Army Corps of Engineers. No comments were received from the general public. The Florida Fish and Wildlife Conservation Commission recommended that two structures, which have supported nesting

	Preferred A	Table 2 Iternative Projects Impacting	g Floodplains and/or Wetlands
EA Project Number	Name	Floodplain/ Wetland Impact	Requirements
02-01	Construct Outdoor Recreation Center	21,016 SF Floodplain	Facility must be located near marina along Santa Rosa Sound near other existing recreational facilities.
04-03	Supply Warehouse	8,297 SF Floodplain	Only the access roadway is within an identified floodplain area, and this is within an area where some military family housing units are currently located.
05-01	123 Person Billeting	16,444 SF Floodplain	Most impact is for parking area and access to existing roa- in floodplain. Must be located adjacent to planned conference center and consolidated club.
07-03A	AT/FP Main Gate and Soundside Access Control Facilities	1,353 SF Floodplain	All new roadway surfaces are needed for security and traffic control into the Soundside area of Hurlburt Field.
07-10A	Base Roadway Improvements	28,444 SF Floodplain	All roadway surfaces connecting existing roadways alread within the floodplain.
08-01	RED HORSE Vehicle Maintenance Facility	4,168 SF Floodplain	One portion of a planned of a 32,500 sq ft building extending into a floodplain. Location needs to be within the self-contained RED HORSE area of the installation.
11-02	Fill/Clear Wetlands, Helicopter Landing Pad	130,078 SF Floodplain	A previously permitted site extending Hurlburt's east apror for expanded operations. 1
11-04	SOF Engine Maintenance and Storage Shop	6,756 SF Wetland	Must be operationally located next to planned SOF C0130 Aircraft Apron (EA Project 11-11).
11-11	SOF C-130 Aircraft Apron	21,074 SF Wetland	Must be operationally located next to existing airfield apror on west side of airfield.
11-13	Hydrant Fueling System	27,128 SF Floodplain 4,761 SF Wetland	Location near airfield and bulk fuel tanks required.
11-22	SOF CV-22 Aircraft Parking	129,223 SF Floodplain	A previously permitted site extending Hurlburt's east apror for expanded operations. 1

colonies of the state-threatened least tern and which are scheduled for demolition (Buildings 90710 and 90329) not be disturbed between April and August-the nesting season for the terns. The Florida Department of Environmental Protection (DEP) suggested that a meeting be scheduled to develop a clear plan of action regarding 404/401 permitting issues. DEP also requires that Hurlburt notify the Northwest District DEP office concerning individual project requirements for storm water treatment. Depending on location, the projects may use a previously established on-site storm water treatment "bank" or may require a separate storm water quality permit and individual treatment for the first half-inch of runoff. Finally, the EA was determined to be conditionally consistent with Chapters 372, Florida Statutes, under the Florida Coastal Management Program. Further details concerning State agency coordination are provided in Appendix A (Coordination Documents) of the EA.

Approved:

Mark D. Wright, Col., USAF Director, Installations and Mission Support

7.0 CONCLUSION

Based on my review of the facts and analysis contained in the EA and an agency review comments, I conclude that Alternative 1 (the Preferred Alternative) would not have a significant impact either by itself or cumulatively with any other known past or future actions. Furthermore, I find that there are no practicable alternatives to the sitings of the listed projects within identified floodplain and wetland areas as shown in Table 2 of this document. Accordingly, the requirements of the National Environmental Policy Act, regulations promulgated by the President's Council on Environmental Quality, and provisions of AFI 32-7061 have been fulfilled. Furthermore, based on public and agency comments on the EA, the U.S. Air Force has determined that no changes to the document are necessary. The draft EA will serve as the final EA. An environmental impact statement is not required and will not be prepared for implementation of the Preferred Alternative.

Date

	Attachment 1			
Sub-Basin	List of Projects Considered			
Project #	FTEV#	Description		
02-01	02-1001	Construct Outdoor Recreation Center, 16 SVS		
04-01	04-1072	ADAL Fitness Center, Building 90517		
04-02	95-3013	Temporary Lodging Facility		
04-03	04-3016	Supply Warehouse		
04-04	99-3036	Child Development Center		
04-05	03-3021	16th Contracting Squadron Facility		
04-06	97-3019	Airmen Leadership School		
04-07	02-3015	SOF JSOU Library/Education Center Com/Language Lab PH 3		
05-01	03-3020	123-Person Billeting		
06-01	01-5007	Consolidated Club		
06-02	02-3011	Mission Planning Center		
07-01	04-3020	ADAL Command Post		
07-02	96-2010	Realign O'Neil Avenue/Install Traffic Signal		
07-03	03-3022	AT/FP Main Gate and Soundside Access Control Facilities		
07-04	04-5003	Family Camping Facility		
07-05	04-3006	SOF Weapons & Release Systems Shop		
07-06	03-3017	STG Headquarters Facility		
07-07	04-3000	Refueling Vehicle Maintenance Facility		
07-08	03-3004	Vehicle Operations Administration Facility		
07-09	96-3008	SOF Maintenance Operations Squadron Facility		
07-10	99-3011	Base Roadway Improvements		
07-11	99-3033	Squadron Operations Facility, 6 SOS		
08-01	00-3009	RED HORSE Vehicle Maintenance Facility		
08-02	02-3005	RED HORSE Mobility and Training Facility (823 RHS)		
08-03	00-5004	Shoppette Facility, East Side		
08-04	99-3013	Construct Dormitory (144 pn) East Side		
08-05	00-3023	Eastside Fitness Center		
08-06	03-3013	Widen Independence Road		
08-07	03-3018	AFLD Waiver, Alter Independence Road		
08-08	04-3011	SOF UAV Squadron Operations Facility		
08-09	04-3012	SOF UAV Maintenance Hangar/Parking Apron		
11-01	04-5002	Construct Workbays at Auto Hobby Shop, Building 90612		
11-02	03-1049	Fill/Clear Wetlands, Helicopter Landing Pad		
11-03	94-3001	ADAL Security Forces Operations (Current Mission)		
11-04	97-3006	SOF Engine Maintenance and Storage Shop		
11-05	97-3018	Fire Crash/Rescue Station		
11-06	01-3021	25th Intelligence Squadron Operations Facility		
11-07	03-3014	Realign Cruz Avenue		
11-08	04-3005	SOF Squadron Opst Talon II		
11-09	02-3010	Add to Visiting Quarters		
11-10	02-3013	ADAL USAFSOS Facility		
11-11	04-3004	SOF C-130 Aircraft Apron		
11-12	04-3007	SOF Survival Equipment Shop		
11-13	97-3016	Hydrant Fueling System		
11-14	03-3006	Visiting Officers Quarters		
11-15	03-3015	Realign Cruz Avenue, Phase 2		
11-16	04-3008	SOF Dash-21 Maintenance Facility		
11-17	04-3009	SOF Maintenance Storage Facility		
11-18	04-3010	SOF C-130 Talon II Maintenance Hangar		
11-19	96-3012	SOF Squadron Operations Facility, 18 Flts		
11-20	97-3009	Operations Group/Operations Pans Facility		
11-21	02-3014	SOF JSOU Headquarters Facility Phase II		
11-22	04-3014	SOF CV-22 Aircraft Parking Apron		

	Attachment 2 Mitigative Actions
Resource or Issue Area	Mitigation
Storm Water and Erosion Control	 Best Management Practices regarding appropriate storm water management and erosion and sediment control plans will be used for all projects. This could include construction of additional detention/retention basins, modifying existing storm water control structures, installation of additional catch basins, temporary use of silt fencing, and use of vegetated swales to slow and absorb surface sheet flow, etc. Bare ground will be revegetated as soon as possible following the construction phase or during any prolonged pause in construction activities.
Threatened and Endangered Species	 Demolition of Buildings 90710 or 90329 during least tern nesting season (April through August) will be avoided.
Landscape Elements	 Sale of downed trees and other woody vegetation for firewood and mulch will be pursued to reduce the amount of woody vegetation in the solid waste stream. Native species will be used for all replacement trees and other plantings as defined by Hurlburt Field's Landscape Management Plan and tree replacement policy.
Wetlands and Floodplains	 Any required wetland permitting will be pursued on a project-by-project basis with the Florida Department of Environmental Protection and the U.S. Army Corps of Engineers as required by Sections 404/401 of the Clean Water Act. Coastal zone consistency will also be reviewed with DEP personnel at this meeting.
"Green Buildings"	 Authorized salvage personnel and/or incorporation of specific deconstruction techniques will be used the maximum extent to minimize solid waste generation during building renovation, construction, or demolition. Current building codes will be incorporated into new structure development in order to maximize energy efficiency. Energy efficient equipment and utilities will be specified when designing facilities in order to decrease energy demand and minimize greenhouse gas emissions.
Installation Restoration Program	 Work on all projects identified as potentially impacting a known IRP site and/or installed IRP site monitoring or remediation systems will be coordinated through the Hurlburt IRP manager as early in the design stage as possible and prior to any soil disturbance.

GENERAL PLAN ENVIRONMENTAL ASSESSMENT HURLBURT FIELD, FLORIDA

Prepared For:

16 Civil Engineering Squadron Hurlburt Field, Florida

Prepared By:



and



October 2005



TABLE OF CONTENTS

			Page
Secti	on 1.0–	-Background	1-1
1.1		on and Area	1-1
1.2		/ Mission	1-1
1.3		eneral Planning Process	1-6
1.4		nmental Documentation Approach	1-8
1.5	GIS C	omponent to the EA Analysis	1-18
Secti	on 2.0-	-Purpose and Need	2-1
2.1	Utilitie	S	2-1
2.2		Jse	2-1
2.3		portation	2-2
2.4		I Improvements	2-2
Secti	on 3.0-	-Description of Proposed Action and Alternatives	3-1
3.1	Alterna	ative 1 (Implementation of Bundled Five-Year CIP Projects)—Preferred Alternative .	3-1
3.2	Alterna	ative 2 (Siting and/or Design of CIP Projects in Alternative Installation Locations)	3-2
3.3	No-Ac	tion Alternative	3-2
3.4	Alterna	ative Initially Considered but Dismissed	3-2
	3.4.1	Bundled Environmental Analysis of All CIP Projects	3-2
3.5	Resou	rce/Issue Areas Not Analyzed	3-7
	3.5.1	Topography, Geology, and Soils	3-7
	3.5.2	Estuarine Resources	3-7
	3.5.3	Land Use	3-7
	3.5.4	Historical Resources	3-7
	3.5.5	Aircraft Operations	3-7
	3.5.6	Safety and Occupational Health	3-8
	257	Pormitting logged	20

			Pa
Secti	ion 4.0-	-Resource/Issue Areas	
4.1	Groun	dwater	
4.2		e Water and Storm Water	
4.3		plains	
4.4		Surge Areas	
4.5		al Zone Management	
4.6		nds	
4.7		and Fauna	
4.8		Threatened, and Endangered Species	
4.9		ological Resources	
4.10			
4.11		ality	
4.12		ructure and Traffic	
4.13 4.14		ated Special, Solid, and Hazardous Materials and Wastes	
		-Environmental Consequences and Cumulative Impacts	
- 1	المخمد ال		
5.1 5.2		action	
5.2	Region	nal Analysis of Air Quality, Noise, and Coastal Zone Impacts	
	5.2.1	Air Quality	
	5.2.2	Noise	
	5.2.3	Coastal Zone Impacts	
	5.2.4	Socioeconomic Resources	
5.3		asin 1	
5.4	Sub-B	asin 2	
	5.4.1	Overview of Alternative 1	
	5.4.2	Overview of Alternative 2	
	5.4.3	Analysis	
5.5	Sub-B	asin 3	
5.6	Sub-B	asins 4 and 5	
	5.6.1	Overview of Alternative 1	
	5.6.2	Overview of Alternative 2	
	5.6.3	Analysis	
5.7	Sub-B	asin 6	
	5.7.1	Overview of Alternatives 1 and 2	
	5.7.2	Analysis	
5.8	Sub-B	asin 7	
	5.8.1	Overview of Alternative 1	
	5.8.2	Overview of Alternative 2	
	583	Analysis	

		Page
5.9	Sub-Basin 8	5-49
	5.9.1 Overview of Alternative 1	5-49
5.10	Sub-Basin 9	
	5.10.1 Overview of Alternative 1	5-59
5.11	Sub-Basin 10	
	5.11.1 Overview of Alternative 1	5-59
5.12	Sub-Basin 11	5-70
	5.12.1 Overview of Alternative 1	5-75
Secti	on 6.0—Findings and Conclusions	6-1
6.1 6.2 6.3 6.4	Unavoidable, Direct, Adverse Effects from the Proposed Action Cumulative Impact Summary Mitigation Measures Summary Relationship of Short-Term Uses and Long-Term Productivity Resulting from the Proposed Action	6-2
Secti	on 7.0—List of Preparers	 7- 1
7.1 7.2	Hurlburt FieldWoolpert, Inc	
Secti	on 8.0—References	8-1

Appendices

Appendix A—Coordination Documents Appendix B—Project List Appendix C—DD Form 1391s

List of Tables

Table		Page
1	Partial List of Hurlburt Field Planning Documents	1-7
2	List of Projects Addressed by Fiscal Year	1-10
3	Environmental Assessment Projects, 2005	1-12
4	Demolitions by Sub-Basin for Alternative 1	3-2
5	Demolitions by Sub-Basin for Alternative 2	3-2
6	Hurricane Strom Categories, Wind Speed, Storm Surges, and Frequencies in the Hurlburt Field Area	4-7
7	Species of Federal-Listed Animals Possible at Hurlburt Field	4-9
8	Florida Coastal Management Plan Proposed Action Checklist	5-3
9	Impact Summary for Sub-Basin 2, Alternative 1	5-4
10	Installation MILCON and SRM Projects in Sub-Basins 4 and 5, Alternative 1	
11	Impact Summary for Sub-Basins 4 and 5, Alternative 1	
12	Installation MILCON and SRM Projects in Sub-Basins 4 and 5, Alternative 2	
13	Impact Summary for Sub-Basins 4 and 5, Alternative 2	
14	Installation MILCON and SRM Projects in Sub-Basin 6, Alternative 1	
15	Impact Summary for Sub-Basin 6, Alternative 1	
16	Installation MILCON and SRM Projects in Sub-Basin 7, Alternative 1	
17	Impact Summary for Sub-Basin 7, Alternative 1	
18	Installation MILCON and SRM Projects in Sub-Basin 7, Alternative 2	
19	Impact Summary for Sub-Basin 7, Alternative 2	
20	Installation MILCON and SRM Projects in Sub-Basin 8, Alternative 1	
21	Impact Summary for Sub-Basin 8, Alternative 1	
22	Installation MILCON and SRM Projects in Sub-Basin 8, Alternative 2	
23	Impact Summary for Sub-Basin 8, Alternative 2	
24	Installation MILCON and SRM Projects in Sub-Basin 10, Alternative 2	
25	Impact Summary for Sub-Basin 10, Alternative 2	
26	Installation MILCON and SRM Projects in Sub-Basin 11, Alternative 1	
27	Impact Summary for Sub-Basin 11, Alternative 1	
28	Installation MILCON and SRM Projects in Sub-Basin 11, Alternative 2	
29	Impact Summary for Sub-Basin 11, Alternative 2	
30	Cumulative Impacts for Alternative 1	
31	Cumulative Impacts for Alternative 2	6-2

List of Figures

Figure	e	Page
1	Vicinity Map	1-2
2	Hurlburt Field	1-3
3	Planning Process	1-7
4	Hurlburt Field Sub-Basin Boundaries	1-19
5	Alternative 1	3-3
6	Alternative 2	3-5
7	Natural Resources and Constraints	4-3
8	Operational Constraints	4-5
9	Surface Water Sub-Basin 1 (Alternative 1)	5-5
10	Surface Water Sub-Basin 1 (Alternative 2)	5-7
11	Surface Water Sub-Basin 2 (Alternative 1)	5-9
12	Surface Water Sub-Basin 2 (Alternative 2)	5-11
13	Surface Water Sub-Basin 3 (Alternative 1)	5-17
14	Surface Water Sub-Basin 3 (Alternative 2)	5-19
15	Surface Water Sub-Basins 4 and 5 (Alternative 1)	5-21
16	Surface Water Sub-Basins 4 and 5 (Alternative 2)	5-23
17	Surface Water Sub-Basin 6 (Alternative 1)	5-31
18	Surface Water Sub-Basin 6 (Alternative 2)	5-33
19	Surface Water Sub-Basin 7 (Alternative 1)	5-37
20	Surface Water Sub-Basin 7 (Alternative 2)	5-37
21	Surface Water Sub-Basin 8 (Alternative 1)	5-51
22	Surface Water Sub-Basin 8 (Alternative 2)	5-53
23	Surface Water Sub-Basin 9 (Alternative 1)	5-61
24	Surface Water Sub-Basin 9 (Alternative 2)	5-63
25	Surface Water Sub-Basin 10 (Alternative 1)	5-65
26	Surface Water Sub-Basin 10 (Alternative 2)	5-67
27	Surface Water Sub-Basin 11 (Alternative 1)	5-71
28	Surface Water Sub-Basin 11 (Alternative 2)	5-73



This page intentionally left blank.



1.1 LOCATION AND AREA

Hurlburt Field is located on 6,634 acres in Okaloosa County within the Florida Panhandle (Figure 1). The installation is about 35 miles east of Pensacola and is bordered by the city of Mary Esther and Santa Rosa Sound and is located within the Eglin Reservation. Primary highway access to Hurlburt Field is via U.S. Highway 98 (US 98). Hurlburt Field was formerly known as Eglin Auxiliary Field 9, and the installation retains close organizational and operational ties to Eglin Air Force Base (AFB). A Host Tenant Agreement exists between Air Armament Center on Eglin AFB and 16th Special Operations Wing (SOW), which gives operational control of Hurlburt Field to the 16th SOW. There are 7.322 active duty, 10,860 family members, and 853 civilians working and/or living on Hurlburt.

Hurlburt Field lies within the region of the Florida Panhandle known as the Emerald Coast, which extends roughly 50 miles on either side of the city of Fort Walton Beach and roughly parallels US 98. This coastal area is known for its white sand beaches, favorable climate, and reasonable cost of living. As a result, the area is undergoing rapid population growth. The city of Mary Esther, located east of Hurlburt Field, has a population of approximately 4,500. The largest municipality in the immediate area of Hurlburt Field is the city of Fort Walton Beach with a population of 22,000. Smaller nearby communities include Navarre, Navarre Beach, Ocean City, and Shalimar.

Hurlburt Field is divided into a western and eastern section by the 9,600-foot runway and associated airfield (Figure 2). Additionally, while

most of the installation is located north of US 98. the Soundside area south of US 98 provides space for officer housing; the Soundside Club; the petroleum, oils, and lubricants (POL) marine dock: the installation marina: and other outdoor recreational facilities. The western section of the installation north of US 98 contains the flight line support functions for Hurlburt Field's fixed-wing missions, the main cantonment area, and additional housing as well as less developed areas containing the rifle range and Explosive Ordnance Disposal (EOD) operations. RED HORSE operations and training, flight line support facilities for Hurlburt Field's rotary-wing missions, additional family housing, commercial (commissary, base exchange, and other concessions), and medical facilities are located east of the airfield.

1.2 MILITARY MISSION

Hurlburt Field is the home of Headquarters Air Force Special Operations Command (HQ AFSOC). Hurlburt Field and Moody AFB (near Valdosta, Georgia) are the only installations in this major command. The HQ AFSOC mission is to organize, train, equip, and educate Air Force special operations forces for worldwide deployment and assignment to regional unified command for conducting:

- Unconventional warfare
- Direct action
- Special reconnaissance
- Counter-terrorism
- Foreign internal defense
- Humanitarian assistance
- Psychological operations





FIGURE 1





Environmental Assessment

Hurlburt Field

Hurlburt Field, Florida

Legend
Installation Boundary
Existing Structures
Golf Course
Roads
Shoreline
Surface Water

- Personnel recovery
- Counter-narcotics

The 16th SOW at Hurlburt Field is HQ AFSOC and it is the oldest and most seasoned unit. It includes the 4th Special Operations Squadron (SOS), 6th SOS, 8th/711th SOS, 9th/5th SOS, 15th SOS, 16th SOS, 19th SOS, and 20th SOS.

The 4th SOS flies AC-130 Spooky Gunships for missions of close air support, armed reconnaissance, and interdiction associated with conventional and joint special operations forces.

The 8th/711th SOS (now a combined Reserve and Active Duty unit located at Duke Field on Eglin AFB) employs the MC-130E Combat Talon, while the 15th SOS based on Hurlburt Field flies the MC-130H Combat Talon II. Both aircraft support unconventional warfare missions and special operations forces and are capable of high-speed, low-level airdrops. The Combat Talon I has terrain-following radar and computer systems which enable it to locate and drop equipment in unmarked drop zones with pinpoint accuracy day or night and under all weather conditions. The 8th SOS can provide refueling of special operation helicopters behind enemy lines. The 8th and 15th SOSs both work closely with the Army Rangers and Navy SEALS. The 716th Maintenance Squadron also operates from Duke Field.

The 9th/5th SOS flies the MC-130P/N Combat Shadow tankers out of Eglin AFB for worldwide clandestine penetration of enemy territory to provide aerial refueling of special operation helicopters. To support the unconventional warfare mission, the 9th SOS flies low-level, communications-out in close trail formation using night-vision goggles.

The 16th SOS flies the AC-130H Spectre Gunship which is a modified version of the Lockheed C-130 aircraft. The aircraft is heavily armed with two side-firing 20 mm Vulcan cannons, a 40 mm Bofors cannon, and one Army 105 Howitzer.

The Air Force's most sophisticated helicopter, the MH-53J Pave Low IIIE, is flown by the 20th SOS, also known as the Green Hornets. The Pave Low is a modified version of the HH-53 Super Jolly equipped for day or night low level penetration into hostile or enemy territory to accomplish clandestine operations, aerial

gunnery support, and reinforcement throughout the world. The Pave Lows are used in longrange infiltration/exfiltration and resupply of special operations forces day, night, or in marginal weather conditions. They also provide combat search and rescue support.

The 6th SOS supports a foreign internal defense-training mission. This unit flies fixedwing BT-67 aircraft, and UH-1H helicopters.

Other components of the HQ AFSOS stationed at Hurlburt Field include the 720th Special Tactics Group (STG), the USAF Special Operations School (USAF SOS) [now under the Joint Special Operations University (JSOU)]. and the 18th Flight Test Squadron. The 720th STG, which has strategically placed units worldwide, is comprised of special operations combat control teams and pararescue forces. The JSOU provides special operations-related education to personnel from all branches of DoD, governmental agencies, and allied nations. Subjects include regional affairs, cross-cultural communications, anti-terrorism, revolutionary warfare, psychological warfare, and other areas. The 18th Flight Test Squadron conducts operational tests and evaluations of equipment, concepts, tactics, and procedures for employment of special operations forces. The Air Force Command and Control Training and Innovation Center located at Hurlburt Field is the focal point for the integration of all air and space command and control. The unit trains combat forces in tactics to conduct joint and combined operations, and is responsible for conducting joint-service, component-level command, and control battlestaff training.

Hurlburt Field flying missions are scheduled through Eglin AFB, and, while munitions testing and evaluation take priority over special operations training on the Eglin AFB range, the predominately nighttime operations of Hurlburt Field's special operations aircraft and troops is generally compatible with other daytime uses of the range. Test Area A-77 is the most heavily used Eglin AFB location for air-to-ground live fire training by Hurlburt Field based units. Special forces dropped by Hurlburt Field aircraft into drop zones scattered throughout the Eglin AFB range span out in various directions depending upon the training objectives. Other frequently used Eglin AFB live fire ranges include A-78, B-7, and R2914A:C52N. Airdrops and landings are accomplished at R29156A:B6 and

R2914A:C61A/C5. Air refueling training takes place over the Gulf of Mexico in W151 designated airspace.

Hurlburt Field aircraft often egress and ingress along the northern border of the Eglin AFB range near the city of Crestview. These flights are associated with nighttime training missions in the mountains of eastern Tennessee and western North Carolina.

1.3 THE GENERAL PLANNING PROCESS

All Air Force installations are required to develop and maintain a General Plan as prescribed in Air Force Instruction (AFI) 32-7062, *Air Force Comprehensive Planning.* The General Plan is a summary of the overall Base Comprehensive Plan (BCP), which is made up of numerous component plans created through a lengthy process involving extensive outreach with stakeholders, detailed research, and review of existing installation documents, development of plan alternatives, and selection and refinement of preferred planning concepts. The General Plan, allows the recommendations developed in the detailed BCP to be communicated in a more concise and user-friendly format.

Component plans within the BCP Process that serve as building blocks to the General Plan include:

- Composite Constraints and Opportunities Plan—Identifies and maps existing natural, operational, and cultural resources (such as geologic features, wetlands, floodplains, Air Installation Compatible Use Zones [AICUZ], etc.).
- Infrastructure Plan—Identifies and maps locations of all utility and communication systems.
- Land Use Plan—Identifies and analyzes functional relationships, land use compatibility, and facility adjacency requirements as well as integrating off-base planning efforts with local governmental and private entities.
- Capital Improvements Plan—Integrates all previous plans and potential projects into one document and provides more detail on

the physical location of specific projects in order to be approved for funding. It also identified planned projects in the context of architectural compatibility and installation landscape development standards.

- Integrated Natural Resources
 Management Plan (INRMP)—Specifically
 outlines the care and management of on-site
 natural resources.
- Integrated Cultural Resources
 Management Plan (ICRMP)—Similar to the
 INRMP, but pertains to the care and
 management of cultural resources.

A wide variety of other underlying and continually updated plans beyond the abovelisted component plans also contribute to the BCP process. As a BCP summary document, the General Plan provides a dynamic and fluid document that represents the environment in and around an installation at a "snapshot in time." In addition to directly supporting the development and updating of the General Plan, Area Plans elaborate on the development of special areas of the installation such as community areas, housing, administrative areas, etc. These plans can include alternative development plans, preliminary facility site development, roadways, parking, etc. Table 1 illustrates Hurlburt Field's comprehensive planning history, each of which is reflected in and contributed to the formation of the General Plan.

Site plans, which may or may not be associated with an Area Plan, are the most-precise planning documents in terms of indicating building locations and orientation, parking areas, etc. These plans are usually considered a preconstruction, design-phase, level of detail and are the basis for environmental analysis in this EA.

The Hurlburt Field General Plan consolidates all available installation planning data, highlights issues, assesses development potential, and provides guidance and direction for future development Figure 3 illustrates the general planning process that has been followed at Hurlburt Field.

Over the past decade, Hurlburt Field has undergone rapid development and redevelopment in response to the increasing

Table 1 Partial List of Hurlburt Field Planning Documents					
	t of Huriburt Field Planning Documents				
Date	Document				
In Progress	General Plan Environmental Assessment				
In Progress	Mission Rehearsal Isolation Area Subarea Development Plan				
In Progress	RED HORSE Subarea Development Plan (Update)				
2003	General Plan				
2003	Air Force Command and Control Training and Innovation Center (AF C2TIC) Phase II Customer Concept Documents				
2002	Cultural Resources Management Plan (Update)				
2002	Integrated Natural Resources Management Plan and Environmental				
	Assessment (Update)				
2002	Air Force Command and Control Training and Innovation Center (AF C2TIC) Phase I Customer Concept Documents				
2002	Joint Special Operations University				
2000	Subarea Development Plan Long-Range Facilities Development Plan (Update)				
1999	Land Use and Community Center Plans (Update)				
1999	Air Force Command and Control Training and Innovation Center (AF C2TIC)				
1999	Subarea Development Plan Aerial Photography, Survey, and Data Creation for Base Map C-1				
1998	Comprehensive Wetland Delineation				
1997	Marine Terminal Subarea Development				
1997	Marina Development Plan				
1997	Landscape Development Plan				
1997	Cody Avenue Subarea Development Plan				
1997	AC-130 Subarea Development Plan				
1997	RED HORSE Subarea Development Plan				
1997	Base-Wide Wetland Delineation				
1996	Cultural Resources Management Plan				
1996	Transportation Plan				
1996	Integrated Natural Resources Management Plan				
1996	Environmental Quality Protection Plan				
1996	Environmental Quality Protection Plan Natural and Cultural Resources Component Plan				
1995	Permanent Exercise Facility Area Development Plan				
1994	Land Use and Community Center Plan				
1994	Long-Range Facilities Development Plan				
1994	Commander's Summary				

importance and technological sophistication of Air Force Special Operations Command (AFSOC). The pace of development and change is expected to continue, thus making good environmental, land use, and facility planning essential to accommodating mission changes while, at the same time, protecting sensitive natural and cultural resource assets and enhancing the quality-of-life for assigned personnel. Hurlburt Field's General Plan was completed in 2002 (Woolpert, Inc., 2002) and has been approved by the 16th SOW




Figure 3: Planning Process

Commander and HQ AFSOC. The Hurlburt Field General Plan reflects all permanently assigned units at Hurlburt Field, and plans/programs for future construction must follow the guidelines established by the Hurlburt Field General Plan. In addition, the General Plan incorporates several area development plans and reflects their findings and recommendations in the Capital Improvements Plan (CIP).

The General Plan was formulated over a 2-year period and included five major components that reflect the more detailed BCP component plans:

- Plan Overview—Compilation of background data, explanation of the planning process, planning goals and objectives, implementation procedures, and installation description.
- Constraints and Opportunities—A
 summary of existing natural resources,
 cultural resources, environmental
 compliance, and operational constraints to
 development across the entire installation.
- Infrastructure Analysis
 —Analysis of utility and communications systems, energy conservation, and fire protection.
- Land Use—Description of existing and future land uses as well as the transportation system of the installation and surrounding area.

5. **CIP**—Discussion of existing facilities, future construction and demolition, and small area development recommendations.

The Hurlburt Field General Plan's foundational documents identifying known and forecasted changes in facility needs at Hurlburt Field over the coming decades are the Land Use Plan, the Long-Range Facilities Development Plan (LRFDP), and the CIP. The LRFDP takes the broad recommendations for the future siting of facilities found in the Land Use Plan and articulates site-specific constraints and opportunities. The purpose of the LRFDP is to provide recommendations for both short-term (5 years) and long-term (20 years) facility siting information consistent with the goals and objectives for future installation development. The stated goals of the LRFDP are as follows:

- Replace outdated facilities.
- Provide guidance for future facility siting.
- Consolidate functional organizations as much as possible.
- Meet long-term facility requirements for all host and associate organizations on the installation.
- Retain flexibility to reuse facilities and modify missions.
- Reflect HQ AFSOC standards in facility design and construction.

The CIP moves the planning process from siting to the preliminary facility design level while also prioritizing all future facility requirements. Projects in the CIP are assigned Project Numbers and Category Codes, and details are provided concerning estimated costs, square footage, environmental issues, and other specific information. Utilization of the CIP in planning and environmental analysis has been particularly advantageous to Air Force installations by allowing the planning process to be more fully integrated into the NEPA process. The CIP provides a starting point for organizing the "when and where" of planned projects.

Projects within the CIP may be funded through any number of variously identified military budgets including Military Construction (MILCON) funds; Sustainment, Repair, and Maintenance (SRM) funds; Non-Appropriated Funds (NAF); Defense Emergency Response Funds; Military Family Housing (MFH) funds; Defense Logistics Agency funds; tenant organization funding; outside grants; and so on.

Most projects are funded through SRM or MILCON funding.

In summary, the projects within Hurlburt Field's General Plan addressed in this EA are the product of literally decades of careful installation planning built on a foundation of many other underlying planning documents. Each of these underlying planning documents whether BCP component plans or Area Plans, in turn, have been developed in a manner sensitive to environmental and cultural resources constraints and opportunities as well as to operational requirements of the installation and the ability of installation infrastructure to support the planned facilities. The facilities addressed in this EA have gone through this long-term multi-planning screen prior to being addressed in a manner focusing on cumulative impacts within this present document.

1.4 ENVIRONMENTAL DOCUMENTATION APPROACH

The environmental impacts of all Air Force facility projects must be documented in accordance with the provisions of AFI 32-7061, Environmental Impact Analysis Process, which satisfies the requirements of the National Environmental Policy Act (NEPA) as implemented through Council of Environmental Quality (CEQ) Regulations (40 CFR Part 1500). The level of required environmental impact analysis depends upon the nature of the project and its location. Determining the level of analysis begins with completion of an AF Form 813 (Request for Environmental Impact Analysis) and coordinating the completed form through the installation's civil engineering environmental staff for evaluation. Projects having negligible impacts may qualify for a Categorical Exclusion (CATEX). Projects with a predicted higher level of impact must be documented through development of an Environmental Assessment (EA) that leads either to a signed decision document (Finding of No Significant Impact) allowing the project to proceed or a determination that an Environmental Impact Statement (EIS) will need to be developed.

This EA was developed using an ecosystem approach to analyzing environmental impacts.

The US Environmental Protection Agency defines "ecosystem" as "the interacting system of a biological community and its non-living environmental surroundings." In other words, the ecosystem approach looks beyond the immediate area of impact (in this case an individual facility site) and, instead, attempts to determine and analyze the impacts over a broader area. In the case of this EA, analysis is conducted within storm water drainage subbasins within the larger watersheds of Santa Rosa Sound and the East Bay River as the "ecosystem" component (Figure 4). Although somewhat artificial boundary lines, each subbasin has an identified discharge point into natural waters surrounding Hurlburt Field. Therefore, water quality and its impact on ecological communities in these freshwater or estuarine natural waters is affected by each project individually and cumulatively within a given watershed. Additionally, beyond impacts on surface waters, projects grouped or bundled by sub-basin serve to organize impact analysis in other areas such as soil disturbance, population and traffic changes, and floodplain/storm surge to name a few. Cumulative impacts, as defined in 40 CFR 1508.7, can also be more readily identified when examining a broader area and a larger timeframe for potential impact. Cumulative impacts or effects are the impact on the environment which results from the incremental impact of an action when added to other past, present, and reasonably foreseeable future actions regardless of what agency or person undertakes such other actions.

In using the ecosystem and cumulative impact approach, this EA addresses a *selected* group of bundled projects currently listed in the CIP that are projected to begin construction within the timeframe of fiscal years (FY) 05 through FY 11. In addition to limiting projects addressed in this EA to this timeframe, CIP projects were also incorporated into or excluded from the EA as follows:

Projects obviously eligible for existing Air Force-approved CATEXs were eliminated. These included projects strictly involving interior renovations and minor exterior changes such as re-roofing, painting and other exterior finish changes, repaving of existing paved areas, and similar actions. Many SRM projects fall into these categories since, by definition, most SRM-funded

- projects are smaller and more limited in scope.
- Projects entirely funded or partially funded by tenant organizations are discussed in this EA. Typically, these are known as NAF projects and include such projects as the addition to the Youth Center and construction of a Consolidated Club. However, all such projects will need separate NEPA documentation through their respective proponent organizations, even though they are consequently being preliminarily analyzed here.
- Demolition projects are listed in the EA and are shown, as needed, on site maps for individual future construction projects. Since demolition project impacts are generally limited to disposal or reuse of structural wastes, demolition projects are not individually analyzed in this EA. However, they are analyzed in terms of the net change in impervious surface area within individual sub-basins. Demolition projects for each alternative are included for reference in Tables 4 and 5 in Section 3.0.
- Future projects that would obviously require very extensive regulatory agency coordination, complex permitting requirements, extensive mitigation, and possible evaluation through development of an EIS. The proposed Marina Basin Expansion along Santa Rosa Sound was one such project, which is not addressed in this EA. Projects such as these will require individual NEPA analysis.
- Projects programmed through MILCON and larger SRM projects make up the bulk of the bundled projects addressed in this EA (see Tables 2 and 3, Figures 5 and 6, and Appendix B).

Although the timeframe for the projects addressed in this EA is focused on FY 05 through FY 11, projects currently programmed for FY 12 as well as several other out-year projects are also included since there is a high probability that the priority of some of these projects may change resulting in moving them into the five FY range primarily addressed as part of the action alternatives analyses.

	Table 2
ETEV.	List of Projects Addressed by Fiscal Year
FTEV#	Description
FY 04 Project 01-1070	
01-1070	Alter Refueling Fill Stand, Building 90132 Special Tactics Advanced Skills Training Facility
FY 05 Project	
97-1001	5
00-1085	Community Activity Center
00-1083	MEI-AFLD Waiver, Repair Storm Drainage
02-1029	Sside East Lift Station
03-1148	ADAL 16 CMS Facility, Building 90034
03-1152	Construct Parking Lot for Fitness Center, Building 90517
03-1183	Construct 16 OSS/OSTO Facility
04-1005	Troop Camp Facility
04-1011	Construct Parachute Tower 16th EMS 90743
04-1079	AT/FP Construct Overwatch Tower, East Gate
04-1019	ADAL Command Post, SRC Collocation
04-1117	Add to HQ AFCOS/SE, Building 90382
FY 06 Project	
96-2010	Realign O'Neil Avenue
99-3031	C2 Exercise/Group Headquarters Complex
02-3011	Mission Planning Center
02-3016	ACC Weapons Instructor Course Facility
03-1049	Fill/Clear Wetlands, Helicopter Landing Pad
04-1072	Add to Fitness Center, Building 90517
FY 07 Project	
94-3001	ADAL Security Forces Operations (Current Mission)
97-3006	SOF Engine Maintenance and Storage Shop
97-3018	Fire Crash/Rescue Station
00-3009	Vehicle Maintenance Facility
01-3021	25th Intelligence Squadron Operations Facility
02-3010	Addition to Transient Personnel Quarters
03-3014	Realign Cruz Avenue
03-3022	Main Gate and Soundside Access Control Facilities
04-3005 FY 08 Project	SOF Squadron Opst Tallon II
99-3029	AFC2TIG Systems/Warrior School Complex
02-3005	RED HORSE Mobility and Training Facility (823 RHS)
02-3003	Joint Special Operations University/USAF Special Operations School Facility
03-3013	Widen Independence Road
04-3006	SOF Weapons & Release Systems Shop
FY 09 Project	
97-3016	Hydrant Fueling System
02-3007	RED HORSE Outdoor Training Area
03-3004	Vehicle Operations/Maintenance Facility
03-3006	Visiting Officers Quarters
03-3017	STG Headquarters Facility
04-3004	SOF C-130 Aircraft Apron
04-3007	SOF Survival Equipment Shop
FY 10 Project	
97-3019	Airmen Leadership School
03-3016	Visiting Airman Quarters
04-3000	Refueling Vehicle Maintenance
04-3008	SOF Dash-21 Maintenance Facility
04-3009	SOF Maintenance Storage
04-3016	Base Supply Facility, 16 LRS
FY 11 Project 99-3036	
03-3021	Child Development Center 16th Contracting Squadron Facility
03-3021	SOF C-130 Talon II Maintenance Facility
04-3010	301 C-130 Taloff II Maifflenance Facility

Table 2 List of Projects Addressed by Fiscal Year				
FTEV #	Description			
FY XX Project	ts .			
96-3008	ADAL Maintenance Operations Squadron Facility			
96-3012	Squadron Operations Facility			
97-3009	Operations Group/Operations Support Facility			
97-3020	Operations Load Master Training Facility (C-130 HULK)			
99-3011	Base Roadway Improvements			
99-3013	Construct Dormitory			
99-3033	Squadron Operations Facility, 6SOS			
00-3001	Munitions Delivery Road			
00-3023	Eastside Fitness Center			
02-3014	SOF JSOU Headquarters Facility			
02-3015	SOF JSOU Library/Education Center Com/Language Lab PH 3			
03-3015	Realign Cruz Avenue Phase 2			
03-3018	AFLD Waiver, Alter Independence Road			
04-3011	SOF UAV Squadron Operations Facility			
04-3012	SOF UAV Maintenance Hangar/parking Apron			
04-3014	SOF CV-22 Aircraft Parking Apron			

	Table 3 Environmental Assessment Projects, 2005							
		Environme	ntai Assessr Total	nent Proje	ects, 20	JUS		
Project	FTEV #	Project Name	Project SF	Sub- Basin	FY	Description of the Project		
02-01	02-1001	Construct Outdoor Recreation Center, 16 SVS	21,015.9	2	10	The current facility is substandard - indoor office and storage space needed, classroom space needed, outdoor storage yard needed to meet expanding demands of a larger installation population.		
04-01	04-1072	Add to Fitness Center, Building 90517	1,003.0	4	6	The current facility is inadequately sized to serve assigned personnel as well as students attending various training schools on the installation.		
04-02	95-3013	Temporary Lodging Facility	80,645.2	4	10	The number of units currently available (24) is inadequate to accommodate inprocessing and out-processing families. Off-installation facilities have limited availability (particularly during tourist seasons or as a result of hurricane damage to local houses), are expensive, and are not conveniently located close to the installation.		
04-03	04-3016	Supply Warehouse	379,995.7	4	10	The current facility is antiquated and undersized to support expanding mission requirements.		
04-04	99-3036	Child Development Center	42,603.8	4	11	Capacity of the existing facility is 172 children while there is a need based on population to accommodate 400 children. There are HVAC, moisture, plumbing and mold problems in the existing facility		
04-05	03-3021	16th Contracting Squadron Facility	32,644.2	4	11	The current facility is over 40 years old, is inadequately sized, and poorly configured for efficient operations.		
04-06	97-3019	Airmen Leadership School	70,614.7	4	11	The existing facility is a modified 1950s church facility, which is inadequately sized, poorly configured, and costly to maintain		
04-07	02-3015	SOF JSOU Library/Education Center Com/Language Lab PH 3	129,149.5	4	12	This facility is needed to support the expanding training requirements for Special Operations Forces and, particularly, to support the development of distance learning course modules.		
05-01	03-3020	Soundside Visiting Quarters (120 pn)	105,296.3	4&5	6	There is an average of over 150 transient (temporarily assigned) personnel per night requiring lodging on or near Hurlburt. Training classes, exercises, and meetings associated with HQ AFSOC activities result in high numbers of visitors. Off-installation lodging is seasonally limited.		
06-01	01-5007	Consolidated Club	96,138.4	6	6	The NCO and Officer's Clubs are currently 3/4 mile apart, both are in older buildings, and neither have adequate dining/meeting space forcing many functions to find space in the surrounding civilian community.		
06-02	02-3011	Mission Planning Center	94,233.4	6	7	There is no current facility on the installation available for high level meetings and briefings with large numbers of senior staff. Existing nearby civilian facilities area inadequate from the standpoints of both security and force protection.		

		Environme	Table ental Assessr		ects, 20	005
Project	FTEV		Total Project	Sub-		
# 07-01	# 04-3020	Project Name ADAL Command Post	SF 5,975.1	Basin 7	FY 5	Description of the Project The current facility is inadequately designed to withstand Category 4 Hurricane winds and is inadequately sized to support additional operations. The inadequacy of the existing facility resulted in the forced relocation of the Wing Commander and key staff during Hurricane Ivan in 2004 into four separate facilities adversely impacting the Command's ability to direct recovery efforts and respond to crisis situations.
07-02	96-2010	Realign O'Neil Avenue/ Install Traffic Signal	26,348.4	7	6	This project will improve safety at the intersection of Terry Avenue and Independence Road will include providing a left turn lane onto Independence, improve the intersection geometrics, and install a traffic signal.
07-03	03-3022	AT/FP Main Gate and Soundside Access Control Facilities	246,468.0	7	7	This project is needed to meet the demands of vehicular control and inspection while also ensuring efficient flow of traffic at busiest installation intersection. Increased numbers of personnel associated with expanding C-130 mission creating additional traffic. Current gate configuration can handle a maximum of 14,000 vehicle per hour, projected need is to handle 16,000 vehicles per hour.
07-04	04-5003	Family Camping Facility	67,336.9	7	8	The project would double the current 24 full-service sites at Hurlburt. This responds to the heavy seasonal demand for RV sites along the Gulf Coast and a significant source of NAF income.
07-05	04-3006	SOF Weapons & Release Systems Shop	28,733.1	7	8	The expanding SOF mission at Hurlburt requires and expansion or replacement of the existing facility
07-06	03-3017	STG Headquarters Facility	125,569.0	7	9	The 720th STG mission has expanded accompanied by an increase in staff. Current facility is a converted former clinic, limited vehicular access and no secure conference area
07-07	04-3000	Refueling Vehicle Maintenance Facility	6,296.0	7	10	The existing facility is over 40 years old and inadequate for existing and projected mission requirements. Refueling vehicles cannot be maintained in other maintenance facilities because of the potential safety hazards.
07-08	03-3004	Vehicle Operations Administration Facility	8,110.5	7	10	This project would correct poor space utilization within the 16 Trans Squadron, which currently operates out of multiple ageing buildings and uses numerous storage buildings scattered on site interfering with administration of duties and efficient functioning.
07-09	96-3008	ADAL Maintenance Operations Squadron Facility	28,003.3	7	12	Current facility space is inadequate to support existing requirements for the command section and orderly room, maintenance operations, maintenance training, Logistics Group quality assurance and the base master technical order library.

	Table 3 Environmental Assessment Projects, 2005								
Duningt	FTEV	Litviiolille	Total	Sub-	JOIG, 20	-			
Project #	#	Project Name	Project SF	Basin	FY	Description of the Project			
07-10	99-3011	Base Roadway Improvements	114,205.3	7	12	Roadway improvements are needed to support greatly expanded SOF activities on Hurlburt. The original roadway system was designed in the 50s. Installation expansion east of the airfield is inadequately serviced by existing roadways and backups at Main Gate and East Gate creating unacceptable delays.			
07-11	99-3033	Squadron Operations Facility, 6SOS	18,716.3	7	12	There is a need for additional space for quality assurance and training operations, which are currently located in several separate buildings			
08-01	00-3009	Vehicle Maintenance Facility	32,496.3	8	7	Vehicle maintenance currently functions out of three buildings. Building infrastructure and life-safety problems are associated with the existing facilities. Work often must be performed outdoors on oversized equipment subjecting mechanics to weather extremes and creating difficult working conditions.			
08-02	02-3005	RED HORSE Mobility and Training Facility (823 RHS)	9,566.7	8	8	The current facility was built as a temporary facility in 1974. It is totally inadequate in size and condition to accommodate the necessary 400-person deployment operations. Space in a new facility is also needed for fitness training and as a hurricane shelter for first-responders.			
08-03	00-5004	Shoppette Facility	26,672.3	8	10	This new facility would provided needed services (including gasoline) on the east side of Hurlburt Field.			
08-04	99-3013	Construct Dormitory (144 pn) Eastside	98,880.3	8	12	Hurlburt has insufficient facilities to accommodate assigned single enlisted personnel. Off-installation accommodations are often too expensive for this segment of the military population. This project complies with the Air Force Dormitory Master Plan, and would provide needed quality of life improvements.			
08-05	00-3023	Eastside Fitness Center	76,114.4	8	12	Three new dormitories have been constructed on the east side of Hurlburt to accommodate the growing installation population, which is projected to increase by over 1600 military personnel in the next few years. The location of the current fitness facility is on the west side of the installation and is not large enough for the existing and projected future military population.			
08-06	03-3013	Widen Independence Road	42,307.2	8	12	The project would extend the four-lane improvements beyond the credit union/19 SOS intersection.			
08-07	03-3018	AFLD Waiver, Alter Independence Road	97,810.3	8	12	This project would realign the segment of Independence Road that currently intruding into the designated Primary Surface of the airfield.			
08-08	04-3011	SOF UAV Squadron Operations Facility	8,000.0	8	12	This project is required to support a new unmanned aerial vehicle mission scheduled for beddown at Hurlburt Field			
08-09	04-3012	SOF UAV Maintenance Hangar/Parking Apron	172,523.2	8	12	This project is required to support a new unmanned aerial vehicle mission scheduled for beddown at Hurlburt Field			

		Environme	Table ental Assessn		ects, 20	005
Project	FTEV		Total Project	Sub-		
# 11-01	# 04-5002	Project Name Construct Workbays at Auto Hobby Shop, Building 90612	SF 2,720.0	Basin 11	FY 5	Description of the Project The existing facility in inadequate in size to support the installation population. There are long waits for access to existing bays throughout the week and on weekends adversely impacting quality of life - especially for younger troops depending on the facility to help reduce the cost of auto maintenance.
11-02	03-1049	Fill/Clear Wetlands, Helicopter Landing Pad	130,079.0	11	6	This project would impact approximately 12 acres of forested wetland, but is permitted under a 10-year USACE permit 404 permit. The project is needed to accommodate increased helicopter activity on Hurlburt and in anticipation of the beddown of new CV-22 aircraft on the installation.
11-03	94-3001	ADAL Security Forces Operations (Current Mission)	4,698.8	11	7	The existing facility was constructed in 1979 with a capacity of 80 personnel. Post-9/11 permanently assigned personnel levels now exceed 220 not including Army National Guard augmentees. Expanded facility needs include additional space for administrative functions, guardmount and conference rooms lockers and showers, and holding cells.
11-04	97-3006	SOF Engine Maintenance and Storage Shop	96,929.5	11	7	The current facility was built in the 1950s and added to in the early 1990s. However, it is still vastly undersized to meet expanded mission requirements involving inspection, repair, maintenance, and storage of engines, propellers, stands, racks, and other equipment associated with Special Operations Forces aircraft.
11-05	97-3018	Fire Crash/Rescue Station	99,314.3	11	7	The existing wood frame facility was built in 1956 and is inadequate in size and configuration for the 72 assigned personnel and 16 pieces of major fire protection equipment. The HVAC systems within the existing facility are failing as is the concrete flooring. Additional C-130 aircraft are due to arrive in FY 07 requiring expanded fire crash/rescue support.
11-06	01-3021	25th Intelligence Squadron Operations Facility	42,532.6	11	7	Current operational efficiency is adversely impacted as a result of the 25th IOS operating out of three separate buildings - all of which are old, inadequately sized, and which have outmoded/degraded infrastructure. A new facility is needed to adequately meet mission requirements of providing combat aircrew threat assessments.
11-07	03-3014	Realign Cruz Avenue	34,149.6	11	7	The existing road is deteriorating from heavy traffic and poor storm water runoff. It is also too close to existing and planned facilities (beddown of additional C-130 aircraft in FY 09) to afford required force protection.
11-08	04-3005	SOF Squadron Opst Talon	41,790.7	11	7	Current facilities are inadequate to accommodate increases in mission and numbers of personnel projected over the next several years.

Table 3 Environmental Assessment Projects, 2005							
		Environnie	Total	lient Froje	;ci5, 2i	503	
Project #	FTEV #	Project Name	Project SF	Sub- Basin	FY	Description of the Project	
11-09	02-3010	Add to Visiting Quarters	4,592.7	11	8	A Needs Assessment Study conducted in 2003 identified a shortage of 187 adequate rooms to accommodate the numerous transient personnel visiting Hurlburt for training and mission rehearsal purposes. Normal occupancy rates of existing facilities is over 90 percent with surge requirements often resulting in approximately 150 persons per night using off-installation facilities.	
11-10	02-3013	ADAL USAFSOS Facility	36,691.8	11	9	This addition to the Joint Special Operations University building is needed to provide an energy-efficient building to house the command suite, academic office and seminar-styled conference rooms. Currently JSOU used a temporary building to house faculty and staff, and there is insufficient room to accommodate planned course expansion.	
11-11	04-3004	SOF C-130 Aircraft Apron	416,459.3	11	9	The project is required to provide additional parking for C-130 aircraft scheduled to arrive at Hurlburt within the next 5 years. Space is required for loading, unloading, servicing, and fueling.	
11-12	04-3007	SOF Survival Equipment Shop	15,516.0	11	9	The current facility is over 50 years old and too small to adequately support the mission of maintaining personnel parachutes and storage and maintaining of survival equipment such as flotation equipment, rubberized rafts, etc.	
11-13	97-3016	Hydrant Fueling System	47,807.3	11	10	Current fuel delivery to aircraft is limited to the use of refueling trucks (R-11 refueling units) and two flight line fill stands. Additionally, the bulk fuel storage system does not meet standards. Current slow turnaround associated with aircraft refueling will deteriorate further with the expected arrival of additional C-130 aircraft and the eventual deployment of CV-22 aircraft to Hurlburt Field.	
11-14	03-3006	Visiting Officers Quarters	10,913.3	11	10	The facility is needed to correct the severe shortage of adequate transient quarters for visiting officers and non-commissioned officers attending training courses, meetings, and exercises on Hurlburt.	
11-15	03-3015	Realign Cruz Avenue, Phase 2	57,457.5	11	10	The existing road is deteriorating from heavy traffic and poor storm water runoff. It is also too close to existing and planned facilities (beddown of additional C-130 aircraft in FY 09) to afford required force protection.	
11-16	04-3008	SOF Dash-21 Maintenance Facility	10,836.1	11	10	The existing facility is over 40 years old and is inadequate to support the mission of the 16th Special Operations Wing. The existing building is sited on the flight line and is in the way of construction of a much-needed new C-130 maintenance hangar.	
11-17	04-3009	SOF Maintenance Storage Facility	5,413.3	11	10	The existing facility is in the way of future construction of a needed C-130 hangar. There is a need to maintain adjacency between future aircraft maintenance operations and the maintenance storage facility.	

	Table 3 Environmental Assessment Projects, 2005							
Project	FTEV	LITVIIOIIIIle	Total Project	Sub-	613, ZI	000		
Project #	#	Project Name	SF	Basin	FY	Description of the Project		
11-18	04-3010	SOF C-130 Maintenance Hangar	72,332.8	11	11	There are presently only two maintenance hangars for C-130 on Hurlburt serving 31 aircraft. Additional hangar space will be needed to accommodate seven additional aircraft as part of a new mission beddown.		
11-19	96-3012	SOF Squadron Operations Facility, 18 Flts	49,380.6	11	12	The squadron currently operates out of three separate buildings as well as leased facilities off-installation. The existing condition causes delays in test planning and test execution reducing operational availability of Special Operations Forces aircraft. There is also a need for environmentally controlled storage space for sensitive electronic equipment currently exposed to ambient humidity levels resulting in equipment deterioration.		
11-20	97-3009	Operations Group/Operations Support Facility	59,767.8	11	12	There is a need to consolidate and modernize existing facilities currently spread out in four separate building throughout the installation.		
11-21	02-3014	SOF JSOU Headquarters Facility Phase II	135,223.7	11	12	New headquarters needed to provide administrative and classroom spaces to accommodate expanded training mission		
11-22	04-3014	SOF CV-22 Aircraft Parking Apron	129,223.4	11	12	This project is required to support the new CV-22 Osprey aircraft scheduled for beddown at Hurlburt Field replacing the MH53J Pave Low helicopters currently used by Special Operations Forces.		

This EA is not a programmatic document. All projects detailed in this EA are addressed at a level sufficient to allow them to proceed to funding and construction without additional NEPA documentation. This approach is possible given Hurlburt Field's planning foundation developed over the past decade and the installation's close coordination with regulatory agencies and local governmental entities on a routine basis.

Extensive documentation has been developed for such environmental constraints as jurisdictional wetlands (both federal and state): rare, threatened, and endangered species habitat; storm surge and floodplain boundaries; contamination areas under the Installation Restoration Program (IRP); noise contours associated with AICUZ; and groundwater usage. The location, nature, and extent of environmental and operational constraints have been incorporated into the Hurlburt Field Geographic Information System (GIS) and are available on a site-specific basis as shown later in this EA and its appendices. These constraints have, for the most part, been avoided during the preliminary siting process. Existing agency agreements such as Hurlburt Field's 10-year wetland permit, various Land Use Controls (LUC), and regional groundwater withdrawal agreements will be discussed throughout the environmental analysis, and these agreements will continue to be honored as previously agreed to with the respective agencies.


The approach to bundling of a number of future projects provides a distinct advantage when addressing cumulative impacts. This is particularly true in the areas of storm water runoff (quantification of net changes in sub-basin impervious surfaces), total wetland impacts from area development, potable, and non-potable water demand changes, infrastructure requirements, and traffic pattern and congestion changes.

1.5 GIS COMPONENT TO THE EA ANALYSIS

Hurlburt Field is able to meet its NEPA requirements as detailed in AFI 32-7061 most efficiently by using up-to-date GIS site information on environmental and operational opportunities and constraints. The approach changes traditional environmental analysis

methodologies of "predict, mitigate, and implement" by adding two additional components—monitor and adapt. This will allow environmental professionals at Hurlburt Field the ability to monitor the accuracy of impact predictions as time progresses and will allow flexibility to reduce impacts when needed.

This EA was prepared in conjunction with the development of an environmental GIS database for Hurlburt Field. Beginning with the individual future projects covered under SRM and MILCON funding sources, a GIS database of individual projects was developed and combined with existing environmental data for Hurlburt Field such as wetlands, rare species locations, floodplains, quantity/distance explosive safety arcs, and noise contours. After completion of the base mapping process, GIS analysis tools were used to determine, where possible, quantifiable environmental impacts resulting in a detailed map for each project. For the purposes of analysis, the installation was divided into 11 previously identified storm water sub-basin areas (Figure 4). The cumulative impacts of proposed General Plan projects in each storm water sub-basin were determined and then combined with an end result of a base-wide environmental analysis. Using GIS technologies, both the individual and cumulative environmental impacts of many projects were able to be examined. In addition, the initial GIS database can be altered and expanded providing the staff at Hurlburt Field with a living database that can aid in future environmental analysis. A complete list of MILCON and SRM projects addressed and analyzed in this EA is provided in Tables 2 and 3 and Figure 4.





ECTION 2.0
AND NEED

Hurlburt Field (16th SOW) and HQ AFSOC propose to seek funding and construct the CIP projects listed in Table 2 as part of implementation of the Hurlburt Field General Plan (Woolpert, Inc., 2002). As the primary HQ AFSOC installation in the U.S. with highly dynamic and rapidly changing mission requirements, it is essential that Hurlburt have an up-do-date and environmentally sound and documented General Plan reflecting known and projected future facility and infrastructure requirements. These requirements are driven both by evolving mission changes and the need to improve and maintain facilities supporting the existing mission requirements at Hurlburt. General and specific needs or findings identified within the General Plan include the following.

2.1 UTILITIES

- Growth on the east side of the base has increased demand for all utility systems
- Electrical distribution on the east side of the base is hindered by the two feeders supplying power to this side of the base. The current load cannot be equally divided between the two feeders.

2.2 LAND USE

 The base has very little expansion capability due to the existing built environment as well as environmental and operational constraints.

- Direct roadway access from the east to the west sides of the base is limited and contributes to transportation problems.
- Continued development of the east side rotary wing operations area, the Permanent Exercise area, and the Community Center will create the need for supporting uses such as dining, fitness and dormitory facilities.
- Changes in AFSOC missions, including the planned acquisition of the CV-22 aircraft, will place additional demands on developable land and require informed land use decisions.
- Space is limited for the development of aircraft operations and maintenance uses along the existing flight line area.
- Growth of AFSOC and Hurlburt Field, in conjunction with changes in Air Force standards, will place additional demand on both accompanied and unaccompanied housing. Expansion opportunities need to be identified so that Hurlburt can meet existing demand and the needs that additional growth will generate.
- Need to improve the relationship between accompanied housing and community commercial and outdoor recreational uses.
- Need to minimize the conflict between administration and aircraft operations and maintenance activities.

 Availability of medical services to unaccompanied housing areas should be improved.

2.3 Transportation

- There is insufficient quantity/capacity at entry gates to provide adequate access to Hurlburt Field for both military personnel and civilians.
- The intersections of major routes that feed Hurlburt Field must be able to accommodate entering and exiting traffic volumes.
- Traffic flow patterns must be smooth and efficient to minimize vehicle delay throughout the installation.
- Pavement and sidewalk conditions must be maintained and improved where necessary.
- Parking must be sufficient to accommodate current and future personnel.

2.4 Capital Improvements

- There is base wide potential to consolidate organizations and eliminate outdated structures in an effort to create development parcels.
- There is potential to relocate several uses on the west side of the base to more remote locations to reduce congestion.
- The relocation of several small storage facilities along the west side flight line will open up prime flight line development space.
- The possible relocation of Cruz Avenue to the west will provide space for increased parking in the west side flight line area.
- The reconfiguration of the base supply/open storage yard may create additional space for industrial-related uses needed to support the flying mission.
- There is room for the expansion of the west side apron north of the Commando hangar after several aircraft ground equipment (AGE) facilities are relocated.

- The possibility of building multi-story facilities base-wide exists; thus, reducing building footprints and leaving space for additional parking.
- Space for the development of additional modern dormitories exists after the removal of Buildings 90322, 90323, 90329, 90330, 90334, 90343, and 90349. Space was recently created by the removal of Buildings 90344 and 90350.
- There is an opportunity to further develop the "office park" in the Industrial Core Area south of Hartson Street.

Without an up-to-date General Plan to guide development, identify potential facilities sites, and set priorities; Hurlburt risks losing its ability to meet mission requirements in a timely, economical, and efficient manner. Furthermore, without adequate, quickly available NEPA documentation, individual project funding can be jeopardized even if the project is part of General Plan implementation.

Justification for each individual project addressed in this EA is provided in project-specific DD Forms 1391 (Appendix C) as well as listed in Table 3. These sources are on file and available from the16th Civil Engineering Squadron (CES) and they can be consulted if necessary. A brief description excerpted from 1391s for each project by sub-basin (when available) is provided in the Table 3.



3.1 ALTERNATIVE 1 (IMPLEMENTATION OF BUNDLED FIVE-YEAR CIP PROJECTS)—PREFERRED ALTERNATIVE

This alternative would involve selecting the CIP projects programmed for funding and construction over FYs 05 to 11 that would require an EA-level of analysis, analyzing them as one action, and completing a single decision document (FONSI) (see Table 2 for a list of projects and Figure 5). As discussed in Section 1.0, the selection of the projects to include or exclude for analysis in this EA as part of Alternative 1 was based on the following rationale:

- Most of the projects addressed in Alternative 1 are programmed through MILCON or are larger SRM projects.
- Projects obviously eligible for existing Air Force-approved CATEXs are not included for analysis under this alternative.
- Demolition projects are discussed primarily in terms of their relationship to construction projects such as making room for new projects or increasing open space land use. A major example of this would be the planned demolition of 306 units of single family military housing in the Pine Shadows

and Live Oak Terrace areas on the western portion of the base north of US 98. This action, which is part of a larger military family housing privatization program, is discussed in terms of the substantial land use change associated with it. Total square footage associated with all programmed demolitions is also used in determining rough approximations of net changes in impervious surface areas by sub-basin. Demolition projects are included for reference in Table 4.

Future projects that would obviously require very extensive regulatory agency coordination, complex permitting requirements, extensive mitigation, and possible evaluation through development of an EIS. The proposed Marina Basin Expansion along Santa Rosa Sound was one such project, which is not addressed in this EA. As a result, the Marina Basin Expansion project will require individual NEPA analysis. Other possible future programs and projects falling into this category of extensive coordination and not covered in this EA also include plans for a Mission Rehearsal Isolation Area (MRIA) east of the airfield and the beddown of CV-22 (Osprey) aircraft. This latter program was documented in an earlier EA and FONSI, which now requires updating due to projected changes in the beddown (AFCEE, 2001).

Demolitions scheduled as part of Alternative 1 are shown in Table 4.

Table 4				
Demolitions	by Sub-Basin for I	Alternative 1		
	# of	Total Area (SF)		
Sub-Basin	Demolitions	of Demolitions		
1	0	0		
2	45	178,096		
3	0	0		
4 and 5	138	596,214		
6	4	20,015		
7	19	114,245		
8	9	44,293		
9	2	1,687		
10	1	2,387		
11	40	238,719		

3.2 ALTERNATIVE 2 (SITING AND/OR DESIGN OF CIP PROJECTS IN ALTERNATIVE INSTALLATION LOCATIONS)

This alternative would involve constructing and/or designing all of the same CIP projects included in Alternative 1 (Preferred Alternative) but at alternative sites on Hurlburt or using alternative designs at sites adjacent to or nearby the preferred site (Figure 6). The same approach to incorporating build or demolition projects and the same exclusions regarding future highly complex projects with potential regulatory difficulties applies to this alternative as to Alternative 1.

Demolitions associated with Alternative 2 are shown in Table 5.

Table 5 Demolitions by Sub-Basin for Alternative 2					
Sub-Basin	# of Demolitions	Total Area (SF) of Demolitions			
1	0	0			
2	43	171,063			
3	0	0			
4 and 5	121	527,244			
6	0	0			
7	4	161,231			
8	2	53,445.1			
9	0	0			
10	0	0			
11	11	39,948.8			

3.3 No-Action Alternative

The No-Action alternative would not construct any of the projects detailed in the Hurlburt Field General Plan or LRFDP. Existing facilities would continue to be used and the only improvements would be related to general maintenance and upkeep. Any new missions that are expected to come on-line at Hurlburt would be required to find space within existing facilities.

Independently funded projects would likely continue to be constructed and these may require an EA-level of environmental analysis. These types of projects would be addressed individually and, in some cases, possibly tiered from other existing EAs. Planned or programmed demolitions would also likely take place; however, the amount of demolitions would be less than either Alternatives 1 or 2, as any demolitions associated with this alternative would not be tied to any future construction.


3.4 ALTERNATIVE INITIALLY CONSIDERED BUT DISMISSED


3.4.1 Bundled Environmental Analysis of All CIP Projects

This alternative would address all CIP projects extending out 20 years and requiring an EAlevel of environmental documentation in one EA document. Extending the analysis beyond even five years becomes impractical due to the difficulty in predicting Hurlburt Field's future mission requirements. As mentioned previously, Air Force Special Operation missions are dynamic and can change focus rapidly in response to changing threats, national defense policies, new technologies, etc. Also, the regulatory environment involving a variety of issue or resource areas is another source of uncertainty in impact analysis. Laws and regulations related to wetlands, floodplains, and storm surge areas, threatened and endangered species, and other areas may change substantially over a 5-year period.

This approach is also procedurally not permissible if following accepted good practices in the development of NEPA documents.

According to the CEQ Forty Most Asked Questions Concerning CEQ's NEPA Regulations (Question #32), environmental documentation of on-going programs (such as General Plan implementation) should be reevaluated every five years to determine the





need for a supplement per the requirements of 40 CFR 1509.

As a result of both the practical and procedural problems associated with attempting to develop a NEPA document analyzing the alternative of including all CIP projects out to 20 years was dismissed and will not be analyzed in this EA.

3.5 RESOURCE/ISSUE AREAS NOT ANALYZED

3.5.1 Topography, Geology, and Soils

Elevations range from sea level to approximately 40 feet above mean sea level, and slopes range from 0 to 8 percent. Hurlburt Field soils are sandy, have low fertility and generally high permeability. Depth to bedrock is approximately 500 to 600 feet below the surface at the depth of the Floridan aguifer. There is no karst formation in the Hurlburt area and, therefore, no sinkhole risk. The installation is also in a historically stable seismic area. Overall, the topography, geology, and soils of the Hurlburt area do not impose any unusual constraints to construction nor would the proposed action be expected to have any substantial impact on these resource areas. Also, most of the proposed projects addressed in this EA are within the existing developed area of the installation, in the vicinity of existing structures, and would have building footprints similar to surrounding structures. Therefore, these areas will not be analyzed in this document.

3.5.2 Estuarine Resources

Santa Rosa Sound, which borders the Soundside area of Hurlburt, is known for its lush seagrass beds, beautiful beaches, and value as a marine life nursery as well as its importance as part of the Intercoastal Waterway. East Bay is a Class II water area, which allows oyster harvesting. These estuarine resources are directly and indirectly impacted by land use decisions made on Hurlburt.

Hurlburt Field includes approximately three miles of coastal area bordering Santa Rosa Sound, the southern boundary of the installation. The waters of the sound are considered estuarine, including both salt and brackish waters. Four small estuarine wetland areas

totaling 4.3 acres border Santa Rosa Sound within installation boundaries (Woolpert, Inc., 2001). These estuarine wetlands were created by Hurlburt as part of mitigation for wetland impacts under Section 404 Permit Number 199900679. These created wetlands were planted in native saltmarsh cordgrasses, which contribute to the high value that the Sound provides for biological communities in the region. In addition, there are three salt marshes that total 9 acres. They were created under a separate set of permits, two state permits and two federal permits. However, since all impacts to the surrounding estuarine receiving waters are indirect and can be adequately analyzed by examining proposed action impacts on areas such as storm water, floodplains, and wetlands; this resource area will not be addressed in this EA.

3.5.3 Land Use

Land use planning is the foundation of General Plan development and sets the stage for future facility siting and improvements in installation operational efficiency. Therefore, land use issues have already been addressed for each project as part of the General Plan development processes and will not be readdressed in this EA (Woolpert, Inc., 2002).

3.5.4 Historical Resources

A historic building survey has recently been completed for all structures at Hurlburt Field (MWH Americas, Inc, 2004). No structures were found eligible for listing on the National Register of Historic Places. Therefore, historic resources will not be analyzed in this EA

3.5.5 Aircraft Operations

Aircraft operations are not analyzed in this document as the proposed action is concerned with land-based facilities which may or may not be directly related to aircraft operations. Land use and facility changes are influenced by flying mission requirements, but do not, themselves, directly influence the flying mission. Therefore, changes in aircraft operations will not be analyzed in this EA.

3.5.6 Safety and Occupational Health

Safety and occupational health issues are not analyzed in this document as the proposed action is not expected to raise new concerns, except perhaps minor and temporary concerns during the construction phase.

3.5.7 Permitting Issues

Permitting issues are critical for all future actions on the installation, and will require coordination through various regulatory agencies for compliance with applicable regulations. This coordination will have to take place on an individual project basis as facility design becomes more detailed. Mitigation actions required as part of any future permitting will also need to be developed, negotiated, and implemented on an individual project basis. Among the more significant permitting issues are those relating to storm water discharge, wastewater discharge, and wetland impacts. These issues are addressed as appropriate under other resource/issue areas analyzed in Section 5.0.



Topics evaluated in this section and subsequently analyzed in Section 5.0 were selected based on their relevance as indicated by on-site visits, secondary source documents, regulatory agency input, and information from Hurlburt personnel. Figure 7 displays a graphic of the natural resources and Figure 8 displays operational resources at Hurlburt Field.

4.1 GROUNDWATER

Hurlburt Field is underlain by a surficial Sandand-Gravel aguifer, which includes the Citronelle Formation and the Floridan aquifer of interbedded limestones and dolomite, which is approximately 500 to 600 feet below the surface. The main potable water supply source at Hurlburt, and all surrounding communities is the upper Floridan aquifer, which averages more than 1,000 feet in thickness and produces well yields from several hundred to over 10,000 gallons per minute (gpm). With the rapid rate of regional population growth and accompanying water demand, the Floridan aquifer has lowered 90 feet as a result of extensive pumping in the region. Should this trend continue, increases in saltwater intrusions and decreases in water storage along Santa Rosa Sound are possible (Woolpert, Inc., 2001). Ensuring the long-term sustainability of the Floridan aquifer has become an important regional planning issue requiring cooperation in water conservation among all users of the aquifer. The rapidly developing region of Santa Rosa, Okaloosa, and Walton Counties is designated by the Northwest Florida Water Management District (NFWMD) as a Water Resource Caution Area because of concerns about salt water intrusion, groundwater depletion, and potential contamination.

The potable water system at Hurlburt is permitted and regulated through the Florida Department of Environmental Protection (FDEP), under the authority of Chapter 403, Part IV, Florida Statutes. FDEP also monitors and regulates drinking water standards under the authority of Chapter 62,550. Florida Administrative Code. A number of facilities and all family housing units use potable water from the Floridan aguifer for lawn watering and irrigation. Hurlburt currently has five potable water wells in operation that have a total production capacity of 2,100 gpm, or 3.03 million gallons per day (gpd). Hurlburt Field's Consumptive Water Use Permit, allows a maximum groundwater withdrawal rate from the Floridan Aquifer of 1.390 million gallons per day. Hurlburt developed a water management plan in 2001 to eliminate the use of water from the Floridan aguifer for landscape irrigation and other non-potable uses. For example, the Gator Lakes Golf Course uses surface water from Hurlburt Lake for irrigation. Also, in a regional cooperative effort to reduce reliance on the Floridan aquifer for non-potable use, treated wastewater from the Hurlburt wastewater treatment plant is piped to the City of Fort Walton Beach for industrial use.

The shallow Sand-and-Gravel aquifer in the Hurlburt vicinity ranges in thickness from about 150 feet in the east to some 200 feet near the center of the installation. Yields of more than 300 gpm are possible in the main producing zone just southeast of Hurlburt Field (Woolpert, Inc., 2001). Many individual facilities on Hurlburt have irrigation wells that draw water from the shallow Sand-and-Gravel aquifer.

4.2 SURFACE WATER AND STORM WATER

Hurlburt Field has 11 storm water sub-basins and 10 outfall structures (see Figure 4) (MWHA. 2002). Drainage Basin 11 is by far the largest and roughly encompasses the northern half of the installation—emptying into East Bay Swamp and East Bay River flowing west into East Bay. Drainage Basin 10 includes Commando Village where surface waters drain southward offinstallation, as well as the northern half of the eastern base perimeter where surface waters flow eastward, eventually into Cinco Bayou. The remaining nine drainage basins largely take surface water flow southward into Santa Rosa Sound. In addition to natural drainage patterns there are man-made drainage ditches that flow into wetlands and other natural surface waters to the north and south. Potential changes in quantity and quality of storm water runoff from the developed areas of Hurlburt have important implications for the protection of sensitive estuarine and freshwater receiving waters.

Hurlburt has an up-to-date Storm Water Pollution Prevention Plan (SWPPP) developed in accordance with Air Force Instruction 32-7014, Water Quality Compliance, and in compliance with the National Pollutant Discharge Elimination System Storm Water Permit issued by the USEPA. The SWPPP identifies all industrial and potential sources of non-point source pollutants occurring within the 11 distinct drainage sub-basins on Hurlburt Field (Figure 4). Section 319 of the Clean Water Act requires the use of best management practices (BMPs) to prevent storm water pollution from industrial operations as well as from construction sites and from grounds maintenance. BMPs associated with grounds maintenance include percolation trenches, vegetated retention/ detention basins, natural mulches, geosynthetics, and other measures as necessary, to reduce non-point source pollution. In addition, slow-release fertilizers are to be used when possible to reduce nutrient release into run-off from improved grounds.

Storm water runoff is controlled through a combination of man-made and natural structures including drainage ditches, five regional storm water retention ponds, and wetlands (refer to Section 4.5: Wetlands). Drainage ditches are used throughout Hurlburt to channel storm water

into the retention and detention ponds. The three ponds located south of US 98 are the Southwest, South Central, and Southeast Regional Storm Water Ponds. The other two are located south of Independence Road (East Regional Storm Water Pond) and on the south side of Loop Road, south of the commissary (Loop Road Regional Storm Water Pond). These retention and detention areas are not always filled with standing water; some are dry unless a storm event occurs. All of the regional ponds are equipped with automatic samplers at their outlets, and the East Regional Pond also has an automatic sampler in the inlet.

Surface water and storm water issues are analyzed with this EA in the context of storm water runoff changes expected by the proposed action. The 11 sub-basins are used as an organizing principle in the development of the EA with projects within a given storm water sub-basin analyzed together.

4.3 FLOODPLAINS

Numerous areas of Hurlburt Field are within the 100-year floodplain, as shown in Figure 7. A majority of the northeast and northwest portions of the installation is included in the floodplain associated with East Bay River and East Bay Swamp. Other small floodplain areas are scattered to the east and west of the airfield and also occur in a floodplain/storm surge fringe along Santa Rosa Sound (Woolpert, Inc., 2002). Many of the floodplain areas on Hurlburt Field correspond with documented wetland areas. This is due to the extensive swamps, marshes, ponds, and bayous that occur in and around Hurlburt Field. Per Executive Order 11988 (Floodplain Management), any floodplain development requires justification through development of a Finding of No Practicable Alternative signed by HQ AFSOC.

4.4 STORM SURGE AREAS

Storm surge areas are those regions that are subject to high water due to seawater blown inland during tropical storms and hurricanes. The portion of Hurlburt Field principally south of U.S. 98 and bordering Santa Rosa Sound occurs in such an area (Figure 7). Storm surge areas are determined from hurricane inundation zones and represent "worst case scenarios" (such as during high tide) (Table 6) as measured



Not to Scale

on the National Oceanic and Atmospheric Administration's Saffir Simpson Scale. According to the National Weather Service. Category 1 storms, with winds of 74-95 mph, occur on average once every 10 years. Category 2 storms, with winds of 96-110 mph. occur in the Hurlburt region with a frequency of once every 27 years. Category 3 storms, with winds of 111 to 130 mph, occur about once every 42 years on average. Category 4 storms, with winds of 131 to 155 mph, and Category 5 storms, with winds greater than 155 mph, have not occurred historically in the Hurlburt Field region (see Table 6). Each of these categories results in higher amounts of water coming ashore and flooding areas. As seen in Table 6, each storm surge category builds upon each other and results in greater flooding potential for facilities in those areas.

Table 6 Hurricane Storm Categories, Wind Speed, Storm Surges, and Frequencies in the Hurlburt Field Area					
Storm Category	Wind Speed	Storm Surge Elevations	Average Frequency		
1	74 to 95 mph	3.5 Feet	Once in 10 Years		
2	96 to 110 mph	5.0 Feet	Once in 27 Years		
3	111 to 130 mph	10.5 Feet	Once in 42 Years		
4	131 to 155 mph	15.5 Feet	No Historical Occurrence		
5	>155	17.5 Feet	No Historical Occurrence		
	ational Weather S ational Hurricane				

Two Category 3 hurricanes have made landfall near Hurlburt over the past ten years. In 1995, the eyewall of Hurricane Opal passed seven miles west of Hurlburt Field resulting in maximum sustained winds of 84 mph and gusts to 144 mph (National Hurricane Center, 2001). The storm surge elevation associated with Opal came up to about the 8.5 foot contour line. On September 16, 2004, Hurricane Ivan made landfall near Gulf Shores, AL as a strong Category 3 hurricane. Peak sustained winds at Hurlburt with this storm were 119 mph accompanied by a storm surge that ranged from 10.30 feet in Gulf Breeze, Florida to 6.12 feet at the Fort Walton Beach Brooks Bridge.

Categories 1 and 2 hurricanes will flood low coastal areas on Hurlburt south of US 98.
Categories 3, 4, and 5 hurricanes will impact low areas north of US 98 that are southeast of the flight line along with an area of housing and administrative buildings that are approximately 1,100 feet north of the highway (Woolpert, Inc.,

2002). From a human safety and a practical construction standpoint, Hurlburt adheres to general construction standards as defined in Florida's Coastal Protection Act when siting facilities within potential storm surge areas along Hurlburt Field's Santa Rosa Sound shoreline.

4.5 COASTAL ZONE MANAGEMENT (CZM)

The CZM Act of 1972 requires federal facilities to carry out their activities in a manner consistent with the state's coastal zone management program. The entire state of Florida is considered to be within the coastal zone, as regulated by the Florida Coastal Zone Protection Act of 1985 and administered by FDEP. As a result, the state has the authority to review federal actions for consistency with the Florida Coastal Management Program (FCMP). The FCMP consists of a network of 23 Florida Statutes administered by eleven state agencies and four of the five water management districts (see Table 8 in Section 5.2.3). Under Florida's program, permits are required for any erosion control devices, excavations, or erection of structures within the coastal construction control line (CCCL). This line extends landward from the shores along the Gulf of Mexico, excluding Choctawhatchee Bay, and its potential inland extent of erosion due to a 100-year storm. As Hurlburt Field borders Santa Rosa Sound, that portion of the mainland has no designated CCCL; however, county regulations require a 50- foot setback from the mean high water line for all new principal structures. Project information is submitted for review by a State Clearinghouse, which coordinates the review process. Consistency reviews of projects which require permits from the USACE, US Coast Guard, or require a State Environmental Resource Permit are conducted during the state permit review and must include an evaluation on the project based upon Florida's 23 statutes (see Table 8 in Section 5.2.3). Any CZM issues are discussed from a regional perspective in Section 5.2.3, and a draft of this EA will be submitted to the State of Florida for a consistency determination of the overall proposed action.

4.6 WETLANDS

Wetland areas are abundant throughout the installation and include swamps, cypress heads, marshes, ponds, and bayous. Around 3,400 acres of jurisdictional wetlands exist as listed under federal and/or state standards, comprising 52 percent of the land area on Hurlburt Field (Figure 7) (Woolpert, 1998). Air Force Instruction 32-7064 directs that all installations shall develop and maintain current inventories of wetlands in order to plan for long-term protection or mitigation. Federal regulations applicable to wetlands include Executive Order (EO) 11990 and Section 404 of the Clean Water Act.

Formal delineations of state and federal jurisdictional wetlands were conducted in 1995-97 and confirmed by the U.S. Army Corps of Engineers (USACE) Panama City office and the FDEP (Woolpert, 1998). The majority of wetland areas occurs within the northern half of the installation and is contiguous with East Bay Swamp. The most common wetland types within the installation include cypress-gum swamps/ cypress domes, shrub wetlands, and herbaceous wetlands. Within the installation, cypress-gum swamp habitat is most prevalent within the northern half of the installation, which borders East Bay Swamp. Herbaceous wetlands are generally infrequent and small (Woolpert, Inc., 2001). Wetland areas are the primary limiting factor to the expansion of Hurlburt facilities beyond currently developed areas.

Agreements and permits between Hurlburt, the State of Florida, and the USACE are currently in effect and must be honored in any future development planning. A Section 404 permit [Permit Number 199900679 (IP-DH), expiration date September 24, 2010] has been obtained from the USACE that includes all projects from the 10-year development plan and their associated wetlands impacts. Similarly, a wetland permit has been obtained from the Florida DEP that requires the preservation and enhancement of the majority of the installation's wetlands as mitigation for the permitted action (Woolpert, Inc., 2002). Most future developments will require new permitting from the USACE and FDEP. In this regard, the establishment of a wetlands mitigation bank (salt marsh as well as possible freshwater wetlands off of the installation) would facilitate any needed permitting for new construction on Hurlburt.

Some of the projects programmed within Alternative 1 and 2 include wetland areas that have already been permitted. The analysis for this EA will classify wetland impacts in terms of its permitted status (permitted or un-permitted) in addition to the amount of wetland being impacted.

4.7 FLORA AND FAUNA

The flora of Hurlburt is composed of a diverse number of species that have been extensively studied (Woolpert, Inc., 2002). While much of the plant diversity is concentrated in the western, undeveloped, areas of the installation, smaller pockets of native plant communities are also scattered throughout developed areas. The vegetation at Hurlburt Field within the unimproved areas consists of long-leaf pine flatwoods and cypress swamps. Turf and/or landscaped areas encompass 674 acres of improved and 834 acres of semi-improved grounds on the installation, including a 160-acre golf course (Woolpert, Inc., 2002). Additional plant communities within the installation include sandhill, cypress domes, sand pine scrub, maritime hammock, and some disturbed plant associations.

As off-installation development impacting natural communities continues, preservation of many of these communities within the boundaries of Hurlburt is of regional and, in some cases, national interest. Ecosystem restoration on Hurlburt is on-going and includes limited restoration of long-leaf pine habitat on the western portion of the installation. The restoration of a native long-leaf pine/wire grass community on Hurlburt is associated with a multi-year wetland permit, which must be honored throughout the planning process. In addition to planting long-leaf pines, management involves periodic controlled burning of restored and existing pine flatwoods, which helps control accumulation of a dense flammable understory and the spread of non-native and invasive species.

As with many areas of Florida, invasive plant species management is an important issue on Hurlburt, particularly in disturbed areas transitioning between developed and undeveloped areas. Non-native invasive plant species such as Chinese tallow tree (Sapium sebiferum) and cogon grass (Imperata

cylindrica) are most frequent in disturbed areas, but can reduce floral diversity (and wildlife diversity) in adjacent natural plant community areas as well. Dominant species of plants within the above-mentioned plant communities are described in the Hurlburt Field INRMP (Woolpert, Inc., 2001).

A variety of wildlife is found within Hurlburt Field. Fish species are found in Hurlburt Lake, several golf course ponds, the East Bay River, and in several large drainage ditches (Woolpert, Inc., 2002). Terrestrial vertebrate fauna that occur within the installation include many species of amphibians, reptiles, mammals, and birds (both resident and migrant). A master list of potential vertebrate fauna (terrestrial and aquatic) for the installation, with observed species noted, is provided in the INRMP (Woolpert, Inc., 2001).

4.8 RARE, THREATENED, AND ENDANGERED (RTE) SPECIES

A number of state RTE plant species occur on Hurlburt, with the greatest density of these species occurring on the wetland areas in the western portion of the installation (Woolpert, Inc., 2001). No federal endangered plant species have been located on the installation, though the former federal candidate white-top pitcherplant (*Sarracenia leucophylla*) is frequent in cypress domes and wet flatwoods across the base (Figure 7) (Woolpert, Inc., 2002).

Important habitat areas for threatened and endangered fauna are widespread on Hurlburt Field, as shown in Figure 7. The majority of critical fauna habitats are in the western portion of the installation and include pine flatwoods as well as cypress head wetlands. A total of 19 rare animal species have been discovered to date, though only three of five possible federal-listed animals have been historically reported within or adjacent to the installation—the flatwoods salamander, bald eagle, and red-cockaded woodpecker (see Table 7 and Figure 7).

The flatwoods salamander is a federal threatened species that breeds in flatwoods ephemeral wetlands during the fall. This amphibian was observed at seven locations during surveys west of the EOD area by the FNAI (FNAI, 1993, 1994a). Surveys in 1999 and

Table 7 Species of Federal-Listed Animals Possible at Hurlburt Field				
Scientific Name	Common Name	Federal Status		
Ambystoma cingulatum	Flatwoods Salamander	Threatened		
Drymarchon corais couperi	Eastern Indigo Snake	Threatened		
Charadrius Melodus	Piping Plover	Threatened		
Haliaeetus leucocephalus	Bald Eagle	Threatened		
Picoides Borealis	Red-Cockaded Woodpecker	Endangered		
Sources: Labat-Anderson, Inc., 1994. Florida Fish and Wildlife Conservation Commission, 1997.				

in 2000 further determined that 12 additional wetlands have the potential as breeding sites

(Printiss and Hipes, 2000). However, salamanders have not yet been found in these wetlands. Because of weather conditions not conducive to salamander breeding in the fall of 1999 and of 2000, surveys are continuing. The salamander will be assumed to occur in all potential breeding sites until proven otherwise.

Two former gopher tortoise populations on Hurlburt reported by Printiss and Hipes (1997) no longer exist. The small, isolated population in the southwestern section of the installation apparently died out or migrated out of the area. Tortoises from the isolated population east of Loop Road were relocated into a larger population within Eglin AFB. Without gopher tortoise burrow habitat, the federal threatened indigo snake is also not expected to be found on Hurlburt Field.

The piping plover is a federal threatened shorebird that winters along the Gulf Coast on sandy beaches and tidal mudflats (AOU, 1998). Very marginal habitat is available along the installation's southern edge (such as bordering Santa Rosa Sound) and there were no observations of the species by any survey.

The bald eagle is a federal threatened bird that breeds within coastal marshes and adjacent to large rivers and lakes (Printiss and Hipes, 1997) where large isolated trees provide nest sites. While bald eagles are occasionally observed flying over the installation, they have not yet been found breeding within its boundaries.

There has been no red-cockaded woodpecker (RCW) nesting activity on Hurlburt for at least 10 years and no active RCW cavity trees found in over 15 years. Although a few scattered former cavity trees still exist in the vicinity of Commando Village and the Permanent Exercise Facility, the USFWS has indicated that no additional consultation under Section 7 of the Endangered Species Act is needed prior to conducting activities or undertaking construction in these former RCW areas.

State-listed or rare species of vertebrate fauna that were documented during surveys include Bachman's sparrow (Aimophila aestivalis), great egret (Ardea alba), reddish egret (Egrette rufescens), coal skink (Eumeces anthracinus), gopher tortoise, osprey (Pandion haliaetus), brown pelican (Pelecanus occidentalis), and least tern (Sterna antillarum) (USAF, 1996; Printiss and Hipes, 1997). A survey across the installation for rare invertebrates was conducted by Flowers in 1997 and again in 2002. Eight species of rare insects were documented, which include two caddisflies, three beetles, one dragonfly, one grasshopper, and one fly.

4.9 ARCHAEOLOGICAL RESOURCES

Past surveys have revealed few prehistoric and historic sites on Hurlburt Field. In 1994 the USACE conducted a survey at Hurlburt Field for archeological resources and produced an archeological sensitivity map based upon areas of high and low probability of finding resources. An area designated as a high probability area typically included locations within 200 miles of potable water and situated no more than 50 feet above water (USACE, 1994). Historically and prehistorically, human occupation at Hurlburt Field was confined to the area around Santa Rosa Sound; therefore, this is the area with the highest potential for historic resources. Nine archaeological sites have been identified from past surveys on the installation. Phase II testing conducted by Brockington and Associates in 1997 resulted in a determination of National Register of Historic Places (NRHP) eligibility for five sites (Woolpert, Inc., 2002). The installation Cultural Resources Management Plan contains details on all known archaeological sites whether or not they are eligible for listing on the NRHP (Woolpert, Inc., 2001). Based on these earlier studies, zones of probability (high,

medium, and low) have been identified for various areas of Hurlburt. Ground-disturbing activities in any high probability areas should be accompanied by a preliminary archaeological survey. Section 110 and 106 provisions of the National Historic Preservation Act will need to be fulfilled during all future Hurlburt Field development.

4.10 Noise

To balance the needs of aircraft operations and community concerns, the Department of Defense (DoD) has established the AICUZ program to protect the health, safety, and welfare of those living near military airfields while preserving the flying mission. The AICUZ program at Hurlburt Field delineates various noise level contours (65 to 85 average day-night sound levels, or DNL) and accident potential that can impact future facility sitings and serves as a document to discuss noise issues with local governmental agencies (see Figure 8). Airfield and training operation noise generation is a factor in Hurlburt facility planning and in a continuing dialog with surrounding communities to insure land use compatibility with critical military mission requirements. An EA in support of the CV-22 beddown suggested that existing aircraft noise may be encroaching into Mary Esther (AFCEE, 2001). A follow-up noise study was completed in FY 02 to validate/invalidate this. The results found that noise stayed within the perimeter of the base, therefore no Joint Land Use Study was required (Philip Pruitt, 2004. Personal Communication). The existing 65 dbA noise contours from aircraft operations on the Hurlburt Field flight-line has been shown as completely contained on Hurlburt or extending over water areas.

Low-level ingress and egress of aircraft along flight routes north of Eglin range near Crestview, Florida (west of Hurlburt) has resulted in periodic complaints of noise from local citizens. To deal with these complaints the Special Operations Forces use GPS data points to create no-fly zones over areas where complaints have been received. Aircraft noise, whether generated by engines on fixed-wing aircraft or by engines and blade slap on rotary-winged aircraft, generally present little problem in relation facility siting and land use on Hurlburt. Noise from weapons firing on the Eglin range, traffic noise from surrounding highways, as well as construction

noise on Hurlburt present little impact potential on installation programs (Woolpert, Inc., 2002).

4.11 AIR QUALITY

Hurlburt Field is within the jurisdiction of the Northwest District Air Quality Control Region of the FDEP, which monitors air pollution controls and permitting. Title I of the Clean Air Act requires that all federal facilities conform to the provisions of the State Implementation Plan (SIP). Specifically, the installation is in Air Quality Control Region #5, which encompasses southern Alabama, southern Mississippi, and north Florida. The Clean Air Act Amendments of 1990 (CAAA) are currently the comprehensive federal legislation regulating the prevention and control of air pollution. Title I of the CAAA requires federal actions to conform with the provisions of the approved SIP, which is developed and maintained by FDEP. Title V of the Clean Air Act Amendment (1990) requires identification and characterization of emissions from all minor sources including aircraft maintenance facilities, fuel storage tanks, and emissions from aircraft and motor vehicles. Aircraft represent the major source of air emissions at Hurlburt. Okaloosa County, including Hurlburt, is in an attainment area for all National Ambient Air Quality Standard criteria pollutants—particulates equal to or less than 10 microns in diameter (PM-10), sulfur dioxide, carbon monoxide, nitrogen dioxide, ozone, and lead. There is currently no established baseline of criteria pollutants for the attainment area encompassing Hurlburt.

Major stationary sources of air pollution on Hurlburt Field include: aircraft refueling, storage tanks, vehicle refueling, landfills, architectural and industrial maintenance coatings, aircraft engine test cell, natural gas-fired boilers, fugitive emissions, and auxiliary power generators. Historically, Hurlburt has been classified as a synthetic minor air pollution source. The synthetic minor source designation is defined as sources that have the physical and operational capability to emit major source levels of pollutants, but are not considered major sources because the owner/operator has accepted an enforceable limitation. This designation allows Hurlburt Field to operate without a Title V permit and reduced levels of regulatory screening, but it does limit emissions to levels below a set major source ceiling. Future growth may result in

having to apply for a Title V permit at a later date.

Although Hurlburt Field is in an attainment area, construction activities could create localized fugitive dust, and a temporary decrease in air quality from construction equipment emissions. Facility changes will also need to be documented as the facilities are programmed for construction to insure that Hurlburt remains classified as a synthetic minor source.

4.12 INFRASTRUCTURE AND TRAFFIC

Utility issues can become limiting factors in determining the siting of future facilities. Mission support, particularly east of the flightline, continues to drive the need for utility system improvements. Development and redevelopment of facilities require infrastructure support and changes in existing utility systems, however, they also provide opportunities for increased energy efficiency. The infrastructure systems at Hurlburt Field include water distribution, sanitary sewer, storm drainage, natural gas, electrical distribution, communications, and liquid fuels distributions.

As stated previously, Hurlburt currently has five potable water wells in operation that have a total production capacity of 2,100 gpm to 3.03 million gpd. Hurlburt Field is permitted by the State of Florida to pump a maximum combined withdrawal of 1.63 million gpd during a single day. The demand on the existing water system is greatest during the summer months due to use of irrigation systems (Woolpert, Inc., 2002).

The installation's sewage treatment plant is permitted by the State of Florida to treat one million gpd. Based on monthly averages, the plant is currently treating 0.7 million gallons of flow per day. The sanitary sewer system consists primarily of force mains supplied by over 60 lift stations (Woolpert, Inc., 2002). In addition, there is a cooperative program with the NFWMD and the City of Fort Walton Beach to provide treated wastewater to the city for industrial use (Woolpert, Inc., 2001), Industrial wastewater comprises less than four percent of the total flow to the installation's wastewater treatment facility. The vast majority of the industrial wastewater at Hurlburt originates from washracks located in aircraft maintenance

areas. The wastewater is then discharged from oil/water separators located near these aircraft and vehicle maintenance facilities to the wastewater treatment plant.

There are five storm water detention or retention ponds on the base: one at the south end of the runway (East Retention Pond), one along the south edge of Loop Road (Loop Retention Pond), one located south of US 98 and Hume Drive (Southwest Retention Pond), two located south of US 98 and west of the arc (South Central Retention Pond and Southeast Retention Pond). All of these ponds discharge to Santa Rosa Sound through three major outfalls (see Figures 2 and 4).

Okaloosa Gas supplies natural gas to Hurlburt Field. The company also owns and operates the system up to the meter. All systems within the buildings are the responsibility of Hurlburt Field. The primary use of natural gas on the base is for hot water and heating.

Gulf Power Company supplies electrical power to Hurlburt Field. There is one substation on the base that converts the incoming 110 kV transmission line to 12.5 kV on-base distribution lines. Gulf Power Company owns the incoming high-voltage transmission line and the Air Force owns the low voltage distribution system on base. The distribution system primarily consists of above-ground power lines.

Communications within the installation include telephone, data networking, radio, and security systems. The base telephone distribution system consists of copper cable, fiber optics, and manhole/conduit. The current distribution scheme is primarily copper wiring. Several noncore buildings require fiber connectivity to support high-speed network connectivity. The base telephone switch is government-owned and operated. The backbone of the data networking system at Hurlburt Field consists of an unclassified LAN that supports approximately 8.500 users. A classified network implemented primarily through Network Encryption Systems and TACLANES resides on the unclassified LAN and supports approximately 800 users.

JP-8, the principal liquid fuel, is delivered to the base by barge. A lightweight offload hose accomplishes barge connection and fuel is transferred to the base by a 4,500 foot underground 8-inch steel pipeline. Three ground

product stations are located on the base: AGE, mobility supply and storage, and RED HORSE. A majority of the service stations consist of multiple aboveground storage single wall steel tanks with dispenser pumps. Further details on installation infrastructure systems are provided in the General Plan (Woolpert, Inc., 2002).

A Transportation Plan for Hurlburt Field was completed in the mid-1990s (Woolpert, 1996). Numerous improvements to gates and internal circulation have been made since that time with more planned as part of General Plan implementation. Long-term changes in facility locations impact installation traffic density, internal circulation patterns, and gate usage.

Traffic circulation and parking patterns on Hurlburt Field are a direct result of the travel demand and the available capacity of the road and parking facilities. Safe and efficient traffic circulation is critical to the movement of personnel and materials within as well as onto and off of Hurlburt Field. The Transportation Plan (Woolpert, 1996) revealed five basic areas that needed improvements: Gating/Installation Access Control, Access/ Egress, Traffic Circulation, Road Conditions, and Off-Street Parking. For example, currently, the Main and Lovejoy Gates do not allow efficient entry onto Hurlburt Field, creating excessive stacking on Lovejoy Road, Cody Avenue, and US 98. Also, smooth traffic flow on base is interrupted by traffic entering and exiting numerous curb cuts (Woolpert, Inc., 2002). In addition, reduced parking and street network changes resulting from force protection requirements have put a strain on the parking and circulation of traffic on site. For more in-depth transportation information, refer to the Transportation Plan developed by the 16th CES and Woolpert, Inc.

4.13 REGULATED SPECIAL, SOLID, AND HAZARDOUS MATERIALS AND WASTE

According to Hurlburt Field's Solid Waste Management Plan, which implements Air Force guidance for solid and hazardous waste disposal, contractors transport, process, and dispose of solid waste streams generated on Hurlburt. According to Air Force Instruction 32-7042, Solid and Hazardous Waste Compliance, the Solid Waste Management Plan promotes an

integrated approach to waste collection. Yard waste, wood waste, and shredded paper that are generated on base are taken to Wright Composting and Landfill in Wright, Florida, while construction debris is taken to JMB Landfill in Fort Walton Beach, Florida, and Center Point Landfill in Crestview, Florida. Household garbage, as well as dumpster waste, is transported to Santa Rosa County Landfill in Marianna, Florida. Adequate landfill capacity remains within the region at the present time. In addition, Hurlburt operates a Qualified Recycling Program that has a diversion rate greater than 40 percent (Woolpert, Inc., 2002). Construction, deconstruction, and demolition wastes are handled as part of individual construction contracts and are disposed of off the installation. Pesticide use on Hurlburt is governed through implementation of the annually updated Integrated Pest Management (IPM) Plan. Restricted-use pesticides are applied only by DoD-certified applicators.

When contamination is involved concerning asbestos, lead-based paint, and other materials requiring special handling and disposal, specific qualified contractors are used to remove and dispose of it as described in the Asbestos Management Plan, Asbestos Operations Plan, and Lead-based Paint Management Plan. Asbestos regulation in the State of Florida is the responsibility of the FDEP. DoD installations are required to abide by state and local regulations by Executive Order 12088 and Air Force Instruction 32-1052.

Hurlburt uses above-ground storage tanks exclusively for storage of fuels and POL. JP-8 is delivered to the marine off-loading facility and then piped to storage tanks for flightline refueling use. Hurlburt Field's Spill Prevention Control and Countermeasures (SPCC) address control and clean up of fuel and POL spills. Hurlburt Field is a large-quantity generator of hazardous waste under EPA identification number FL7570024375. The installation has a Hazardous and Special Waste Management Plan which is updated annually (at a minimum) to ensure proper handling, accumulation, and disposal of all hazardous/special wastes generated at the facility. The Hazardous and Special Waste Management Plan defines requirements and responsibilities for reusing. recycling, and disposing of recoverable and used POL are detailed in the Hurlburt Field Recoverable and Used Oil Management Plan.

Hurlburt Field operates under both a Hazardous Waste Management Plan and a SPCC Plan. These documents regulate the use and proper disposal of hazardous materials and specify what should be done if a spill were to occur. The Hazardous Waste Management Program is administered by a Program Manager, a 90-Day Accumulation Point Manager, and an Initial Accumulation Point Manager. The Initial Accumulation points are located in shops or squadrons and deal directly with the day-to-day handling of hazardous waste (Figure 8). There are three 90-Day Accumulation Points, each managed separately. The three areas are located in 16th CES (Buildings 99054, 99055, and 99056), 16th EMS (Building 99070), and 16th TRANS (Building 99094).


Demolition, deconstruction, and construction of facilities as part of long-range planning impact special, solid, and hazardous material use and waste generation. Changes in airfield and roadway paving also often result in substantial solid waste generation.

4.14 INSTALLATION RESTORATION PROGRAM (IRP) SITES

The Hurlburt Field IRP is governed by guidance found in Air Force instruction 37-7020, Environmental Restoration Program. Hurlburt Field's IRP was established in 1993. The 16th CES/CEV assumed responsibility for management of all IRP sites located within the base boundaries in 1998 as a result of a joint Resource Conservation and Recovery Act (RCRA) Corrective Action permit signed by the USEPA, Eglin, and Hurlburt in 1998 (see Figure 8). Hurlburt also entered into a POL Cleanup Agreement with the FDEP in February 1999. Hurlburt, FDEP, and USEPA signed a LUC Memorandum of Agreement (MOA) in 1999. Under the LUC, the installation agrees to specific land use restrictions on contaminated sites in order to protect human health and the environment (see Figure 8). The LUC MOA requires that any major change in land use (i.e., from industrial to residential use) will require at least a 60 day notification to the EPA and FDEP (except in emergency situations). In 2001, Hurlburt Field was issued its own RCRA permit

and during 2002, HQ AFSOC/CEV assumed primacy for the IRP sites.

There are a total of 45 Areas of Concern and IRP sites on Hurlburt, as shown in Figure 8. Landfills 13, 14, 15, 16, 17, 18, 19, and 20; the PCB storage facility; the gunnery butt; and the CE storage yard are IRP sites currently in the LUC program. All of the landfills have native soil cover and have restrictions on penetration or other disturbance of the soil cover. Groundwater from these areas can only be used for nonpotable purposes with permission of the IRP Program Manager. The Hurlburt Field IRP Management Action Plan may be consulted for further information on the IRP program; however, the 813 and Dig Permit Process should be utilized prior to any ground penetration on the base.



5.1 Introduction

This section of the EA provides the analytical basis for the comparison of alternatives as required by 40 CFR 1502.14. This discussion of impacts (effects) is organized according to proposed projects within individual storm water sub-basin areas on Hurlburt Field (Figure 4), and it addresses individual resource/issue areas as discussed in Section 5.0. The No-Action Alternative, Alternative 1 (the Preferred Alternative), and Alternative 2 are discussed within each resource area. To the extent possible the direct, indirect, short-term, longterm, beneficial, and adverse impacts of each alternative are described for each resource area. The impacts discussion centers more on the cumulative approach of environmental analysis than on the individual project approach, as discussed in Section 1.4. However, when individual projects have particularly notable impacts, they are likewise discussed within the following narratives.

In each section, the cumulative impacts are discussed in the context of the definition given in 40 CFR 1508.7. The CEQ regulations, which implement NEPA, require assessment of cumulative impacts in the decision-making process for federal projects. Cumulative impacts are defined as "the impact on the environment which results from the incremental impact of the action when added to other past, present, and reasonable foreseeable future actions regardless of what agency (federal or nonfederal) or person undertakes such other actions. Cumulative impacts can result from individually minor, but collectively significant

actions taking place over a period of time" (40 CFR 1508.7).

Cumulative impacts are considered for the No-Action and the action alternatives. Cumulative impacts were determined by combining the impacts of any given project with potential past, present, and reasonably foreseeable future projects on the installation. This includes possible tenant-organization or NAF-funded projects. Reasonable future cumulative actions listed in the 2002 General Plan for Hurlburt Field included:

- Construction of large projects such as a new proposed marina, the proposed Mission Rehearsal Isolation Area (MRIA), and the proposed CV-22 beddown.
- Demolition projects.

Projects analyzed in this EA are arranged by the storm water sub-basin in which they are located. The exceptions to this approach being in regard to the resource/issue areas of air quality, noise, CZM, and socioeconomic resources, which are discussed in Section 5.2. In addition, those projects in Sub-Basins 4 and 5 are analyzed together. This is due to the high-level of boundary cross-over between projects in these two sub-basins, as well as the small size of Sub-Basin 5. Projects that cross sub-basin boundaries are analyzed within the sub-basin where the majority of the square footage is located, and cross-referenced for each subbasin impacted. In addition, there are no complete General Plan projects that are totally within Sub-Basins 1, 3, 9, and 10 associated with Alternative 1 and no projects located in Sub-Basins 1, 2, 3, and 6 for Alternative 2

(see Figures 9, 10, 12, 13, 14, 18, 23, and 25): consequently, these sub-basins will not be analyzed at the level of detail as is done for other sub-basins.

5.2 REGIONAL ANALYSIS OF AIR QUALITY, NOISE, AND COASTAL ZONE IMPACTS

5.2.1 Air Quality

All construction activities would have the potential to generate fugitive dust as well as emissions from construction equipment. Requirements to suppress and minimize fugitive dust generation such as the use of water sprays or other suppressants would be included in individual contract specifications and plan notes. As each new General Plan facility is constructed, an evaluation of any associated emission sources would be necessary. This may require a modification of Hurlburt Field's status as a synthetic minor source under the Title V air permit program. Generally, given the offset from scheduled demolitions, improvements in new building energy efficiency, use of best available control technology (BACT), and improved fuelhandling systems (such as a hydrant system); any overall increases in NAAQS criteria pollutant loads as well as hazardous air pollutants from General Plan projects should be very minor, have little impact on long-term regional air quality, and should not change Hurlburt Field's status as a synthetic minor source of air pollution.

5.2.2 Noise

Airfield noise as detailed in the most recent AICUZ study is an operational impact as opposed to most of the General Plan projects, which are facility oriented. The existing 65 dbA noise contours from aircraft operations on the Hurlburt Field flight-line has been shown as completely contained on Hurlburt or extending over water areas. Projects that are contained within the 65 dbA noise contours are classified as being within AICUZ limits.

Currently, there are 37 projects in Alternative 1 and 40 projects in Alternative 2 (out of 56 being considered in this EA) that fall within the AICUZ. On-installation projects falling with the 65 dbh or higher airfield noise contours would presumably

be associated with those organizations/activities requiring relatively close proximity to airfield operations as determined in the General Plan. Construction noise would accompany all proposed General Plan projects. In each case. this noise would be short-term in duration and would be limited to normal workday hours. Any projects in proximity of particularly noisesensitive activities such as classroom areas or medical facilities would require prior coordination before commencement of construction. Generally, implementation of General Plan projects would have short-term, very minor, adverse impacts on the noise environment on Hurlburt Field. The projects would have no impact on areas beyond the installation boundaries of Hurlburt Field.

5.2.3 Coastal Zone Impacts

Coastal zone impacts are not analyzed on a project by project basis since all projects on Hurlburt are considered within the state-defined coastal zone, and the General Plan projects discussed in this EA will be reviewed for consistency through established State Clearinghouse channels. All projects identified in this EA observe the 50-foot setback from the Santa Rosa Sound shoreline, and those projects within potential storm surge areas and areas subject to maximum hurricane impacts will be appropriately constructed to minimize damage potential. Consistency reviews of projects which require permits from the USACE, US Coast Guard, or require a State Environmental Resource Permit are conducted during the state permit review and must include an evaluation on the project based upon Florida's 23 statutes (see Table 8). The nature of the FCMP lends itself to regional analysis, rather than on an individual, project by project basis. Any CZM issues are discussed from a regional perspective, and a draft of this EA will be submitted to the State of Florida for a consistency determination of the overall proposed action.

5.2.4 Socioeconomic Resources

Socioeconomic resources are not analyzed on a project by project basis as all of the projects in all alternatives would occur wholly within the installation. Most aspects of socioeconomic resources are covered in other sections of this EA, such as any impacts associated with

Table 8 Florida Coastal Management Plan Proposed Action Checklist				
Statute	Consistency	Scope of Statute		
Chapter 161: Beach and Shore Preservation	Not applicable to proposed activities.	Authorizes the Bureau of Beaches and Coastal Systems within the Department of Environmental Protection to regulate the construction on or seaward of the state's beaches.		
Chapter 163, Part II: Growth Policy; County and Municipal Planning; Land Development Regulation	Not applicable to proposed activities.	Requires local governments to prepare, adopt, and implement comprehensive plans that encourage the most appropriate use of land and natural resources in a manner consistent with the public interest.		
Chapter 186: State and Regional Planning	Not applicable to proposed activities.	Details the state level planning requirements. Requires the development of special statewide plans governing water-use, land development, and transportation.		
Chapter 252: Emergency Management	Not applicable to proposed activities.	Provides for the planning and implementation of the state's response to natural and manmade disasters, efforts to recover from natural and manmade disasters, and the mitigation of natural and manmade disasters.		
Chapter 253: State Lands	Not applicable to proposed activities.	Addresses the state's administration of public lands and property of this state and provides direction regarding the acquisition, disposal, and management of all state lands.		
Chapter 258: State Parks and Reserves	Not applicable to proposed activities.	Addresses the administration and management of all state parks and reserves.		
Chapter 259: Land Acquisition for Conservation or Recreation	Not applicable to proposed activities.	Authorizes acquisition of environmentally endangered lands and outdoor recreation lands.		
Chapter 260: Recreational Trails System	Not applicable to proposed activities.	Authorizes acquisition of land to create a recreational trail system and to facilitate the management of the system.		
Chapter 267: Historical Resources	Archaeological and historical resources found on Hurlburt Field have been identified and none of the proposed projects within this EA will impact known archaeological/historical resources.	Addresses the management and preservation of the state's archaeological and historical resources.		
Chapter 288: Commercial Development and Capital Improvements	Not applicable to proposed activities.	Provides the framework for promoting and developing the general business, trade, and tourism components of the state economy.		
Chapter 334: Transportation Administration	Not applicable to proposed activities.	Addresses the state's policy concerning transportation administration.		
Chapter 339: Transportation Finance and Planning	Not applicable to proposed activities.	Addresses the finance and planning needs of the state's transportation system.		
Chapter 370: Saltwater Fisheries	Not applicable to proposed activities.	Addresses the management and protection of the State's saltwater fisheries.		
Chapter 372: Wildlife	Not applicable to proposed activities.	Addresses the management of the wildlife resources of the state.		
Chapter 373: Water Resources	Not applicable to proposed activities.	Addresses the state's policy concerning water resources.		
Chapter 375: Multipurpose Outdoor Recreation; Land Acquisition, Management, and Conservation	Not applicable to proposed activities.	Develops a comprehensive multipurpose outdoor recreation plan to document recreational supply and demand, describe current recreational opportunities, estimate the need for additional recreational opportunities, and propose a means to meet the identified needs.		

Table 8 Florida Coastal Management Plan Proposed Action Checklist				
Statute	Consistency	Scope of Statute		
Chapter 376: Pollutant Discharge Prevention and Removal	Best management practices and usages of Hurlburt Field's existing pollution prevention/hazardous waste management plans will be used as part of the implementation of projects analyzed in this EA in order to reduce any possible discharges or storage issues.	Regulates the transfer, storage, and transportation of pollutants and the clean-up of pollutant discharges.		
Chapter 377: Energy Resources	Not applicable to proposed activities.	Addresses the regulation, planning and development of the energy resources of the state.		
Chapter 380: Land and Water Management	Not applicable to proposed activities.	Establishes land and water management policies to guide and coordinate local decisions related to growth and development.		
Chapter 381: Public Health, General Provisions	Not applicable to proposed activities.	Establishes public policy concerning the state's public health system.		
Chapter 388: Mosquito Control	Not applicable to proposed activities.	Addresses the mosquito control effort in the state.		
Chapter 403: Environmental Control	Not applicable to proposed activities.	Establishes public policy concerning environmental control in the state.		
Chapter 582: Soil and Water	Best management practices will be	Provides for the control and prevention		
Conservation	utilized throughout implementation of the projects analyzed in this EA to control and prevent soil erosion during construction.	of soil erosion.		
Source: Florida Department of Environmental Protection Website: http://www.dep.state.fl.us/cmp/federal/23_statutes.htm.				

changes in traffic circulation and installation access will be discussed under Infrastructure and Traffic. Impacts resulting from the proposed relocation of military family housing will be addressed as a cumulative impact with reference to the separate Environmental Impact Statement previously prepared for this action. There would be a small increase in regional jobs due to construction at Hurlburt Field. There may also be indirect impacts associated with oninstallation mission expansion that could lead to population growth in the surrounding communities. However, these impacts are difficult to quantify and would only have minor impacts to the socioeconomic climate of Hurlburt and the surrounding area. Therefore, socioeconomic resources will not be addressed in this EA.

5.3 SUB-BASIN 1 (FIGURES 9 AND 10)

There are no construction projects located solely or partially within Sub-Basin 1. Also, there are no planned demolitions located within this sub-basin.

5.4 SUB-BASIN 2 (FIGURES 11 AND 12)


5.4.1 Overview of Alternative 1


There is one Alternative 1 project located solely within Sub-Basin 2, Project 02-01 (Construct Outdoor Recreation Center, 16 SVS). This project is shown in relationship to the entire subbasin in Figure 11, with additional site detail in Appendix B. This project consists of constructing an outdoor recreation center along Marina Road. More detailed information on this project can be found in the DD Form 1391 included in Appendix C. A general impact summary for this project within Sub-Basin 2 is calculated in Table 9 and analyzed in the following paragraphs.

Table 9 Impact Summary for Sub-Basin 2, Alternative 1				
Impact Area Result				
Floodplains	21,015.9 SF			
Within a Storm Surge Area	Category 1, 2, 3, 4, and 5			
New Impervious Surface	3,111 SF for Buildings 17,904.9 for Parking/Roads			
Demolitions	45 (178,096 SF)			









Other projects not in General Plan CIP but having a potential cumulative impact on the environment within Sub-Basin 2 include the demolition of 45 single MFH units as part of the DoD MFH privatization program. Demolition of these housing units would clear approximately 4.0 acres within the southern portion of this subbasin. The planned demolition of all the MFH units north of US 98 in both Sub-Basins 2 and 4 would open up approximately 99 total acres for redevelopment. The demolition of the family housing area as part of a privatization program involving both Hurlburt Field and Eglin AFB is addressed in an Environmental Baseline Survey (SAIC, 2003) and a Draft EIS (SAIC, 2004) and is addressed here only in terms of its cumulative impact. Project 02-01 would have no impact on the following resource areas—permitted or unpermitted wetland areas, endangered species, cultural resources, hazardous materials/IRP sites, AICUZ, Q/D arcs, or the permit process.

5.4.2 Overview of Alternative 2

There are no Alternative 2 projects located in Sub-Basin 2 and no analysis will be done in this sub-basin. The Alternative 2 site for Project 02-01, would be located wholly within Sub-Basin 7 and is included in the discussion of impacts under that sub-basin.

5.4.3 Analysis

5.4.3.1 Groundwater

Alternative 1—Although the Outdoor Recreation Center project would not draw substantial amounts of potable water from the Floridan Aquifer or the Sand and Gravel Aguifer, the overall reduction in oninstallation population resulting from the removal of 306 units (147 of which located in Sub-Basins 4 and 5) of MFH (SAIC, 2003) would cumulatively reduce potable water demand on Hurlburt—at least in the short term. However, new housing being constructed on Eglin AFB would draw from the Floridan Aquifer, which would result in no overall net loss or gain regionally. There would be a short-term, minor, beneficial impact on Floridan Aquifer groundwater supplies following demolition of the housing, but a long-term negligible impact. Additionally, the MFH demolitions along with the proposed Outdoor Recreation Center

taken cumulatively would result in a negligible, short-term beneficial impact on recharge of the shallow Sand and Gravel Aquifer underlying Hurlburt. There could be a minor beneficial impact on Sand and Gravel Aquifer recharge since there would be a net decrease in impervious surface area of approximately 157,080 SF, or 3.6 acres. In the long-term, the cumulative impacts on groundwater associated with this alternative would be negligible. There would be no impact to recharge of the deeper Floridan Aquifer since Hurlburt is not in a recharge zone for this aquifer.

No-Action Alternative—The No-Action Alternative would involve no new construction within Sub-Basin 2. However, the MFH demolitions would still take place thereby resulting in a short- and long-term moderate beneficial impact to recharge of the Sand and Gravel Aquifer. This alternative would have no impact on recharge or use of the Floridan Aquifer.

5.4.3.2 Surface Water and Storm Water

- Alternative 1—The Outdoor Recreation Center site (Project 02-01) drains via sheet flow directly to adjacent Santa Rosa Sound. Individually, this project would result in a short-term, minor, adverse impact on storm water quality due to potential increases in erosion from demolition and construction activities. Cumulative impacts resulting from initial construction activities and the subsequent long-term net decrease in impervious surface areas (approximate reduction of 157,080 SF) from MFH demolitions should decrease run-off of storm water thus having a short- and long-term. minor beneficial impact. Additionally, the use of lawn and garden pesticides often associated with MFH would be eliminated with a long-term, minor, beneficial impact on storm water quality in this sub-basin.
- No-Action Alternative—The No-Action Alternative would involve no new construction within Sub-Basin 2. However, the MFH demolitions would still take place. The result of these demolitions would result in a possible short-term increase in erosion potential followed by a long-term decrease in the quantity and increase in the quality of storm water runoff. Cumulatively, the MFH

demolitions could also improve storm water quality through the long-term reduction of pesticides within this sub-basin.

5.4.2.3 Floodplains

- Alternative 1—Project 02-01 is entirely within an identified 100-year floodplain. A Finding of No Practicable Alternative would need to be approved prior to construction. Consequently, Alternative 1 would have a long-term but very minor adverse impact upon the floodplain and flood elevation. The total area of the Outdoor Recreation Center project within 100-year floodplain is approximately 21,015.9 SF (0.48 acre) within Sub-Basin 2. Cumulatively, when taking into consideration the planned demolition of the existing MFH units in Sub-Basin 2, Alternative 1 would have a longterm, minor, beneficial impact upon floodplain capacity.
- No-Action Alternative—The No-Action Alternative would result in no construction within Sub-Basin 2. However, cumulatively, the removal of MFH units would have a long-term negligible to minor beneficial impact on floodplain capacity.

5.4.2.4 Storm Surge Areas

Alternative 1—The Alternative 1 project within Sub-Basin 2 includes one habitable structure within identified storm surge areas. Project 02-01 is located in Storm Surge Areas 1, 2, 3, 4, and 5. There have been no recorded cases of hurricanes in the Hurlburt vicinity that have generated storm surge elevations impacting Storm Surge Areas 4 or 5 (Woolpert, Inc., 2001). Storm Surge Areas 1, 2, and 3 were last impacted during Hurricane Ivan in September 2004, which produced storm surges of 6 to 9 feet at Hurlburt (National Hurricane Center, 2005). Individually, this project would have either no or a long-term negligible adverse impact in terms of future potential damage from hurricane storm surges. Coastal Protection Act guidance would need to be used in designing and constructing the outdoor recreation facility to insure a consistency determination under the Florida CZM Program.

Cumulatively, the removal of existing MFH units currently in Storm Surge Areas 4 and 5 would result in a long-term, minor, beneficial impact in terms of reducing the possibility of future storm damage to installation facilities.

No-Action Alternative—The No-Action Alternative would involve no new construction within any storm surge areas. However, cumulatively, removal of existing MFH units currently in Storm Surge Areas 4 and 5 would result in a long-term, minor, beneficial impact in terms of reducing the possibility of future storm damage to installation facilities.

5.4.2.5 General Flora and Fauna

Alternative 1—Construction of the Outdoor Recreation Facility would require no removal of mature trees from the site. This project would be within Hurlburt Field's developed area, so there would be few impacts on flora and fauna. Individually, this project would have a long-term, negligible adverse impact on landscape trees in the vicinity of the recreation center. When taking into account the probable cutting of numerous mature trees (many are mature live oaks) as part of the MFH demolition, cumulatively, all of the projects in Sub-Basin 2 would have a longterm, moderate adverse impact on landscape trees. Replanting landscape trees (per the installation's tree replacement policy) would mitigate some of the impact. The maximum use of native tree and herbaceous vegetation in all new landscaping should be encouraged as discussed in the Hurlburt INRMP (Woolpert, Inc., 2001).

The project as well as the MFH demolition project would have a short- and long-term negligible adverse impact on urban wildlife habitat (nest trees, nectar-bearing plants, landscape plantings around quarters, and so on).

No-Action Alternative—The No-Action Alternative would involve no new construction within Sub-Basin 2. However, cumulatively, the loss of mature landscape trees within the existing MFH area would result in a short- and long-term minor to moderate adverse impact.

5.5 SUB-BASIN 3 (FIGURES 13 AND 14)

There are no construction projects located solely within Sub-Basin 3 (see Figures 13 and 14). However, Alternative 1 includes 0.35 acre of Project 07-10A (Base Roadway Improvements) in Sub-Basin 3 and 0.30 acre in Sub-Basins 4 and 5 (see Figure 13). These acreages are the same for impacts to floodplains as well. The majority of Project 07-10A, 1.86 acres (74 percent) occurs within Sub-Basin 7 (refer to that sub-basin section for impact descriptions, including cumulative impacts). Alternative 2 would result in 1.43 acres (100 percent) of roadway in Sub-Basin 7, and there are no floodplain impacts.

There are no planned demolitions located within this sub-basin.

5.6 SUB-BASINS 4 AND 5 (FIGURES 15 AND 16)

5.6.1 Overview of Alternative 1

Projects within these sub-basins (see Figures 15 and 16) for Alternative 1 are listed in Table 10 and are shown in relationship to the entire subbasin areas in Figure 15 with additional site detail in Table 3 and Appendix B. Several projects with this EA straddle sub-basin boundaries. These projects include Project 05-01 (Soundside Visiting Quarters), which is partially within Sub-Basin 6. Since the majority of this project is contained with in Sub-Basins 4 and 5, it will be discussed within this section. Project 04-07 (SOF JSOU Library/Education Center Com/Language Lab PH 3) has 22,998.7 SF within Sub-Basin 11, and 42,527.9 SF is inside Sub-Basin 7. This project will be discussed in this section under Sub-Basins 4 and 5 since 63,623 SF occur in Sub-Basin 4.

There are 138 demolitions totaling 596,214 SF scheduled for Sub-Basins 4 and 5. Some of these demolitions are programmed in order to facilitate the implementation of the Alternative 1 projects programmed for these sub-basins. These demolitions are addressed here only in terms of their contribution to cumulative impacts of Alternative 1 projects.

The purpose and need for each project listed in Table 10 is summarized in Table 3 in Section 2.0. Detailed project justifications and additional construction information can be found in DD Form 1391 information in Appendix C.

Table 10 Installation MILCON and SRM Projects in Sub-Basins 4 and 5, Alternative 1				
Project #	FTEV #	Description		
04-01	04-1072	ADAL Fitness Center Building 90517		
04-02A	95-3013	Temporary Lodging Facility		
04-02B	95-3013	3013 Temporary Lodging Facility		
04-03	4-03 04-3016 Supply Warehouse			
04-04	99-3036	Child Development Center		
04-05	03-3022	16th Contracting Squadron Facility		
04-06	97-3019	Airmen Leadership School		
04-07	02-3015	3015 SOF JSOU Library/Education Center Complex/Language Lab		
05-01	03-3020	Soundside Visiting Quarters		

The overall impact of all eight projects within Sub-Basins 4 and 5 under Alternative 1 is shown in Table 11 and analyzed in the following paragraphs.

Table 11 Impact Summary for Sub-Basins 4 and 5, Alternative 1			
Impact Area Result			
Floodplains	24,740.9 SF (0.57 Acres)		
Trees Removed	122 Trees		
Within the AICUZ	2 Projects (04-07 and 04-06)		
Within a Storm Surge	1 Project (05-01)		
Area			
IRP	49,841.2 SF (1.14 Acres)		
New Impervious Surface	8 Facilities; 841,952 SF		
	(19.33 Acres)		
Demolitions	138 Facilities; 596,214 SF		
	(13.69 Acres)		

An action with substantial cumulative impacts located within Sub-Basins 4 and 5 under Alternative 1 is the planned demolition of 138 MFH units involving about 13.69 acres. These demolitions are related to land use changes as part of the planned total demolition of all existing Hurlburt family housing areas north of US 98. As mentioned above under Sub-Basin 2, the demolition of the MFH area is part of a privatization program involving both Hurlburt Field and Eglin AFB and is addressed in an Environmental Baseline Study (SAIC, 2003) and in a separate EIS (SAIC, 2004). This action is addressed here only in terms of its cumulative impact. General Plan projects in these subbasins would have no impact on the following issue/resource areas—wetlands (permitted or un-permitted); IRP sites; RTE species; and archeological sites.

5.6.2 Overview of Alternative 2

Alternative 2 projects within these two subbasins are listed in Table 12 and are shown in relationship to the entire sub-basin areas in Figure 16 with additional site detail in Appendix B.

Table 12 Installation MILCON and SRM Projects in Sub-Basins 4 and 5, Alternative 2			
Project # FTEV # Description			
04-02	95-3013	Temporary Lodging Facility	
05-01 03-3020 Soundside Visiting Quarters		Soundside Visiting Quarters	
06-01	01-5007	Consolidated Club	
11-09	02-3010	Addition to Visiting Quarters	

The purpose and need for each project listed in Table 12 is summarized in Table 3 in Section 2.0. Detailed project justifications and additional construction information can be found in DD Form 1391 information in Appendix C.

The overall impact of all four projects within Sub-Basins 4 and 5 under Alternative 2 is shown in Table 13 and analyzed in the following paragraphs in the analysis portion of this section.

Table 13 Impact Summary for Sub-Basins 4 and 5, Alternative 2			
Impact Area	Result		
Un-Permitted Wetlands	90,202 SF (2.07 Acres)		
Trees Removed	17 Trees		
Within the AICUZ	1 Project is Within the 65 db Contour (Project 11-09)		
New Impervious Surface	4 Facilities; 227,017 SF (15.21 Acres)		
Demolitions	121 Facilities; 527,244 SF (12.10 Acres)		


An action with substantial cumulative impacts located within Sub-Basins 4 and 5 under Alternative 2 is the planned demolition of 121 MFH units involving about 12.10 acres. These demolitions are related to land use changes as part of the planned total demolition of all existing Hurlburt family housing areas north of US 98. As mentioned above under Sub-Basin 2. the demolition of the MFH area is part of a privatization program involving both Hurlburt Field and Eglin AFB and is addressed in an Environmental Baseline Study (SAIC, 2003) and will be addressed in a separate EIS. This action is addressed here only in terms of its cumulative impacts. General Plan projects in these subbasins would have no impact on the following issue/resource areas—storm surge areas;


floodplains; IRP sites; RTE species; and archeological sites.

5.6.3 Analysis

5.6.3.1 Groundwater

- Alternative 1—There are eight proposed projects in Sub-Basins 4 and 5 that involve the construction of new facilities—some of which would require a connection to the potable water system and which would increase demand on the Floridan Aquifer. None of the individual Alternative 1 projects within Sub-Basins 4 and 5 would directly impact recharge of the Floridan Aquifer. The overall reduction in on-installation population resulting from the demolition of 258 MFH units (138, of which, under Alternative 1, are located in Sub-Basins 4 and 5) would cumulatively reduce potable water demand on Hurlburt—at least in the short term. However, new housing being constructed on Eglin AFB and additional permanent and temporary personnel using new facilities within Sub-Basins 4 and 5 would draw from the same aguifer, which would result in no overall increase or decrease in potable water demand. Additionally, the actions taken cumulatively in these sub-basins (including removal of over 596,214 SF of impervious surface area) would result in a negligible, short-term beneficial impact on recharge of the shallow Sand and Gravel Aguifer underlying Hurlburt. However, construction of the eight Alternative 1 projects within Sub-Basins 4 and 5 would eventually add 841,952 SF of impervious surface resulting in a net increase of 245,738 SF. This increase in impervious surface area could result in a very minor adverse impact on Sand and Gravel Aquifer recharge.
- Alternative 2—There are four projects in Sub-Basins 4 and 5 associated with this alternative that involve the construction of new facilities, additions to existing facilities, or roadway modifications. New facilities would add to the demand on the Floridian Aquifer. None of the individual Alternative 2 projects within Sub-Basins 4 and 5 would directly impact recharge of the Floridan Aquifer. The overall reduction in oninstallation population resulting from the demolition of 258 MFH units (121, of which,





under Alternative 2, are located in Sub-Basins 4 and 5) would cumulatively reduce potable water demand on Hurlburt—at least in the short term. However, new housing being constructed on Eglin AFB and additional permanent and temporary personnel using new facilities within Sub-Basins 4 and 5 would draw from the same aguifer, which would result in no overall increase or decrease in potable water demand. Additionally, the actions taken cumulatively in these sub-basins (including removal of over 527,244 SF of impervious surface area) would result in a negligible. short-term beneficial impact on recharge of the shallow Sand and Gravel Aquifer underlying Hurlburt. However, construction of the four Alternative 2 projects within Sub-Basins 4 and 5 would eventually add 227,017 SF of impervious surface resulting in a net increase of 300,2279 SF in pervious surface area. This increase in surface area could allow a very minor beneficial impact on Sand and Gravel Aquifer recharge.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins and, therefore, would not increase demand on potable water sources for Hurlburt.

However, the demolition of MFH units and other facilities would have a long-term minor to moderately beneficial impact on recharge of the Sand and Gravel Aquifer. With the No-Action Alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.6.3.2 Surface Water and Storm Water

• Alternative 1—All project locations within Sub-Basins 4 and 5 drain to the Southwest Regional Storm Water Pond south of US 98 and, in times of high flow, discharge to Santa Rosa Sound through Outfall 006 (Sub-Basin 2) or Outfall 005 (Sub-Basin 4). Individually, the projects within these sub-basins would result in short-term, minor, adverse impacts on storm water quality due to potential increases in soil disturbance and erosion. The removal of 122 existing trees in these sub-basins would also contribute to minor, short-term increases in storm water runoff from the project site due to a loss of ground cover that could lead to increased erosion of top-soil. Subsequent to construction, there would be increased impervious surface areas associated with the buildings, parking areas and road access, which would increase storm water quantity and decrease storm water quality within these sub-basins.

Cumulatively, even when taking into consideration the planned demolition of the existing MFH units in Sub-Basin 4; Alternative 1 projects would have a long-term, minor, adverse impact on storm water as a result of a net increase (841,952 SF) in overall impervious surface area.

• Alternative 2—All project locations within Sub-Basins 4 and 5 drain to the Southwest Regional Storm Water Pond south of US 98 and, in times of high flow, discharge to Santa Rosa Sound through Outfall 006 (Sub-Basin 2) or Outfall 005 (Sub-Basin 4). Individually, the projects within these subbasins would result in short-term, minor, adverse impacts on storm water quality due to potential increases in erosion from construction activities. The removal of 17 existing trees in Sub-Basins 4 and 5 would also contribute to minor, short-term increases in storm water runoff from the project site due to a loss of ground cover.

Cumulatively, when taking into consideration the planned demolition of the existing MFH units in Sub-Basin 4; Alternative 2 would have a long-term, minor, beneficial impact on storm water quantity and quality as a result of a net increase (300,2279 SF) of overall pervious surface area within Sub-Basins 4 and 5.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins, and, therefore, would not directly impact surface waters or storm water. However, the demolition of the MFH units and other facilities would have a long-term, moderate beneficial impact on surface water and storm water quantity and quality within Sub-Basins 4 and 5. With the No-Action Alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.6.3.3 Floodplains

- Alternative 1—Projects within Sub-Basins 4 or 5 that are partially or entirely within an identified floodplain include Projects 04-03 (Supply Warehouse) and 05-01. Project 05-01 roadway and/or parking improvements within these sub-basins are also within identified floodplains. Impacts to the floodplain by these projects would be longterm and be only negligibly adverse as few structures are involved. A Finding of No Practicable Alternative would need to be approved prior to construction of the supply warehouse or the Soundside Visiting Quarters. Consequently, Alternative 1 would have a long-term, minor adverse impact upon the floodplain. The total area of all Alternative 1 projects within the 100-year floodplain is approximately 24.740.9 SF (0.57 acres) in all of Sub-Basins 4 and 5.
- Alternative 2—Proposed projects within Sub-Basins 4 and 5 under Alternative 2 do not fall within or near the confines of a floodplain and would therefore not be impacted or impact existing floodplains nor be subject to the provisions of Executive Order 11988.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins and, therefore, would not impact floodplains. With the No-Action Alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.6.3.4 Storm Surge Areas

• Alternative 1—The Soundside Visiting Quarters complex is located in Storm Surge Areas 1, 2, 3, and 4. There have been no recorded cases of hurricanes in the Hurlburt vicinity that have generated storm surge elevations impacting Storm Surge Areas 4 or 5 (Woolpert, Inc., 2001). Storm Surge Areas 1, 2, and 3 were last impacted during Hurricane Ivan in September 2004, which produced storm surges of 6 to 9 feet at Hurlburt (National Hurricane Center, 2005). Individually, and depending on the severity of future hurricanes, the projects in Sub-Basins 4 and 5 would have a long-term moderate, adverse impact in terms of future potential damage from hurricane storm surges. Coastal Protection Act guidance would need to be used in designing and constructing the billeting facility (Project 05-01) in order to insure consistency with the Florida CZM Program.

Cumulatively, the removal of existing MFH units currently in Storm Surge Areas 4 and 5 would result in a long-term, minor, beneficial impact in terms of reducing the possibility of future storm damage to installation facilities.

 Alternative 2—The proposed projects under Alternative 2 within Sub-Basins 4 and 5 do not fall within or near the confines of a storm surge area and therefore would not be impacted by future hurricane storm surges.

Cumulatively, the removal of existing MFH units currently in Storm Surge Areas 4 and 5 under Alternative 2 would result in a long-term, minor, beneficial impact in terms of reducing the possibility of future storm damage to installation facilities.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins and, therefore, would not impact storm surge areas. With the No-Action Alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this subbasin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.6.3.5 General Flora and Fauna

• Alternative 1—Most of the Alternative 1 projects would be within Hurlburt Field's already developed areas or in areas scheduled for redevelopment, so there would be few impacts on flora and fauna. Site clearing would involve 122 trees covered by the installation's tree replacement policy for Alternative 1. The individual project in Sub-Basins 4 and 5 having the most impact on landscape trees is Project 05-01, which would impact roughly

53 trees in Sub-Basin 5 south of Purcell Drive. Many of these trees are mature live oaks. When taking into account the probable cutting of numerous mature trees as part of the MFH demolition, cumulatively, all of the projects in Sub-Basins 4 and 5 would have a long-term, moderate adverse impact on landscape trees. The maximum use of native trees and herbaceous vegetation in all new landscaping should be encouraged as discussed in the Hurlburt INRMP (Woolpert, Inc., 2001).

Projects associated with Alternative 1 in Sub-Basins 4 and 5 would have a short- and long-term minor adverse impact on urban wildlife habitat (nest trees, nectar-bearing plants, landscape plantings around quarters, and so on).

Alternative 2—Most of Alternative 2 projects would be within Hurlburt Field's already developed areas or in areas scheduled for redevelopment, so there would be few other impacts on flora and fauna. Site clearing would involve 17 trees covered by the installation's tree replacement policy for Alternative 1. When taking into account the probable cutting of mature trees as part of the construction efforts, cumulatively, all of the projects in Sub-Basin 4 would have a long-term, minor adverse impact on landscape trees. The maximum use of native trees and herbaceous vegetation in all new landscaping should be encouraged as discussed in the Hurlburt INRMP (Woolpert, Inc., 2001).

Projects associated with Alternative 2 in Sub-Basins 4 and 5 would have a short- and long-term minor adverse impact on urban wildlife habitat (nest trees, nectar-bearing plants, landscape plantings around quarters, and so on).

No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins and, therefore, would not impact flora and fauna within developed areas of Hurlburt. Planned demolitions would have a short-term, adverse impact on mature trees. With the No-Action Alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see

Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.6.3.6 Archaeological Resources

- Alternative 1—The Soundside Visiting Quarters (Project 04-03) along Santa Rosa Sound is in an area with a potentially high probability of containing archeological resources. As such, the project area should be checked for the presence of archaeological resources prior to construction activities, and any resources would need to be recovered. Should any human remains be located, the provisions of the Native American Graves Protection and Repatriation Act (NAGPRA) must be followed.
- Alternative 2—The projects in Sub-Basins 4 and 5 under this alternative do not appear to fall within the vicinity of any archaeological or other known cultural resources.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins; therefore, would not impact potential archaeological resources. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.6.3.7 Infrastructure and Traffic

Alternative 1—In terms of utility infrastructure, the single most important action within Sub-Basins 4 and 5 would be the cumulative impacts related to the demolition of existing MFH. As discussed under Section 5.5.3.1, demand on Floridan Aguifer installation wells supplying the Hurlburt potable water system would be substantially reduced as a result of this action. Fewer housing residents on Hurlburt would also result in reduced wastewater generation and reduced demand for electricity and gas. Alternative 1 implementation, along with the demolition of existing MFH units, would have a short-term moderate beneficial impact on utility infrastructure and demand within SubBasins 4 and 5. However, new housing being constructed on Eglin AFB would likely draw from the same resources as Hurlburt Field for utility supply. There is currently a MFH privatization environmental impact statement being conducted that will examine this issue in greater detail.

Demolition of MFH and subsequent construction of new structures in the existing MFH area (Project 04-04, Child Development Center; 04-05, 16th Contracting Squadron Facility; and 05-01, Visiting Airmen Quarters) would change roadway configurations, traffic patterns, and traffic levels in this portion of the installation. Proposed improvements in roadway geometry and surfacing in the Soundside area east of the marina would improve traffic flow in this area. The proposed Soundside Visiting Facility in Sub-Basin 5 would only negligibly increase traffic in the Soundside area. Alternative 1 would have an individual and cumulative (with inclusion of the MFH demolition), long-term, minor, beneficial impact on traffic patterns and traffic flow on Hurlburt.

Alternative 2—In terms of utility infrastructure, the single most important action within Sub-Basins 4 and 5 would be the cumulative impacts related to the demolition of existing MFH units. As discussed under Section 5.5.3.1, demand on Floridan Aguifer installation wells supplying the Hurlburt potable water system would be substantially reduced as a result of this action. Fewer housing residents on Hurlburt would also result in reduced wastewater generation and reduced demand for electricity and gas. Alternative 2, along with the demolition of 121 existing MFH units, would have a short-term moderate beneficial impact on utility infrastructure and demand. However, with new housing being constructed on Eglin AFB, there would likely be a demand for the same utility resources that also service Hurlburt Field. There is currently a MFH privatization environmental impact statement being developed that will examine this issue in greater detail.

Projects 11-09 (Addition to Visiting Quarters) and 04-02 (Temporary Lodging Facility) are positioned adjacent to Tully Street and would require curb cuts to facilitate safe

circulation of traffic into and out of these facilities. Alternative 2 would have an individual and cumulative (with inclusion of the MFH demolition), long-term, minor, beneficial impact on traffic patterns and traffic flow on Hurlburt.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins and, therefore, would not directly impact utilities or traffic movements within Hurlburt. However, the demolition of the MFH units would reduce utility demands, change local traffic patterns, and reduce overall levels of traffic within these sub-basins. With the No-Action Alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.6.3.8 Regulated Special, Solid, and Hazardous Materials and Wastes

- Alternative 1—Some solid waste generation would be associated with site clearing and grubbing for some of the new facilities included under Alternative 1 in both Sub-Basins 4 and 5. Most of this waste would be trees and other vegetation cleared from the sites prior to construction. Individually, Alternative 1 projects in Sub-Basins 4 and 5 would have a short-term. minor, adverse impact on solid waste generation. Tree removal within Sub-Basins 4 and 5 is also scheduled for other projects that straddle or share a border with Sub-Basins 4 and 5. Substantial solid waste generation would also occur as part of MFH demolition. Cumulatively, Alternative 1 and the MFH demolitions would have a shortterm, moderate, adverse impact on solid waste generation. Demolitions could also involve the need to remove and dispose of minor amounts of asbestos-containing wastes, materials containing lead-based paints, and other special or hazardous materials and wastes.
- Alternative 2—Some solid waste generation would be associated with site clearing and grubbing for some of the new facilities included under Alternative 2 in Sub-Basins 4 and 5. Most of this waste would be

trees and other vegetation cleared from the sites prior to construction. Individually, the Alternative 2 in Sub-Basins 4 and 5 would have a short-term, minor, adverse impact on solid waste generation. Substantial solid waste generation would occur as part of MFH demolition Cumulatively, Alternative 2 and the MFH demolitions would have a short-term, moderate, adverse impact on solid waste generation. Demolitions could also involve the need to remove and dispose of minor amounts of asbestos-containing wastes, materials containing lead-based paints, and other special or hazardous materials and wastes.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins; therefore, solid waste generation with respect to construction activities and tree removal would not be generated. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.6.3.9 IRP Sites

Alternative 1—There are two projects that intersect with known IRP sites. Project 04-03 and project 05-01 impact portions of IRP sites SD-208 and SS-214 respectively (Appendix B). Project 04-03 impacts 42,820 SF of the IRP site SD-208. Project 05-01 impacts 7.020.8 SF of IRP site SS-214. Any projects potentially impacting contaminated sites would be coordinated through the IRP Program Manager to insure consistency with the Management Action Plan and to avoid disturbance of subsurface contamination. LUC agreements would also be checked prior to detailed facility design to insure compatibility under existing legal agreements. Alternative 1 projects would have a long-term, minor, adverse impact on contaminated sites in terms of potential future problems with both contamination and with site clean-up.

- Alternative 2—There are no known IRP sites on or within the vicinity of Alternative 2 projects programmed for construction with Sub-Basins 4 and 5.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins; therefore, would not impact identified IRP sites. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.7 SUB-BASIN 6 (FIGURES 17 AND 18)

5.7.1 Overview of Alternatives 1 and 2

Alternative 1 has two projects within this subbasin. Alternative 2 has no projects within SubBasin 6. The following is an overview of Alternative 1 only. Projects within this sub-basin are listed in Table 14 are shown in relationship to the entire sub-basin in Figure 17 with additional site detail in Appendix B. No Alternative 1 project within Sub-Basin 6 straddles sub-basin boundaries. Alternative 2 locations for the two projects shown in Table 14 are in Sub-Basins 4 and 5 for Project 06-01 and Sub-Basin 7 for Project 06-02 and their impacts are discussed under those sub-basins.

There are four demolitions (Total: 20,015 SF) scheduled within this sub-basin. Some of these demolitions are programmed in order to facilitate the implementation of the projects listed in Table 14.

Table 14 Installation MILCON and SRM Projects in Sub-Basin 6, Alternative 1			
Project # FTEV # Description			
06-01	01-5007	Consolidated Club	
06-02	02-3011	Mission Planning Facility	

The purpose and need for each project listed in Table 14 is summarized in Table 3 in Section 2.0. Detailed project justifications and additional construction information can be found in DD Form 1391 information in Appendix C.

The general overall impact of all projects within Sub-Basin 6 is calculated in Table 15 and analyzed in the following paragraphs.

Table 15 Impact Summary for Sub-Basin 6, Alternative 1			
Impact Area	Result		
Trees Removed	23 Trees		
Within a Storm Surge Area	2 Projects (06-01 and 06-02)		
New Impervious Surface	2 Facilities; 190,372 SF (4.37 Acres)		
Demolitions	4 Facilities; 20,015 SF (0.46 Acres)		

Although there are only two projects currently planned within Sub-Basin 6, both are substantial, requiring approximately 190,372 SF of combined building footprint. The Consolidated Club (Project 06-01) would be a large complex with associated parking located between the Mission Planning Center and Santa Rosa Sound. Other projects located in Sub-Basin 6 that may have some cumulative impact in association with Alternative 1 are four demolitions, clearing approximately 20,015 SF (0.46 acres) of land. Individually and cumulatively, Alternative 1 projects in this subbasin would be expected to have no impact on the following issue/resource areas: floodplains, wetlands, RTE species, hazardous materials, or IRP sites.

5.7.2 Analysis

5.7.2.1 Groundwater

Alternative 1—There are two proposed projects in Sub-Basin 6 that involve the construction of new facilities—which would require connections to the potable water system and which would increase demand on the Floridan Aquifer. None of the individual Alternative 1 projects within Sub-Basin 6 would directly impact recharge of the Floridan Aguifer. Although there would be an increase to impervious surface area (190,372 SF) associated with the Mission Planning Center and the Consolidated Club project, this increase would be insignificant in terms of changing the recharge rate of the shallow Sand and Gravel Aquifer since the project locations are so close to Santa Rosa Sound. The cumulative impacts resulting from the demolitions in this sub-basin would slightly lessen the amount of water used in the area in the short-term, but the long-term

impacts would roughly be equal to present amounts of water used in this sub-basin. The proposed Mission Planning Facility (Project 06-02) would minimally change the overall installation demand for potable water. Cumulative impacts would be a long-term, minor, adverse impact on potable water demand from the Floridan Aquifer.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact potable water sources for Hurlburt or increase impervious surface area thus reducing Sand and Gravel Aquifer recharge. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this subbasin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.7.2.2 Surface Water and Storm Water

- **Alternative 1**—All project locations within Sub-Basin 6 drain untreated storm water by sheet flow directly into Santa Rosa Sound. Individually, the projects within these subbasins would result in short-term, minor, adverse impacts on storm water quality due to potential increases in erosion from construction activities associated with each project and the planned four demolitions. These impacts would result from initial construction activities and subsequent increased impervious surface areas (190,372 SF) associated with the buildings, parking areas and road access. The removal of 23 existing trees in Sub-Basin 6 would also contribute to minor, short-term increases in storm water runoff from the project site due to a loss of ground cover that could lead to increased erosion of topsoil.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within Sub-Basin 6 and, therefore, would not impact existing surface water or storm water flow. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.





5.7.2.3 Storm Surge Areas

Alternative 1—The projects listed in Sub-Basin 6 are located in storm surge areas. Both the Mission Planning Facility (Project 06-02) and the Consolidated Club (Project 06-01) are located in Category 3 and 4 storm surge areas. A Category 3 and higher hurricane can flood any Soundside area south of US 98.

Cumulatively, the removal of buildings in Sub-Basin 6, which occur in Storm Surge Areas 3 and 4 would result in a long-term, minor, beneficial impact in terms of reducing the possibility of future storm damage to installation facilities.

There have been no recorded cases of hurricanes in the Hurlburt vicinity that have generated storm surge elevations impacting Storm Surge Areas 4 or 5 (Woolpert, Inc., 2001). Storm Surge Areas 1, 2, and 3 were last impacted during Hurricane Ivan in September 2004, which produced storm surges of 6 to 9 feet at Hurlburt (National Hurricane Center, 2005). Individually, and depending on the severity of future hurricanes, these projects could potentially have a long-term, minor to major, adverse impact in terms increasing the possibility of future potential damage from hurricane storm surges. Coastal Protection Act guidance would need to be used in designing and constructing the Consolidated Club (Project 06-01), Mission Planning Facility (Project 06-02), and other projects (Project 07-03) as shown in Sub-Basin 6. but discussed in other sub-basins, in order to insure consistency with the Florida CZM Program.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins or with storm surge areas. With the No-Action Alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.7.2.4 General Flora and Fauna

- **Alternative 1—**As with most of the General Plan projects, the projects in Sub-Basin 6 are already within Hurlburt Field's developed areas or in areas scheduled for redevelopment. Therefore, there are few impacts on flora and fauna. Site clearing would result in removal of a total of 23 trees for all Sub-Basin 6 projects and would be covered by the installation's tree replacement policy. Many of these trees are mature live oaks. Replanting trees would mitigate some of the habitat impacts in the long-term. Cumulatively, the demolition of four facilities in Sub-Basin 6 would not impact existing flora and fauna. Projects comprising Alternative 1 individually and cumulatively would have short- and longterm minor adverse impacts on trees and urban wildlife habitat (nest trees, landscape plantings around quarters, and so on).
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins and, therefore, would not impact flora and fauna on Hurlburt. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this subbasin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.7.2.5 Archaeological Resources

• Alternative 1—Both projects in this subbasin (Projects 06-01 and 06-02) are located near or within high probability areas for archaeological resources. This is particularly true for the new Mission Planning Center. As such, the project areas should be checked for the presence of archaeological resources prior to construction activities. Any archaeological resources would be recovered prior to construction. Should any human remains be located, the provisions of the NAGPRA must be followed.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within Sub-Basin 6; therefore, would not impact potential archaeological resources. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this subbasin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.7.2.6 Infrastructure and Traffic

Alternative 1—All utilities are already available in the area to support the Mission Planning Center and Consolidated Club. The construction of new structures in Sub-Basin 6 would change roadway configurations, traffic patterns, and traffic levels in this portion of the installation. The construction of the Mission Planning Center would increase traffic and parking congestion in this area. The roadways leading to Sub-Basin 6 already experience some congestion (particularly US 98); however, associated improvements to the main gate and other nearby roadways not located in this sub-basin may help to alleviate traffic concerns. Nevertheless, Alternative 1 would have an individual, longterm, moderate, adverse impact on traffic and parking congestion in Hurlburt Field's Soundside area.

Finally, proposed improvements in roadway geometry and surfacing in the Soundside area east of the marina located in Sub-Basin 4 would have a cumulative, long-term, minor beneficial impact on improving traffic flow in this area.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within these sub-basins, and, therefore, would not impact existing utilities or traffic movements. With this alternative those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.7.2.7 Regulated Special, Solid, and Hazardous Materials and Wastes

Alternative 1—Substantial solid waste generation (along with the potential for some special and/or hazardous waste generation) would occur as part construction of the two projects in Sub-Basin 6 and/or the demolition of four existing structures in the vicinity of the planned Mission Planning Center and Consolidated Club. Demolition wastes as well as 23 trees and other vegetation cleared from the construction sites would need to be disposed of in local landfills. Any mitigation required for asbestos-containing materials (ACM), leadbased paint, or other contaminants prior to planned demolitions in this sub-basin would be handled through individual contracts. Individually and cumulatively, the Alternative 1 projects in Sub-Basin 6 would have a short-term, minor, adverse impact on solid waste generation.


None of the Alternative 1 projects would involve construction of facilities specifically for hazardous materials/waste use or storage.


No-Action Alternative—The No-Action Alternative would result in no new facility construction within Sub-Basin 6, and, therefore, would not impact solid and hazardous waste generation. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.8 SUB-BASIN 7 (FIGURES 19 AND 20)

5.8.1 Overview of Alternative 1

Alternative 1 projects within this sub-basin are listed in Table 16, and are shown in relationship to the entire sub-basin in Figure 19 with additional site detail in Appendix B.





The purpose and need for each project listed in Table 16 is summarized in Table 3 in Section 2.0. Detailed project justifications and additional construction information can be found in DD Form 1391 information in Appendix C.

Table 16				
ins		IILCON and SRM Projects Basin 7, Alternative 1		
Project #	FTEV#	Description		
07-01	043020	ADAL Command Post		
07-02	962010	Realign O'Neil Avenue/Install Traffic Signal		
07-03A	033022	AT/FP Main Gate and Soundside Access Control Facilities		
07-03B	033022	AT/FP Main Gate and Soundside Access Control Facilities		
07-04	045003	Family Camping Facility (24 Sites)		
07-05	043006	SOF Weapons and Release Systems Shop		
07-06	033017	SOF Special Tactics Group Headquarters Facility		
07-07	043000	Refueling Vehicle Maintenance Facility		
07-08	033004	Vehicle Operations Administration Facility		
07-09	963008	SOF Maintenance Operations Squadron Facility		
07-10	993011	Base Roadway Improvements		
07-11	993033	Squadron Operations Facility, 6 SOS		

The total impact of all 12 projects within Sub-Basin 7 for Alternative 1 is summarized in Table 17 and analyzed in the following paragraphs.

T	Table 17				
Impact Summary for Sub-Basin 7, Alternative 1					
Impact Area	Result				
IRP Impacts	Impacts to Sites SS-122, ST-68, ST-123, SD-189, OT-43, and LF-20 for a Total of 120, 880 SF Impacted Area (2.77 Acres)				
Q/D Arc	5,169.8 SF (0.12 Acres)				
AICUZ Impacts	10 Projects are Within the 65 db Contour				
Trees Removed	41 Trees				
Within a Storm-Surge Area	2 Projects (07-03B and 07- 04); Categories 3, 4, and 5				
Hazardous Materials	Future SAP for Projects 07- 05, 07-07, 07-08 and 07-09				
New Impervious Surface	12 Facilities (675,762 SF)				
Demolitions	19 Facilities (114,245 SF)				

Actions having potential cumulative impacts and located within Sub-Basin 7 include 19 demolitions totaling 114,245 SF of building footprint. Individually and cumulatively future General Plan projects in this sub-basin would have no impact on the following issue/resource areas: floodplains, un-permitted wetlands,

permitted wetlands, RTE species, cultural resources, and air emissions.

5.8.2 Overview of Alternative 2

Alternative 2 projects within this sub-basin are listed in Table 18, and are shown in relationship to the entire sub-basin in Figure 20 with additional site detail in Appendix B.

Table 18				
Installation MILCON and SRM Projects				
Project #	FTEV#	Basin 7, Alternative 2 Description		
02-01	021001	Construct Outdoor Recreation		
02-01	021001	Center, 16 SVS		
04-01	041072	Add to Fitness Center, Building		
		90517		
04-03	043016	Supply Warehouse		
04-05	033021	16th Contracting Squadron		
		Facility		
06-02	023011	Mission Planning Center		
07-01	043020	ADAL Command Post		
07-02	962010	Realign O'Neil Avenue/Install		
		Traffic Signal		
07-04	045003	Family Camping Facility		
07-06	033017	STG Headquarters Facility		
07-07	043000	Refueling Vehicle Maintenance		
		Facility		
07-08	033004	Vehicle Operations Maintenance		
		Facility		
07-09	963008	ADAL Maintenance Operations		
		Squadron Facility		
07-10	993011	Base Roadway Improvements		
07-11	993033	Squadron Operations Facility, 6 SOS		
11-08	043005	SOF Squadron Ops TALON II		

The purpose and need for each project listed in Table 18 is summarized in Table 3 in Section 2.0. Detailed project justifications and additional construction information can be found in DD Form 1391 information in Appendix C.

Projects that will be analyzed in other subbasins, but have some area located in Sub-Basin 7 include Projects 07-10A and 11-08. Refer to Section 5.5 and 5.12.

The total impact of all 15 projects within Sub-Basin 7 for Alternative 2 is summarized in Table 19 and analyzed in the following paragraphs.

Individually and cumulatively future General Plan projects in this sub-basin would have no impact on the following issue/resource areas: permitted wetlands, cultural resources, and air emissions.

Table 19 Impact Summary for Sub-Basin 7, Alternative 2			
Impact Area	Result		
Floodplain Impacts	1,152.5 SF (0.03 Acres)		
Un-Permitted Wetland	16,527 SF (0.38 Acres)		
Impacts	,		
RTE Habitat	31,400 (0.72 Acres)		
IRP Impacts	Impacts to Sites SS-122, SS-		
	124, SS-125, ST-68, ST-123,		
	and ST 126 for a Total of		
	34,493 SF Impacted Area		
	(0.79 Acres)		
Q/D Arc	14,261 SF (0.33 Acres)		
AICUZ Impacts	14 Projects are Within the 65		
-	db Contour		
Trees Removed	11 Trees		
Within a Storm-Surge	5 Projects (02-01, 04-05, 06-		
Area	02, 07-04, and 07-08);		
	Categories 2, 3, 4, and 5		
Hazardous Materials	Future SAP for Projects 07-		
	07, 07-08, and 07-09		
New Impervious Surface	15 Facilities (542,833 SF)		
Demolitions	4 Facilities (161,231 SF)		

5.8.3 Analysis

5.8.3.1 Groundwater

- Alternative 1—There are twelve Alternative 1 projects in Sub-Basin 7 that involve the construction of new facilities. These new facilities will require potable water from Hurlburt Field's water system, which draws water from the Floridan Aquifer. Any landscape irrigation water needs would be met using water from the shallow Sand and Gravel Aquifer. Cumulatively, demolition of 19 facilities within Sub-Basin 7 would reduce the demand for potable water in this area and have a short-term, very minor, beneficial impact by temporarily reducing potable water demand and reducing the impervious surface area in this sub-basin thus contributing to Sand and Gravel aguifer recharge. Nevertheless, there would be long-term, minor, adverse impacts on potable water demand in this sub-basin due to an increase in facilities-associated personnel. There would also be long-term, minor, adverse impacts to the Sand and Gravel aquifer from the overall net increase in impervious surface area (561,517 SF or 13 acres) within Sub-Basin 7.
- Alternative 2—There are 15 proposed Alternative 2 projects in Sub-Basin 7 that involve the construction of new facilities. These new facilities will require potable water from Hurlburt Field's water system,

- which draws water from the Floridan Aquifer. Any landscape irrigation water needs would be met using water from the shallow Sand and Gravel Aguifer. Cumulatively, demolition of four facilities within Sub-Basin 7 would reduce the demand for potable water in this area and have a short-term, very minor, beneficial impact by temporarily reducing potable water demand and reducing the impervious surface area in this sub-basin thus contributing to Sand and Gravel Aquifer recharge. Nevertheless, there would be long-term, minor, adverse impacts on potable water demand in this sub-basin due to an increase in facilities-associated personnel. There would also be long-term, minor, adverse impacts to the Sand and Gravel Aquifer.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact existing groundwater conditions. Those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.2 Surface Water and Storm Water

Alternative 1—The majority of the projects located within Sub-Basin 7 drain to the South Central and Southeast Regional Storm Water Ponds south of US 98 and, in times of high flow, discharge to Santa Rosa Sound through Outfall 4 (Sub-Basins 4 and 5) and Outfall 3 (Sub-Basin 7). The 19 demolitions scheduled for this sub-basin are likely to have a short-term, minor, beneficial impact by reducing storm water quantity due to a temporary reduction in impervious surface area in this sub-basin. Individually, the Alternative 1 projects within this subbasin would result in short-term, negligible to minor, adverse impacts on storm water quality due to potential increases in erosion from demolition and construction activities associated with each project. However, most of this construction is planned to occur in previously developed areas of the base with established storm water drainage, which will help minimize some of the storm water impacts. Cumulatively, when taking into consideration the planned demolition of 19

existing facilities, the Alternative 1 projects would have a short-term and long-term, minor, adverse impact in terms of increasing storm water quantity and decreasing storm water quality within this sub-basin as a result of an increase in overall impervious surface area. The overall increase in impervious surface area within this sub-basin as a result of Alternative 1 projects would be 561,517 SF (12.89 Acres).

- Alternative 2—The majority of the projects located within Sub-Basin 7 drain to the South Central and Southeast Regional Storm Water Ponds south of US 98 and, in times of high flow, discharge to Santa Rosa Sound through Outfall 4 (Sub-Basins 4 and 5) and Outfall 3 (Sub-Basin 7). The four demolitions scheduled for this sub-basin are likely to have a short-term, minor, beneficial impact by reducing storm water quantity due to a temporary reduction in impervious surface area in this sub-basin. Individually, the projects within this sub-basin would result in short-term, nealigible to minor. adverse impacts on storm water quality due to potential increases in erosion from demolition and construction activities associated with each project. However, most of this construction is planned to occur in previously developed areas of the base with established storm water drainage, which will help minimize some of the storm water impacts. Cumulatively, when taking into consideration the planned demolition of 19 existing facilities. Alternative 2 projects would have a short-term and long-term, minor, adverse impact in terms of increasing storm water quantity and decreasing storm water quality within this sub-basin as a result of an increase in overall impervious surface area. The overall increase in impervious surface area within this sub-basin as a result of Alternative 2 projects would be 323,016 SF (7.41 Acres).
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact existing storm water and surface water conditions. However, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and

could initially compromise the mission requirements for Hurlburt Field.

5.8.3.3 Floodplains

- Alternative 1—There are no Alternative 1 projects within Sub-Basin 7 that would impact designated floodplain areas.
- Alternative 2—Project 07-04 would impact 1,152 SF (0.03 acres) of floodplain in Sub-Basin 7. However, the impacts to floodplains and flood capacity from this project would be negligible.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact existing floodplain conditions. Those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.4 Storm Surge Areas

Alternative 1—There are two projects in Sub-Basin 7 located within a storm surge area (Projects 07-03B and 07-04). Project 07-03B is located in Storm Surge Categories 3, 4, and 5. Project 07-04 is located in Storm Surge Categories 4 and 5.

Storm Surge Categories 1, 2, and 3 were last impacted during Hurricane Ivan in 2004, which produced storm surges of 6 to 9 feet at Hurlburt (National Hurricane Center, 2005). Historically, there have not been storm surges reaching the Categories 4 or 5 levels at Hurlburt. Therefore the Alternative 1 projects scheduled for construction within this sub-basin and within Categories 4 and 5 areas would generally be located beyond any flooding associated with hurricane storm surges. Generally, construction of these structures to withstand hurricane-force winds would be more important than concerns with flooding from storm surge.

Cumulative impacts resulting from the demolition actions that will take place in Sub-Basin 7 would have a long-term, minor, beneficial impact on the prevention of structural damage from storm surges.

Alternative 2—There are five Alternative 2 projects in Sub-Basin 7 located within a storm surge area (Projects 02-01, 04-05, 06-02, 07-04, and 07-08). Project 02-01 is located in storm surge Categories 4 and 5. Project 04-05 is located in Storm Surge Category 5. Project 06-02 is located in storm surge Categories 4 and 5. Project 07-03 occurs within storm surge areas in Sub-Basin 8, where the analysis can be found. Project 07-04 is located in Storm Surge Categories 3, 4, and 5. Project 07-08 is located in storm surge Category 5.

Storm Surge Categories 1, 2, and 3 areas were last impacted during Hurricane Ivan in 2004, which produced storm surges of 6 to 9 feet at Hurlburt (National Hurricane Center, 2005). Historically, there have not been storm surges reaching the Categories 4 or 5 levels at Hurlburt. Therefore the Alternative 2 projects scheduled for construction within this sub-basin in Categories 4 and 5 would generally be located beyond any flooding associated with hurricane storm surges. Generally, construction of these structures to withstand hurricane-force winds would be more important than concerns with flooding from storm surge.

Cumulative impacts resulting from the demolition actions that will take place in Sub-Basin 7 would have a long-term, minor, beneficial impact on the prevention of structural damage from storm surges.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact or be impacted by storm surges. Those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.5 Wetlands

- Alternative 1—This alternative would result in no impacts to permitted or un-permitted wetlands within Sub-Basin 7, and there are no other actions that would contribute to cumulative impacts to wetlands.
- Alternative 2—Project 07-01 would result in 15,292 SF (0.35 acre) of wetland impacts not currently covered by Section 404 permits (i.e., un-permitted). Project 07-04 would result in 336 SF (0.008 acre) of un-permitted wetland impacts, while Project 07-08 would result in 899 SF (0.02 acre) of un-permitted wetland impacts. These potentially impacted areas total 0.38 acre and together are well below the 0.50 acre requiring an Individual permit, but would require a nationwide permit and mitigation. Overall, these projects would have a short-term and long-term very minor, adverse impact on freshwater wetlands on Hurlburt Field. Cumulative impacts would be identical as there are no other projects having wetland impacts in this sub-basin.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact or be impacted by storm surge. Those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.6 General Flora and Fauna

Alternative 1—As with other sub-basins, projects already within Hurlburt Field's developed areas or in areas scheduled for redevelopment would result in few impacts on flora and fauna. The majority of impacts would result from site clearing involving 41 trees in Sub-Basin 7. The individual project having the most impact on landscape trees is Project 07-06, which would impact 18 trees, many of which are mature live oaks. The project having the next greatest impact on tree take is Project 07-03B, which would impact roughly 16 trees in Sub-Basin 7. The only other project that would remove trees is Project 07-09, which would impact seven trees.

Cumulatively, the demolition of 19 facilities in Sub-Basin 7 along with Alternative 1 projects would not directly impact existing flora and fauna, due to the developed nature of the sub-basin. Projects comprising the Alternative 1 would have a short-term, minor adverse, impact on urban wildlife habitat (nest trees, landscape plantings around quarters, and so on). Following the replanting of trees there would be a long-term, minor, beneficial impact on the flora and fauna in Sub-Basin 7.

• Alternative 2—This alternative would result in the removal of 11 trees in Sub-Basin 7. The individual project having the most impact on landscape trees is Project 07-01, which would impact 5 trees. Project 07-09 would impact 4 trees, while Projects 07-06 and 07-07 would each impact 1 tree.

Cumulatively, the demolition of four facilities in Sub-Basin 7 in combination with Alternative 2 projects would not impact existing flora and fauna, due to the developed nature of the sub-basin. Projects comprising Alternative 2 would have a short-term, minor adverse, impact on urban wildlife habitat (nest trees, landscape plantings around quarters, and so on). Following the replanting of trees there would be a long-term, minor, beneficial impact on the flora and fauna in Sub-Basin 7.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact existing vegetation or urban wildlife habitat. With the No-Action Alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.7 Archaeological Resources

Alternative 1—There are no known areas of archaeological significance that would be affected by Alternative 1 projects proposed for Sub-Basin 7. The southern portion of Sub-Basin 7, however, contains some areas of high potential for archaeological sites with several known sites that are potentially eligible for listing on the National Register. Project 07-04 is located in or near any identified high probability areas and may be checked for the presence of archaeological resources prior to construction activities, and any resources recovered. Should any human remains be located, the provisions of the NAGPRA must be followed.

- Alternative 2—There are no known areas of archaeological significance that would be affected by projects proposed in Sub-Basin 7. The southern portion of Sub-Basin 7, however, contains some areas of high potential for archaeological sites with several known sites that are potentially eligible for listing on the National Register. Projects 02-01, 06-02, and 07-04 are located in or near any identified high probability areas and may be checked for the presence of archaeological resources prior to construction activities, and any resources recovered. Should any human remains be located, the provisions of the NAGPRA must be followed.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact archaeological resources. With the No-Action Alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.8 Infrastructure and Traffic

• Alternative 1—Utility systems in Sub-Basin 7 would likely have the same level of load, despite the addition of 12 new facilities and 4 existing facilities scheduled for additions/ alternations. This is due to the demolition of 19 existing facilities. The demolition of these facilities (and subsequent availability of utility infrastructure) would likely facilitate utility connections service for new facilities proposed as part of Alternative 1. There would likely be short-term disturbances to local utility service during construction periods, but the long-term impacts would be minor and beneficial.

Roadway improvements and changes within Sub-Basin 7 will be substantial given that there are planned base roadway

improvements (Project 07-10B) and the realignment of O'Neil Avenue (Project 07-02) located in this sub-basin, as well as a reconfiguration of the main gate (Project 07-03B). The planned base roadway improvements (Project 07-10B) are located within a heavily developed portion of Sub-Basin 7 and will provide greater access and ease traffic flow within this area. The realignment of O'Neil Avenue (Project 07-02) would reconfigure O'Neil with Terry Avenue at the intersection of Terry Avenue and Independence Road. This would provide left turn lanes on Independence Road to O'Neil Avenue and eliminate an existing unsafe turning condition. Project 07-03B (Main Gate and Soundside Access Control Facilities) would have a long-term, moderate, beneficial impact on traffic flow through this area, which would also benefit traffic on adjacent portions of US 98 where, under current conditions, rush-hour backups are standard. This project is required to provide an adequate entry control point for personnel, visitors, and most delivery vehicles. Reconfiguring the main gate area would help prevent unauthorized access to Hurlburt Field as well as maximize vehicular flow. The current main gate facility does not meet the criteria of the DoD Force Protection Program. The Preferred Alternative would have short-term, minor, adverse impacts on the installation, due to traffic disruptions during the construction period. However, there would be an individual and cumulative. long-term. moderate, beneficial impacts on traffic patterns and traffic flow on Hurlburt.

• Alternative 2—Utility systems in Sub-Basin 7 would likely have the same level of load, despite the addition of 12 new facilities and 4 existing facilities scheduled for additions/ alternations. This is due to the demolition of four existing facilities. The demolition of these facilities (and subsequent availability of utility infrastructure) would likely facilitate utility connections service for new facilities proposed for Alternative 2. There would likely be short-term disturbances local utility service during construction periods, but the long-term impacts would be minor and beneficial.

Roadway improvements and changes within Sub-Basin 7 from Alternative 2 projects

would be substantial given that there are planned base roadway improvements (Project 07-10) and the realignment of O'Neil Avenue/Installation of traffic signal (Project 07-02) located in this sub-basin. The reconfiguration of the main gate (Project 07-03B), however, will be located in Sub-Basin 8, where the analysis of impacts can be found. The planned base roadway improvements (Project 07-10) are located within a heavily developed portion of Sub-Basin 7 and will provide greater access and ease traffic flow within this area. The Project 07-02 would install a traffic signal at the intersection of Terry Avenue and Independence Road. This would improve the safety of this intersection, although leftturn lanes would not be provided. The improvements in traffic flow and traffic signalization would result in a long-term, moderate, beneficial impact to traffic safety on the installation. Alternative 2 would have short-term, minor, adverse impacts on the base, due to traffic disruptions during the construction period. However, there would be an individual and cumulative, long-term, moderate, beneficial impacts on traffic patterns and traffic flow on Hurlburt.

No-Action Alternative—The No-Action Alternative would result in no new facility or roadway construction within this sub-basin and, therefore, would not impact existing infrastructure or traffic conditions. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.9 Regulated Special, Solid, and Hazardous Materials and Wastes

• Alternative 1—Substantial solid waste generation (along with the potential for some special and/or hazardous waste generation) would occur as part of the construction of the 12 Alternative 1 projects in Sub-Basin 7 and/or the demolition of 19 other facilities. Some additional solid waste generation would be associated with site clearing and grubbing for some of the new facilities included in Alternative 1. Most of this waste would be trees and other vegetation cleared from the sites prior to construction.

Individually, Alternative 1 projects in Sub-Basin 7 would have a short-term, minor, adverse impact on solid waste generation during demolition and construction activities. Cumulatively, Alternative 1 and the demolition of 19 existing facilities would have a short-term, moderate, adverse impact on solid waste generation. Alternative 1 projects planned for this subbasin, which include fuel handling (Project 07-07) would be constructed to strict standards complying with containment requirements and included in the installation's SPCC Plan update as the projects are completed. None of the proposed Alternative 1 projects would involve construction of facilities specifically for hazardous materials/waste use or storage.

- Alternative 2—Substantial solid waste generation (along with the potential for some special and/or hazardous waste generation) would occur as part of the construction of the 12 Alternative 2 projects in Sub-Basin 7 and/or the demolition of six other facilities within this sub-basin. Some additional solid waste generation would be associated with site clearing and grubbing for some of the new facilities included in Alternative 2. Most of this waste would be trees and other vegetation cleared from the sites prior to construction. Individually, Alternative 2 projects in Sub-Basin 7 would have a shortterm, minor, adverse impact on solid waste generation during the demolition and construction activities. Cumulatively, Alternative 2 and the demolition of 19 existing facilities would have a short-term. moderate, adverse impact on solid waste generation. The Alternative 1 projects planned for this sub-basin, which include fuel handling (07-07) would be constructed to strict standards complying with containment requirements and included in the installations SPCC Plan update as the projects are completed. None of the proposed Alternative 2 projects would involve construction of facilities specifically for hazardous materials/waste use or storage.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact existing

conditions regarding regulated special, solid, and hazardous materials and wastes. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.10 IRP Sites

- Alternative 1—Six Alternative 1 projects have the potential to impact IRP sites within Sub-Basin 7. Total potential IRP site area within Sub-Basin 7 that could be impacted is 120,879.6 SF impacted area (2.77 acres). Specific information by project is given below:
 - Project 07-05 (SOF Weapons and Release Systems Shop)—Impacting 28,733.2 SF of IRP site ST-123.
 - Project 07-07 Refueling Vehicle Maintenance Facility—Impacting 4,357 SF of IRP site ST-68; 537.1 SF of IRP site ST-123; and 1,401.4 SF of IRP site SD-189.
 - Project 07-08 (Vehicle Operations Administration Facility)—Impacting 21.8 SF of IRP site OT-43.
 - Project 07-09 (SOF Maintenance Operations Squadron Facility)— Impacting 26,590.1 SF of IRP ST-123. The demolition of existing structures as well as construction of the new facility will impact existing IRP site ST-123.
 - Project 07-10B (Base Roadway Improvements)—Impacting 23,621.3 SF of IRP site LF-20; 9,701.2 SF of IRP site SD-189; 2,944.7 SF of IRP site ST-123; and 4,255 SF of IRP site SS-122.
 - Project 07-11 (Squadron Operations facility 6 SOS)—Impacting 18,716.3 SF of IRP site ST-123. T.

All Alternative 1 projects potentially impacting contaminated sites would be coordinated through the IRP Program Manager to insure consistency with the Management Action Plan and to avoid disturbance of subsurface contamination. LUC agreements would also be checked prior to detailed facility design to insure compatibility under existing legal agreements. The Alternative 1 projects within Sub-Basin 7 would have a long-term,

minor, adverse impact on contaminated sites in terms of potential future problems with both contamination and with site cleanup.

- Alternative 2—Five Alternative 2 projects have the potential to impact IRP sites within Sub-Basin 7 total potential IRP site area within Sub-Basin 7 that could be impacted isf 34,493 SF impacted area (0.79 acres). Specific information by project is given below:
 - Project 04-03 (Supply Warehouse)— Impacting 1,233 SF of IRP site SS-125.
 - Project 07-07 (Refueling Vehicle Maintenance Facility)—Impacting 9,929 SF of IRP site SS-124.
 - Project 07-09 (SOF Maintenance Operations Squadron Facility)— Impacting 1,649 SF of IRP ST-126. The demolition of existing structures as well as construction of the new facility will impact existing IRP site ST-126.
 - Project 07-10 (Base Roadway Improvements)—Impacting 1,713 SF of IRP site ST-68; 4,259 SF of IRP site SS-122; and 9,140 SF of IRP site ST-123.
 - Project 07-11 (Squadron Operations facility 6 SOS)—Impacting 6,750 SF of IRP site ST-123.

All Alternative 2 projects potentially impacting contaminated sites would be coordinated through the IRP Program Manager to insure consistency with the Management Action Plan and to avoid disturbance of subsurface contamination. LUC agreements would also be checked prior to detailed facility design to insure compatibility under existing legal agreements. Alternative 2 projects would have a long-term, minor, adverse impact on contaminated sites in terms of potential future problems with both contamination and with site clean-up.

No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact existing IRP sites. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.11 Endangered Species Habitat

- Alternative 1—The proposed projects for Alternative 1 would result in no impacts to such species or their habitats. There would also be no cumulative impacts associated with this alternative.
- **Alternative 2—**Hurlburt Field includes habitat for numerous threatened and endangered species, primarily within the undeveloped portions of the installation. Proposed Alternative 2 projects would result in 31,400 SF (0.72 acres) of impact to breeding habitat for the least tern (Sterna antillarum). Project 04-03 would result in the demolition of Building 90710 which provides nesting habitat (i.e., flat gravel roof) for this state threatened species. A minimum of 23 nests are known on the roof of this existing structure, which is located approximately one mile north of Santa Rosa Sound-the primary foraging area for this bird that consumes only live fish as its prey. Previously, the least tern was known to inhabit the rooftops of some installation buildings immediately adjacent to Santa Rosa Sound. The replacement building. however, would provide 379,996 SF (8.72 acres) of suitable breeding/nesting habitat. This bird species is opportunistic in the selection of nesting sites and somewhat tolerable of adjacent human activity. Therefore, the proposed project would result in short-term, moderate, adverse impacts but long-term, moderate, beneficial impacts to this species. There are no other projects in this sub-basin that are known to contribute to cumulative impacts.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not any threatened or endangered species or their habitat. With this alternative, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.8.3.12 Q/D Arc

- Alternative 1—Alternative 1 would result in 5,169.8 SF (0.12 acres) of Q/D Arc (i.e., airfield stand-off) being encroached upon by Project 07-10B. However, since this project is a roadway and not a habitable facility, there would be no impact.
- Alternative 2—Alternative 2 would result in 14,261 SF (0.33 acres) of Q/D Arc (i.e., airfield stand-off) being encroached upon by Project 07-11. Consequently, this alternative would result in an individual and cumulative long-term, minor, adverse impact because of its encroachment upon the Q/D zone.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact existing Q/D arcs. With this alternative those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.9 SUB-BASIN 8 (FIGURES 21 AND 22)

5.9.1 Overview of Alternative 1

Alternative 1 projects within this sub-basin are listed in Table 20 and are shown in relationship to the entire sub-basin in Figure 21 with additional site detail in Appendix B.

Table 20 Installation MILCON and SRM Projects in Sub-Basin 8, Alternative 1				
Project #	FTEV #	Description		
08-01	00-3009	Vehicle Maintenance Facility		
08-02	02-3005	RED HORSE Mobility and		
		Training Facility (823 RHS)		
08-03	00-5004	Shoppette Facility		
08-04	99-3013	Construct Dormitory (144 pn)		
		Eastside		
08-05	00-3023	Eastside Fitness Center		
08-06	03-3013	Widen Independence Road		
08-07	30-3018	AFLD Waiver, Independence		
		Road		
08-08	04-3011	SOF UAV Squadron Operations		
		Facility		
08-09	04-3012	SOF UAV Maintenance		
		Hangar/Parking Apron		

The purpose and need for each project listed in Table 20 is summarized in Table 3 in Section 2.0. Detailed project justifications and additional construction information can be found in DD Form 1391 information in Appendix C.

There is one project partially within this subbasin that will be analyzed as one of the Sub-Basin 11 projects, Project 11-13 (Hydrant Fueling System).

The total impact of all nine projects within Sub-Basin 8 is calculated in Table 21 and analyzed in the following paragraphs.

Table 21 Impact Summary for Sub-Basin 8, Alternative 1				
Impact Area	Result			
Floodplain Impacts	4167.8 SF			
Structures within a Q/D Zone	1 (8,815.9 SF)			
AICUZ Impacts	5 Projects are Within the 65 db Contour			
Within a Storm-Surge Area	1 Project (FTEV: 03-3018, Category 3; 18,642, Category 4; 43,140, and Category 5; 46,137 SF)			
New Impervious Surface	9 Facilities (564,371 SF)			
Demolitions	9 Facilities (44,293 SF)			

Potential cumulative impacts associated with other projects located in Sub-Basin 8 include nine structure demolitions totaling 44,293 SF of footprint. These demolitions are addressed here only in terms of their cumulative impact. Alternative 1 projects within Sub-Basin 8 would have no impact on wetlands, RTE habitat, cultural resources, IRP sites, significant landscape trees, or existing air permitting.

5.9.2 Overview of Alternative 2

Alternative 2 projects within this sub-basin are listed in Table 22, and are shown in relationship to the entire sub-basin in Figure 22 with additional site detail in Appendix B.

The purpose and need for each project listed in Table 22 is summarized in Table 3 in Section 2.0. Detailed project justifications and additional construction information can be found in DD Form 1391 information in Appendix C.

Table 22					
Ins	Installation MILCON and SRM Projects				
	in Sub-E	Basin 8, Alternative 2			
Project #	Project # FTEV # Description				
07-03	03-3022	AT/FP Main Gate and Soundside Access control Facilities			
08-02	02-3005	RED HORSE Mobility and Training Facility (823 RHS)			
08-04	99-3013	Construct Dormitory (144 pn) Eastside			
08-05	00-3023	Eastside Fitness Center			
08-06	03-3013	Widen Independence Road			
08-07	03-3018	AFLD Waiver, Alter Independence Road			
11.01	03-1049	Fill/Clear Wetlands, Helicopter Landing Pad			
11-11	04-3004	SOF C-130 Aircraft Apron			
11-22	04-3014	SOF CV-22 Aircraft Parking Apron			

The total impact of all nine projects within Sub-Basin 8 is calculated in Table 23.

Table 23 Impact Summary for Sub-Basin 8, Alternative 2				
Impact Area	Result			
Floodplain Impacts	129,223 SF			
Un-permitted Wetland Impacts	45,523 SF			
Cultural Resources	4,021 SF			
Structure Within a Q/D Arc	2 (514,086 SF)			
AICUZ Impacts	8 Projects are Within the 65db contour			
Significant landscape trees removed	17			
Within a Storm Surge Area	2 Projects (Category 3, 78,792 SF; Category 4, 105,208 SF, and Category 5, 145,991 SF)			
New Impervious Surface	9 Facilities (1,335,033 SF)			
Demolitions	2 (53,445 SF)			

5.9.3 Analysis

5.9.3.1 Groundwater

Alternative 1—There are nine proposed projects in Sub-Basin 8 that involve the construction of new facilities or roadway modifications. These new facilities would require potable water from Hurlburt Field's water system, which draws water from the Floridan aquifer. Any landscape irrigation water needs would be met using water from the shallow Sand and Gravel aquifer. Demolition of nine facilities within Sub-Basin 8 would remove approximately 44,293 SF of impervious surface area. However, the programmed construction of the nine new facilities in this sub-basin would add 564,371

SF of impervious surface area resulting in a net increase of 520,078 SF or almost 12 acres of impervious surface in Sub-Basin 8. The planned new facilities in this sub-basin would also accommodate an increased population of both permanently assigned and transient personnel resulting in an increase in potable water use. Alternative 1 implementation would result in a long-term, minor, adverse impact on potable water demand in this sub-basin (and on Hurlburt in general) due to an increase in facilities and associated additional personnel. There would also be long-term, minor, adverse impacts to the Sand and Gravel aguifer as a result of increases in impervious surface area both from facilities and from an expansion of the aircraft maintenance hanger/parking apron as well as alterations to Independence Road.

Alternative 2—There are nine proposed projects in Sub-Basin 8 that involve the construction of new facilities or roadway modifications. These new facilities would require potable water from Hurlburt Field's water system, which draws water from the Floridan aguifer. Any landscape irrigation water needs would be met using water from the shallow Sand and Gravel aguifer. Two facilities would be demolished with implementation of this alternative resulting in a removal of 53,445 SF of impervious surface. However, programmed construction of the nine new facilities/roadway improvements in this sub-basin would add 1,335,033 SF or almost 31 acres of impervious surface in Sub-Basin 8. The planned new facilities in this sub-basin would also accommodate an increased population of both permanently assigned and transient personnel resulting in an increase in potable water use. Alternative 2 implementation would result in a long-term, minor, adverse impact on potable water demand in this sub-basin (and on Hurlburt in general) due to an increase in facilities and associated additional personnel. There would also be long-term, minor to moderate, adverse impacts to the Sand and Gravel aguifer as a result of increases in impervious surface area both from facilities and from an expansion of the aircraft maintenance hanger/parking aprons, a helicopter landing pad, alterations to Independence Road and

Alternative 1 Figure 21 Surface Water Sub-Basin 8 717-11 **Sub-Basin 10** 11-18 Sub-Basin 11 **Environmental Assessment** Hurlburt Field 11-<mark>03</mark> Hurlburt Field, Florida 11-09 11-10 Sub-Basin 9 Legend 11-12 Sub-Basin Projects Other EA Projects 08-09 Installation Boundary **Existing Structures Demolitions** 08-08 Airfield Clear Zone 07-05 Shoreline 07-01 Sub-Basin 8 Surface Water **7**07-09 Sub-Basin 7 Sub-Basin 8 08-03 07-10B 07-08 08-04 07-02 07-03B 08-07 Sub-Basin 8 Sub-Basin 6 07-04 Sub-Basin 7 Not to Scale

Alternative 2 Figure 22 Surface Water Sub-Basin 8 11-04 11-16 & 11-17 08-08 08-09 Sub-Basin 10 11-19 08-01 Sub-Basin 1 11-13 11-20 **Environmental Assessment** Hurlburt Field 11-21 & 04-07 Hurlburt Field, Florida Sub-Basin 9 Legend 04-03 Sub-Basin Projects 08-03 04-01 Other EA Projects Installation Boundary **Existing Structures** 11-08 **Demolitions** <u></u>407-06 Airfield Clear Zone 07-09 07-11 Shoreline Surface Water 07-01 Sub-Basin 8 07-07 07-02 08-04 04-05 Sub-Basin 4 06-02 02-01 Sub-Basin 6 Sub-Basin 8 Sub-Basin 7 Not to Scale

- construction of an alternative gate connecting US 98 with Loop Road.
- No-Action Alternative—The No-Action Alternative would result in no new facilities although some demolitions may still take place. Generally, the No-Action Alternative would have a negligible impact on both the use/withdrawal of groundwater from the Floridan Aquifer and Sand and Gravel Aquifer.

5.9.3.2 Surface Water and Storm Water

Alternative 1—The majority of the Alternative projects located within Sub-Basin 8 flows into a north/south drainage ditch originating between the flightline and the taxiway, passing through a culvert beneath US 98 and discharges at Outfall 002 into Santa Rosa Sound. Excess storm water passing through the north/south drainage ditch flows through an overflow channel into the East Regional Storm Water Pond just to the southeast of the airfield. Sheet flow north of US 98 is generally directed to the north/south drainage ditch. Sheet flow south of US 98 flows either into the ditch or directly into Santa Rosa Sound. There are no Alternative 1 projects south of U.S. 98 in Sub-Basin 8 that would drain by sheet flow directly into Santa Rosa Sound. The nine demolitions scheduled for this sub-basin would reduce impervious surface area somewhat, but the impact on storm water runoff would be negated by the planned 564,371 SF of new impervious surface area associated with planned new construction.

Individually, the projects within this subbasin would result in short-term, negligible to minor, adverse impacts on storm water quality due to potential increases in erosion from demolition and construction activities associated with each project as well as an overall increase in impervious surface area in this sub-basin. However, most of this construction is planned to occur in previously developed areas of the installation with established storm water drainage, which would help minimize some of the storm water impacts. Cumulatively, when taking into consideration the planned demolition of two existing facilities in this sub-basin; Alternative 1 projects would have a short-term and long-term, minor, adverse

- impact on storm water quality and quantity within this sub-basin. The estimated total long-term increase in impervious surface area within this sub-basin is 520,078 SF or 12 acres.
- Alternative 2—As discussed under Section 5.8.3.1. Alternative 2 projects would result in considerably more construction and impervious surfaces (around 31 total acres) than would Alternative 1 (about 12 total acres). As a result there would be more than twice the amount of long-term, cumulative storm water runoff generated by Alternative 2 as there would be by Alternative 1. There would also be more soil disturbance and wetland disturbance during construction of Alternative 2 projects. This would result in greater temporary soil erosion and sedimentation than would construction of Alternative 1 projects. Impacts on existing wetlands (see Section 5.9.3.5) would also reduce storm water absorptive capacity within this sub-basin and further increase storm water runoff. The planned aircraft parking and helicopter landing pad projects would also contribute to increased potential contaminate levels associated with oils. greases, and metals in storm water runoff. Cumulatively, implementation of this alternative would result in short-term and long-term moderate adverse impacts on both the quantity and quality of storm water run off.
- No-Action Alternative—The No-Action Alternative would maintain the status quo in terms of facilities within Sub-Basin 8. Some demolitions may still occur as would routine facility maintenance and minor interior upgrades. However, the No-Action Alternative would essentially have no impact on storm water or surface waters beyond the present conditions within the sub-basin. Those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.9.3.3 Floodplains

Alternative 1—The only Alternative 1
 project impacting any 100-year floodplain is
 Project 08-01 (RED HORSE Vehicle
 Maintenance Facility). Although the

floodplain impacts of this project are actually in Sub-Basin 11 near Brimms Road the project will be analyzed here. There are 4,167.8 SF of floodplain impacts (out of a 32,496 SF building) associated with this project. Other facilities are already located within this floodplain area. This project would result in a long-term minor adverse impact to the floodplain. The floodplain impact involves only a portion of a building mostly outside of the floodplain and since the building site must be located within the existing RED HORSE area for operational purposes A Finding of No Practicable Alternative would be required.

- Alternative 2—No Alternative 2 projects would impact floodplains.
- No-Action Alternative—The No-Action Alternative would result in no new facility construction within this sub-basin and, therefore, would not impact floodplains. Those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.9.3.4 Storm Surge Areas

- Alternative 1—Sub-Basin 8 covers areas that could be impacted by a possible storm surge of Categories 1 through 5, however there is only one Alternative 1 project in Sub-Basin 8 located within storm surge areas (Projects 03-3018 (AFLD Waiver, Alter Independence Road), A Category 3 storm surge could flood a small segment of realigned Independence Road southeast of the flightline (Appendix B). A Category 4 or 5 storm surge would flood most of the southern portion of realigned Independence Road. However, since there has been no historic record of storm surges reaching areas on Hurlburt beyond Category 3, any adverse impacts, particularly to a roadway. would probably be of short duration and minor.
- Alternative 2—There are two Alternative 2 projects in Sub-Basin 8 that could be impacted by Category 3 or higher storm surges. Both of these projects are roadway realignments or new alignments (Project 07-03 and Project 08-07). The Main Gate

- project would include structures such as ID check gate houses, entry control/vehicle inspection center, metal canopy over three lanes of traffic, quard booths, overwatch area with shelter and a K-9 facility in addition to the new roadway surfaces. It would require a Category 3 storm surge to begin directly impacting either of these projects. A Category 3 storm surge could also flood across major portions of US 98 adjacent to Hurlburt and could result in its temporary closing and lack of access to the relocated Main Gate. Generally, both roadway-related projects in Alternative 2 could be moderately adversely affected by Category 3 and higher storm surges. However, the adverse effects would normally be of short duration.
- No-Action Alternative—The No-Action Alternative would not result in any additional facilities, including roadways being constructed within Sub-Basin 8. The problems and needs as outlined under the DD Forms 1391 for projects within this subbasin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.9.3.5 Wetlands

- Alternative 1—There are no Alternative 1
 projects that would either individually or
 cumulatively impact existing wetlands within
 Sub-Basin 8.
- **Alternative 2—**Three projects within Alternative 2 would impact wetlands not currently covered by Section 404/401 permits. These projects include 07-03 (AT/FP Main Gate and Soundside Access Control Facilities), 08-04 (Construct Eastside Dormitory), and 08-07 (AFLD Waiver, Alter Independence Road). Individually or cumulatively, these projects would require permits for the USACE and the FDEP prior to construction. Mitigation would also be required for these projects. Individually and cumulatively, Alternative 2 would have a short-term and long-term, moderate, adverse impact on wetlands within Sub-Basin 8.
- No-Action Alternative—With no planned facility construction, the No-Action Alternative would have no impacts on

wetlands existing within Sub-Basin 8. No Section 404 permit or mitigation would be required.

5.9.3.6 General Flora and Fauna

- Alternative 1—Alternative 1 projects are already within Hurlburt Field's developed areas or in areas scheduled for redevelopment. Therefore, there are few impacts on flora and fauna. Whatever very minor impacts on trees and other developed landscape elements that might result from implementation of Alternative 1 would be mitigated by replanting and new landscaping. This alternative could have a short-term negligible to minor adverse impact on urban wildlife habitat (nest trees, landscape plantings around quarters, and so on). However, following the replanting of trees there would be a long-term, negligible to minor, beneficial impact on the flora and fauna in Sub-Basin 8.
- Alternative 2—Alternative 2 projects would result in the removal of approximately 17 total landscape trees of significant size. Additionally, the projects impacting wetlands as indicated in Section 6.8.2.5 above would also impact wetland species of plants and animals. Although no RTE species are known from these wetland areas, a more thorough survey for these species may be necessary in order to meet Section 404/401 permit requirements prior to construction. Individually and cumulatively, Alternative 2 projects would have a long-term, minor to moderate, adverse impact on flora and fauna within Sub-Basin 8.
- No-Action Alternative—The No-Action Alternative would have no impacts on flora or fauna in Sub-Basin 8. Those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.9.3.7 Archaeological Resources

 Alternative 1—Alternative 1 projects will not impact any known archaeological sites within Sub-Basin 8.

- Alternative 2—Project 07-03 would impact recorded archaeological site 80K474. However, this Archaic prehistoric site was determined as ineligible for listing on the National Register of Historic Places (USACE, 1994). No other Alternative 2 project would impact any known archaeological site. Therefore, Alternative 2 implementation would have a negligible impact on archaeological resources.
- No-Action Alternative—The No-Action
 Alternative would involve no new facility or roadway work within Sub-Basin 7.

 Therefore, there would be no impacts on archaeological resources from the No-Action Alternative.

5.9.3.8 Infrastructure and Traffic

Alternative 1—Utility systems in Sub-Basin 8 would likely have somewhat higher demands due to the addition of nine new facilities/roadway projects. However, Sub-Basin 8 is within a highly developed area of Hurlburt Field with relatively easy access to existing utilities. This area of the installation also is reported to not yet be at full capacity for any of the major utility systems. There will likely be short-term disturbances in the utility infrastructure system during construction periods, but the long-term impacts will be minor and beneficial.

Roadway improvements and changes within Sub-Basin 8 are likely to be extensive for this area given the planned improvements to Independence Road. There are two projects scheduled for this area that deal with Independence Road. Project 08-07 (AFLD Waiver, Alter Independence Road) will alter Independence Road moving out of the airfield Primary Surface zone and project 03-3013 will widen parts of Independence Road southwest of Loop Road. The proposed action would have short-term, minor, adverse impacts due to traffic disruptions during the construction period. However, there would be an individual and cumulative. long-term, moderate, beneficial impact on traffic patterns and traffic flow on Hurlburt.

 Alternative 2—Utility systems in Sub-Basin 8 would likely have somewhat higher demands due to the addition of nine new facilities/roadway projects. However, SubBasin 8 is within a highly developed area of Hurlburt Field with relatively easy access to existing utilities. This area of the installation also is reported to not yet be at full capacity for any of the major utility systems. There will likely be short-term disturbances in the utility infrastructure system during construction periods, but the long-term impacts will be minor and beneficial.

Project 07-03 would create a major change in installation access from US 98. This project would shift installation access to from the west side of the airfield the east side of the airfield with Loop Road serving as a major connector to Independence Road and the rest of the installation. Major shifts in traffic circulation as well as the creation of potential capacity and safety problems could arise from this proposed change unless additional roadway changes were made. The project individually and all Alternative project cumulatively would have a long-term, moderate, adverse impact on traffic circulation and safety within Sub-Basin 8 and throughout the installation.

No-Action Alternative—The No-Action Alternative would result in no modification of existing utility systems or roadways within Sub-Basin 8. This could lead to increased congestion on local roadways over the longterm. There would be no anticipated impact on utilities.

5.9.3.9 Regulated Special, Solid, and Hazardous Materials and Wastes

Alternative 1—Solid waste generation (along with the potential for some special and hazardous waste generation) would occur as part construction of the nine projects in Sub-Basin 8 and/or the demolition of four facilities. Waste generation would be associated construction material debris; demolition debris; and site clearing, grubbing and grading. Limited amounts of special wastes and hazardous materials and wastes associated with construction and demolition could include asbestos-containing materials and leadbased paint in demolition debris as well as solvents, fuels, pesticides and other materials potentially used in constructionrelated activities. Individually, Alternative 1 would have a short-term, negligible to minor,

adverse impact on special, solid, and hazardous wastes and hazardous materials generation during the demolition and construction of the proposed projects. None of the Alternative 1 projects would involve construction of facilities specifically for hazardous materials/waste use or storage. However, Project 08-01 (RED HORSE Vehicle Maintenance Facility) and Project 08-09 (SOF UAV Maintenance Hangar/ Parking Apron) would be a designated satellite accumulation point locations under the Hurlburt Hazardous Waste Management Plan.

Alternative 2—Solid waste generation (along with the potential for some special and hazardous waste generation) would occur as part construction of the nine projects in Sub-Basin 8 and/or the demolition of two facilities. Waste generation would be associated construction material debris; demolition debris; and site clearing, grubbing and grading. Limited amounts of special wastes and hazardous materials and wastes associated with construction and demolition could include asbestoscontaining materials and lead-based paint in demolition debris as well as solvents, fuels, pesticides and other materials potentially used in construction-related activities. The increased amount of paving associated with several Alternative 2 projects, e.g. Projects 07-03 (AT/FP Main Gate and Soundside Access Control Facilities), 11-02 (Fill/Clear Wetlands, Helicopter Landing Pad), 11-11 (SOF C-130 Aircraft Apron), and 11-22 (SOF CV-22 Aircraft Parking Apron) would increase the use of petroleum-based materials and associated waste material generation. Individually, Alternative 2 projects would have a short-term, moderate, adverse impact on special, solid, and hazardous wastes and hazardous materials generation during the demolition and construction of the proposed projects. None of the Alternative 2 projects would involve construction of facilities specifically for hazardous materials/waste use or storage. However, Project11-02 (Helicopter Landing Pad), Project 11-11 (SOF C-130 Aircraft Apron, and Project 11-22 (SOF CV-22 Aircraft Parking Apron) would be designated satellite accumulation point locations under the Hurlburt Hazardous Waste Management Plan.

 No-Action Alternative—The No-Action Alternative would involve no new construction. However demolitions could still take place resulting in some very limited generation of special wastes such as asbestos-containing materials and leadbased paint.

5.10 SUB-BASIN 9 (FIGURES 23 AND 24)

5.10.1 Overview of Alternative 1

There are no Alternative 1 projects sited within Sub-Basin 9.

5.10.2 Overview of Alternative 2

The only Alternative 2 project sited within Sub-Basin 9 is Project 08-03 (Shoppette Facility, East Side), which is shown in relationship to the entire sub-basin in Figure 24 with additional site detail in Appendix B. The Alternative 1 location for this project is in Sub-Basin 8.

The purpose and need for this project is given in Table 3 in Section 2.0. Detailed project justification and additional construction information can be found in DD Form 1391 information in Appendix C.

The only resource area that would be impacted would be the removal of nine mature trees. There would be no impacts from this project on floodplains; wetlands; rare, threatened, or endangered species; cultural resources, IRP site, or hazardous materials/hazardous wastes. The site would not be impacted by storm surge Q/D Arcs, or flightline noise.

There are no demolitions or other planned actions within this sub-basin that need to be considered in cumulative impact analysis.

5.10.3 Analysis

Alternative 2—Project 08-03 (Shoppette Facility, East Side) would add approximately 26, 611 SF of additional impervious surface area to Sub-Basin 9. This project would also result in removal of a number of significantly sized landscape trees currently on the proposed construction site. This project would have negligible to extremely minor impacts on recharge of the Sand and Gravel Aquifer and on surface water/storm water quantity and quality.

 No-Action Alternative—The No-Action Alternative would have no impacts within Sub-Basin 9.

5.11 SUB-BASIN 10 (FIGURES 25 AND 26)

5.11.1 Overview of Alternative 1

Alternative 1 has no projects within Sub-Basin

5.11.2 Overview of Alternative 2

Alternative 2 has two projects within this subbasin. Alternative 2 projects within this subbasin are listed in Table 24 and are shown in relationship to the entire sub-basin in Figure 26 with additional site detail in Appendix B. The Alternative 1 locations for the two projects shown in Table 24 are in Sub-Basins 4 and 8 for Projects 04-04 and 08-01, respectively; and their impacts are discussed under those two subbasins.

Table 24 Installation MILCON and SRM Projects in Sub-Basin 10, Alternative 2				
Project # FTEV # Description				
04-04	99-3036	Child Development Center		
08-01 00-3009 Vehicle Maintenance Facility				

The purpose and need for these projects is given in Table 3 in Section 2.0. Detailed project justification can be found in DD Form 1391 in Appendix C. The total impact of the projects within Sub-Basin 10 is calculated in Table 25 and analyzed in the following paragraphs.

There are no demolitions associated with the Alternative 2 projects in this sub-basin, and therefore, no cumulative impacts from localized demolition.

Table 25 Impact Summary for Sub-Basin 10, Alternative 2			
Impact Area Result			
Floodplain Impacts	32,496 SF (0.74 Acre)		
Un-permitted Wetland	32,380 SF (0.74 Acre)		
Impacts			
New Impervious Surface	2 Facilities (108,942 SF)		
Demolitions	None		

General Plan projects in this sub-basin would have no impact on the following issue/resource areas: permitted wetland areas, RTE species, cultural resources, IRP sites, tree removal, and air emissions.

5.11.3 Analysis

Since there are no Alternative 1 projects located within Sub-Basin 10, the following analyses are limited to potential impacts only from Alternative 2 and the No-Action Alternative.

5.11.3.1 Groundwater

• Alternative 2—The new Alternative 2 facilities would require potable water from Hurlburt Field's water system, which draws water from the Floridan Aquifer. Any landscape irrigation water needs would be met using water from the shallow Sand and Gravel Aquifer.

There are no planned demolitions of existing facilities or reductions in working populations within Sub-Basin 10 that would reduce the demand on potable water over the short or long-term. However, there would be long-term, minor, adverse impacts on potable water demand as a result of the new facilities. There would also be long-term, minor, adverse impacts to the Sand and Gravel aquifer as a result of increases in impervious surface area both from the new facilities.

No-Action Alternative—The No-Action Alternative would not construct any new facilities in Sub-Basin 10. The existing vehicle maintenance center and child development center would be continue to be used and maintained as needed, neither of which are located in Sub-Basin 10. Therefore, there would be no impact on groundwater in this sub-basin.

5.11.3.2 Surface Water and Storm Water


• Alternative 2—The majority of the projects located within Sub-Basin 10 drain southward to areas off-installation along with the northern half of the eastern installation perimeter. Eventually, storm water from this area drain into Cinco Bayou. There are no planned demolitions for Alternative 2 within

Sub-Basin 10. Individually, the projects within this sub-basin would result in shortterm, negligible to minor, adverse impacts on storm water quality due to potential increases in erosion from construction activities associated with each project, as well as an overall increase in impervious surface area in this sub-basin. However, most of this construction is planned to occur in previously developed areas of the installation with established storm water drainage, which will help minimize some of the storm water impacts. Cumulatively, the projects listed as part of Alternative 2 would have a short-term and long-term, minor, adverse impact on storm water quality and quantity within this sub-basin. Estimated change increase in impervious surface area within this sub-basin is 108,942 SF or about 2.5 acres.


No-Action Alternative—The No-Action Alternative would involve no construction of new facilities. This would have a long-term, minor, beneficial impact on storm water runoff. However, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.


5.11.3.3 Floodplains

- Alternative 2—The only project within Sub-Basin 10 that is partially or entirely within an identified floodplain is Project 08-01 (Vehicle Maintenance Facility). Project 08-01 would impact 32,496 SF of 100-year floodplain. This project would result in a long-term minor adverse impact to the floodplain. A Finding of No Practicable Alternative (FONPA) would need to be approved prior to construction of this building.
- No-Action Alternative—The No-Action Alternative would involve no new construction within Sub-Basin 10. The existing facilities on the installation would continue to be used. However, those problems and needs as outlined under the DD Forms 1391 for projects within this subbasin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.









5.11.3.4 Wetlands

- Alternative 2—Project 08-01 (Vehicle Maintenance Facility) would result in 32,380 SF (0.74 acre) of un-permitted wetland impacts. This amount of wetland impact would require an Individual Section 404 permit and mitigation. Overall, this project would have a short-term and long-term, minor, adverse impact on freshwater wetlands on Hurlburt Field.
- No-Action Alternative—The No-Action Alternative would involve no new construction within Sub-Basin 10, and therefore there would be no wetland impacts and no Section 404 permit or mitigation would be required. However, those problems and needs as outlined under the DD Forms 1391 for projects within this subbasin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.11.3.5 General Flora and Fauna

- Alternative 2—There are few impacts on flora and fauna since both Alternative 2 projects in this sub-basin are in highly developed areas of the installation. It is not anticipated that any trees would need to be removed as part of implementing this alternative. Alternative 2 projects in Sub-Basin 10 would have a short-term, negligible adverse impact on urban wildlife habitat (nest trees, landscape plantings around guarters, and so on) during construction. Following construction, there would be a long-term, negligible, beneficial impact on the flora and fauna in Sub-Basin 10 from additional landscaping using native plant materials.
- No-Action Alternative—The No-Action Alternative would not involve any facility construction within Sub-Basin 10. Therefore, there would be no impacts on flora or fauna. However, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.11.3.6 Infrastructure and Traffic

Alternative 2—Utility systems in Sub-Basin 10 would likely have a slightly higher load due to the addition of two new facilities. However, the location of Sub-Basin 10 is on the edge of the highly developed area of Hurlburt Field with relatively easy access to existing utilities. This area of the installation also is reported to not yet be at full capacity for any of the major utility systems, and the new facilities would be constructed using energy efficient and water-saving systems. There will likely be short-term disturbances in the utility infrastructure system during construction periods, but the long-term impacts will be minor and beneficial.

There are no planned roadway changes associated with this alternative, however, the implementation of the two new facilities would increase traffic in the general area. Alternative 2 projects would have short-term, minor, adverse impacts on installation traffic and utility systems during the construction period. However, there would be an individual and cumulative, long-term, minor, beneficial impact on utility usage on Hurlburt, but the lack of roadway improvements would have a long-term, minor, adverse impact on traffic circulation.

No-Action Alternative—The No-Action Alternative would not involve any facility construction within Sub-Basin 10. Therefore, there would be no impacts on infrastructure and traffic. However, those problems and needs as outlined under the DD Forms 1391 for projects within this sub-basin (see Appendix C) would tend to increase and could initially compromise the mission requirements for Hurlburt Field.

5.11.3.7 Regulated Special, Solid, and Hazardous Materials and Wastes

• Alternative 2—Some solid waste generation (along with the potential for some special and hazardous waste generation) would occur as part of construction of the two projects in Sub-Basin 10. Some additional solid waste generation would be associated with site clearing and grubbing for some of the new facilities included in this alternative. Most of this waste would be vegetation cleared from the sites prior to construction. Individually, Alternative 2 in Sub-Basin 10 would have a short-term, negligible to minor, adverse impact on solid waste generation during the construction of the proposed projects. The construction of Project 08-01 (Vehicle Maintenance Facility) would be the future site of a satellite hazardous waste accumulation point. Alternative 2 Sub-Basin 10 projects would have a short-term, moderate, adverse impact on solid waste generation.

No-Action Alternative—The No-Action Alternative would not generate substantial amounts of solid waste, as no facilities would be constructed in Sub-Basin 10. However, the problems and needs as outlined under the DD Forms 1391 associated with projects in this sub-basin (see Appendix C) would increase over time and could have a long-term negative impact on the mission of Hurlburt Field.

5.12 SUB-BASIN 11 (FIGURES 27 AND 28)

5.12.1 Overview of Alternative 1

Projects associated with Alternative 1 within this sub-basin are listed in Table 26 and are shown in relationship to the entire Sub-Basin 11 in Figure 27 and in additional site detail in Appendix B.


Sub-Basin 11 contains the largest number of projects included in the General Plan. The purpose and need for each Alternative 1 project listed in Table 26 is summarized in Table 3 in Section 2.0. Detailed project justifications and additional construction information can be found in DD Form 1391 information in Appendix C.

The only project located in Sub-Basin 11 that will be analyzed in another sub-basin is Project 04-07 (SOF JSOU Library/Education Center Complex/Language Lab Ph 3), which is described in Sub-Basin 4. Project 11-13 (Hydrant Fueling System) contains some area within Sub-Basin 8, but is analyzed in this section.

The total impact of all 22 projects within Sub-Basin 11 is calculated in Table 27 and analyzed in the following paragraphs in the analysis portion of this section.

Table 26 Installation MILCON and SRM Projects					
	in Sub-Basin 11, Alternative 1				
Project #	FTEV#	Description			
11-01	04-5002	Construct Workbays at Auto			
		Hobby Shop; Bldg. 90612			
11-02	03-1049	Fill/Clear Wetlands, Helicopter			
		Landing Pad			
11-03	94-3001	ADAL Security Forces Operations			
11-04	97-3006	SOF Engine Maintenance and			
		Storage Shop			
11-05	97-3018	Fire Crash/Rescue Station			
11-06	01-3021	25 th Intelligence Squadron			
44.07	00 0044	Operations Facility			
11-07	03-3014	Realign Cruz Avenue			
11-08	04-3005	SOF Squadron Operations Tallon			
44.00	00.0040				
11-09	02-3010	Addition to Visiting Quarters			
11-10	02-3013	ADAL USAFSOS Facility			
11-11	04-3004	SOF C-130 Aircraft Apron			
11-12	04-3007	SOF Survival Equipment Shop			
11-13	97-3016	Hydrant Fueling System			
11-14	03-3006	Visiting Officers Quarters			
11-15	03-3015	Realign Cruz Avenue-Phase II			
11-16	04-3008	SOF DASH-21 Maintenance			
11-17	04.0000	Facility			
11-17	04-3009	SOF Maintenance Storage			
11-18	04-3010	Facility SOF C-130 Talon II Maintenance			
11-16	04-3010				
11-19	96-3012	Hanger Squadron Operations Facility, 18			
11-19	96-3012	FLTS			
11-20	97-3009	Operations Group/Operations			
		Plans Facility			
11-21	02-3014	SOF JSOU Headquarters Facility,			
		Phase II			
11-22	04-3014	SOF CV-22 Aircraft Parking			
		Apron			

Table 27				
Impact Summary for Sub-Basin 11, Alternative 1				
Impact Area	Result			
Floodplain Impacts	286,430 SF (6.57 acres)			
Un-permitted Wetland	32,590.6 SF (0.75 acres)			
Impacts				
Permitted Wetland	136,388 SF (3.13 Acre)			
Impacts				
IRP Impacts	11 Projects Will Impact IRP			
	Areas for a Total of 103,224.8			
	SF (2.37 acre)			
AICUZ Impacts	22 Projects are Within the 65			
	db Contour			
Q/D Arc Stand-off	292,565.6 SF (6.72 Acres)			
Distances	Must be in Stand-Off Areas			
Trees Removed	32 Trees			
Hazardous Materials	Future Satellite Accumulation			
	Points (SAP) for Projects 11-			
	01, 11-02, 11-04, 11-11, 11-			
	13, 11-16, 11-18, and 11-22			
Air Emission Permits	1 Project Will Need a			
	Modification to the Air			
	Emissions Permit (Project			
	11-13)			
New Impervious Surface	1,503,830 SF			
Demolitions	40 Facilities (238,719 SF)			



Alternative 2 Figure 28 Surface Water Sub-Basin 11 **Environmental Assessment** Hurlburt Field L . . Hurlburt Field, Florida **Sub-Basin 11** Legend Sub-Basin Projects Other EA Projects 11-16 & 11-17 **Sub-Basin 10** 80-80 N Installation Boundary 11-15 08-09 **Existing Structures Demolitions** Airfield Clear Zone 08-01 Shoreline Surface Water 11-20 Sub-Basin 11 11-06^N 11-21 & 04-07 **04-02** Sub-Båsin 🦻 04-03 08-02 08-03 06-01 08-06 Sub-Basin & 07-09 <u></u> 07-06 Sub-Basin 7 .07-10 08-05 08-07 07-02 07-03 Not to Scale 08-04

The total area (*i.e.*, new impervious surface) of all projects by Alternative 1 in Sub-Basin 11 is 1,503,830 SF or 34.52 acres. Other projects within Sub-Basin 11 (Alternative 1) not part of the General Plan but which could have cumulative impacts include 40 facility demolitions clearing approximately 238,719 SF (5.48 acres). These demolitions are programmed in order to facilitate the implementation of the projects. Individually and cumulatively future General Plan projects in this sub-basin would have no impact on the following issue/resource areas: storm-surge, RTE species, or cultural/archaeological resources.

5.12.2 Overview of Alternative 2

Projects within this sub-basin for Alternative 2 are listed in Table 28 which are shown in relationship to the entire Sub-Basin 11 in Figure 28 and in additional site detail in Appendix B.

		Table 28	
Installation MILCON and SRM Projects			
in Sub-Basin 11, Alternative 2			
Project #	FTEV#	Description	
04-06	97-3019	Airmen Leadership School	
07-05	04-3006	SOF Weapons and Release	
		Systems Shop	
08-08	04-3011	SOF UAV Squadron Operations	
		Facility	
08-09	04-3012	SOF UAV Maintenance Hanger/	
		Parking Apron	
11-01	04-5002	Construct workbays at Auto	
		Hobby Shop	
11-03	94-3001	ADAL Security Forces Operations	
11-04	97-3006	SOF Engine Maintenance and	
		Storage Shop	
11-05	97-3018	Fire Crash/Rescue Station	
11-06	01-3021	25 th Intelligence Squadron	
		Operations Facility	
11-07	03-3014	Realign Cruz Avenue	
11-10	02-3013	ADAL USAFSOS Facility	
11-12	04-3007	SOF Survival Equipment Shop	
11-13	97-3016	Hydrant Fueling System	
11-14	03-3006	Visiting Officer Quarters	
11-16 &	04-3008	SOF DASH 21 Maintenance	
11-17	& 04-	Facility and Storage Facility	
	3009		
11-18	04-3010	Talon II Maintenance Hanger	
11-19	96-3012	Squadron Operations Facility	
11-20	97-3009	Operations Group Plans Facility	
11-21	02-3004	SOF JSOU HQ Facility	

Projects located in Sub-Basin 11 that overlap with other sub-basins include Project 11-10. The purpose and need for each project listed in Table 3 in Section 2.0. Detailed project justifications and additional construction information can be found in DD Form 1391 information in Appendix C.

The total impact of all 19 Alternative 2 projects within Sub-Basin 11 is calculated in Table 29 and analyzed in the following paragraphs in the analysis portion of this section.

Table 29 Impact Summary for Sub-Basin 11, Alternative 2		
Impact Area	Result	
Floodplains	635,696 SF (14.59 acres)	
Un-permitted Wetlands	1,013,994 SF (23.28 acres)	
IRP Sites	8 projects will Impact IRP Areas for a Total of 159,838 SF (3.67 acres)	
Q/D Arc Stand-off	124 SF (0.003 acres) must be	
Distances	in stand-off areas	
AICUZ	17	
Trees Removed	13	
RTE Habitat	39,950 SF (0.92 acres)	
Hazardous Materials	Future SAP for 07-05, 08-09, 11-01, 11-04, 11-13, 11-16, 11-17, and 11-18.	
Air Emissions Permits	1 project will need a modification to the air emissions permit (11-13)	
New Impervious Surface	1,924,031 SF	
Demolitions	12 Facilities (57,820.8 SF)	

The total area (*i.e.*, new impervious surface) of all projects by Alternative 2 in Sub-Basin 11 is 1,924,031 SF (44.17 acres). Other projects within Sub-Basin 11(Alternative 2) not part of the General Plan but which could have cumulative impacts include 12 facility demolitions clearing approximately 57,820.8 SF (1.33 acres). Some of these demolitions are programmed in order to facilitate the implementation of the projects. Individually and cumulatively, future General Plan projects in this sub-basin would have no impact on the following issue/resource areas: storm surge, permitted wetland areas, or cultural/archaeological resources.

5.12.3 Analysis

5.12.3.1 Groundwater

Alternative 1—There are 13 proposed projects in Sub-Basin 11 that involve the construction of new facilities requiring connection to the potable water system and which would add to demand on the Floridan Aquifer. There are also three additions to existing buildings programmed. Although some of the new facility demand would be offset by the facilities scheduled for closure and demolition within this sub-basin, construction of all of the facilities proposed in the General Plan would have an overall long-term, very minor, adverse impact on

- groundwater supplies from the Floridan Aquifer. The increase in impervious surface area of approximately 1,265,111 SF (29.04 acres) within this sub-basin (specifically addition of an aircraft parking apron, helicopter landing pad, as well as alterations to Cruz Avenue) would also have a long-term, minor, adverse impact on recharge of the shallow Sand and Gravel Aquifer beneath Hurlburt. Cumulatively, the proposed actions in Sub-Basin 11 would have a long-term, minor, adverse impact on groundwater.
- Alternative 2—There are 16 projects in this alternative that involve the construction of new facilities that will likely require connection to the potable water system. There are also several additions to existing buildings programmed. The additional facilities would add to demand on the Floridan Aguifer. Although a portion of the new facility demand would be offset by those facilities scheduled for demolition, construction of all the proposed facilities would have a long-term, minor, adverse impact on groundwater supplies. In addition, the total increase in impervious surface area of approximately 1,083,499.7 SF (24.87 acres) from such projects as the aircraft parking apron and the realignment of Cruz Avenue would limit the recharge ability of the shallow Sand and Gravel Aquifer beneath Hurlburt. This would have a longterm, minor, adverse, impact on recharge in Sub-Basin 11. Cumulatively, the actions associated with Alternative 2 in Sub-Basin 11 would have a long-term, minor, adverse impact on groundwater.
- No-Action Alternative—The projects discussed for Sub-Basin 11 would not be pursued under this alternative. The impacts on the existing groundwater draw would be minimal and, in the long-term, beneficial, as planned demolitions would occur, but no new structures would be built that would further draw on potable water resources. Those problems and needs as outlined under the DD Forms 1391 related to projects in Sub-Basin 11 (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.12.3.2 Surface Water and Storm Water

- Alternative 1—The majority of the projects located within Sub-Basin 11 have no obvious storm water discharge outfalls. though Outfalls 1,8, 9, and 10 likely receive storm water from some projects. Considerable sheet flow is likely to enter East Bay Swamp to the north. A few projects drain to the East Regional Storm Water Pond just to the southeast of the airfield and, in times of high flow, discharge to Santa Rose Sound through Outfall 2 (Sub-Basin 8). The 40 demolitions scheduled for this sub-basin are likely to have a short-term, minor to moderate, beneficial impact on storm water due to a temporary reduction in impervious surface area in this area. However, the main airfield and addition of an aircraft parking apron, helicopter landing pad, and numerous facilities would negate the beneficial impact resulting from the demolitions. Additionally, most of this construction is planned to occur in previously developed areas of the installation with established storm water drainage, which will help minimize some of the storm water impacts. Cumulatively, when taking into consideration the planned demolition of 40 existing facilities and all of the projects within Alternative 1, there would be a long-term, minor, adverse impact on storm water quantity and quality within this sub-basin. There would be an overall increase of 1.265.111 SF (29.04 Acres) of impervious surface within Sub-Basin 11 as a result of planned Alternative 1 projects along with planned facility demolitions.
- Alternative 2—The majority of Alternative 2 projects located within Sub-Basin 11 have no obvious storm water discharge outfalls, though Outfalls 1,8, 9, and 10 likely receive storm water from some projects. Considerable sheet flow is likely to enter East Bay Swamp to the north. A few projects drain to the East Regional Storm Water Pond just to the southeast of the airfield and, in times of high flow, discharge to Santa Rose Sound through Outfall 2 (Sub-Basin 8). The 12 demolitions scheduled for this sub-basin are likely to have a short-term. minor, beneficial impact on storm water due to a temporary reduction in impervious surface area in this area. However, the addition of an aircraft parking apron and

numerous new facilities would negate the beneficial impact resulting from the demolitions. Additionally, most of this construction is planned to occur in previously developed areas of the installation with established storm water drainage, which will help minimize some of the storm water impacts. Cumulatively, when taking into consideration the planned demolition of 12 existing facilities and all of the projects within Alternative 2, there would be a long-term, minor, adverse impact on storm water quantity and quality within this sub-basin. There would be a net increase of 1,083,499.7 SF (24.87 acres) of impervious surface as a result of Alternative projects within Sub-Basin 11 also taking into account planned Sub-Basin 11 demolitions.

No-Action Alternative—The projects discussed for Sub-Basin 11 would not be pursued under this alternative. Consequently, no additional impervious surface would be added to Sub-Basin 11, including areas designated for vehicular or aircraft parking. This would result in a shortterm and long-term moderate, beneficial impact on storm water quantity (less impervious surface) and quality (less contaminants from new operations). The 40 planned demolitions set to occur in this subbasin would likely occur, resulting in an overall, long-term, decrease in impervious surface areas. However, those problems and needs as outlined under the DD Forms 1391 associated with the projects programmed within Sub-Basin 11 (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.12.3.3 Floodplains

Alternative 1—There are three projects associated with Alternative 1 that are partially or wholly within 100-year floodplains: Project 11-02 with 130,078.6 SF of impact; Project 11-13 with 27,128 SF of impact; and Project 11-22 with 129,223.4 SF of impact. There is a total of 286,430 SF (6.57 acres) of floodplain impacts associated with this alternative. In accordance with Executive Order 11988 and Air Force policy, each individual project sited within a floodplain will need to be evaluated and validated with a Finding of No Practicable

Alternative prior to construction. Overall, Alternative 1 would have a long-term, minor, adverse impact on floodplain capacity and functioning.

- Alternative 2—There are five projects as part of Alternative 2 that are located partially or wholly within the 100-year floodplain:
 - Project 08-08 with 23,000 SF of impact.
 - Project 08-09 with 383,605 SF of impact.
 - Project 11-05 with 120,329 SF of impact.
 - Project 11-13 with 39, 661 SF of impact.
 - Project 11-18 with 691,101 SF of impact.

There is a total of 1,257,696SF (28.87 acres) of floodplain impact associated with this alternative. In accordance with Executive Order 11988 and Air Force policy, each individual project sited within a floodplain will need to be evaluated and validated with a Finding of No Practicable Alternative prior to construction. Overall, Alternative 2 would have a long-term, minor, adverse impact on floodplain capacity and functioning.

No-Action Alternative—The projects discussed for Sub-Basin 11 would not be pursued under this alternative. This would entail no additional encroachments to the floodplain areas in Sub-Basin 11 and would not require additional permitting. Operationally, those problems and needs as outlined under the DD Forms 1391 associated with Sub-Basin 11 (see Appendix C) and the projects therein would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.12.3.4 Wetlands (Permitted and Un-Permitted)

Alternative 1—There are four projects that impact wetlands (One in permitted wetlands, three in un-permitted wetlands). Project 11-02 with 136,388 SF of permitted impacts; Project 11-04 with 6,755.6 SF of unpermitted impacts; Project 11-11 with 21,074.3 SF of un-permitted impacts; Project 11-13 with 4,760.7 SF of unpermitted wetland impacts. There is a total

of 168,957.6 SF (3.88 acres) of total wetland impacts associated with Alternative 1. The portion of wetland impact associated with project 11-02 is already permitted under Hurlburt Field's 10-year permit No. 17-0151212 dated May 5, 2000.

Individually and cumulatively, projects described as part of Alternative 1 would have short-term and long-term, moderate adverse impacts on wetlands in Sub-Basin 11. All un-permitted wetland impacts would need to be documented and approved by the USACE and the FDEP through the Section 404 and 401 permitting process.

- Alternative 2—There are 10 projects that impact wetlands (all 10 are in un-permitted wetland areas).
 - Project 04-06 with 8,533 SF of impact.
 - Project 04-07/11-21 with 43,066 SF of impact.
 - Project 08-08 with 36,496 SF of impacts.
 - Project 08-09 with 383,605 SF of impact.
 - Project 11-01 with 6,605 SF of impact.
 - Project 11-10 with 6,869 SF of impacts.
 - Project 11-13 with 33,529 SF of impact.
 - Project 11-14 with 3,831 SF of impact.
 - Project 11-18 with 446,560 SF of impacts.
 - Project 11-19 with 46,930 SF of impact.

There is a total of 1,013,994 SF (23.28 acres) of wetland impact associated with Alternative 2. None of the projects associated with this alternative have been previously permitted to impact wetlands.

Individually and cumulatively, projects described as part of Alternative 2 would have short-term and long-term, major adverse impacts on wetlands in Sub-Basin 11. All un-permitted wetland impacts would need to be documented and approved by the USACE and the FDEP through the Section 404 and 401 permitting process.

No Action Alternative—The projects discussed for Sub-Basin 11 would not be pursued under this alternative. This would entail no additional encroachments to the wetlands areas in Sub-Basin 11 and would not require additional permitting. However, it is likely that those wetland areas that currently are permitted to be filled would be filled in the future. Therefore, cumulatively, there would still be along-term, minor, adverse impact to wetlands in Sub-Basin 11. Operationally, those problems and needs as outlined under the DD Forms 1391 associated with Sub-Basin 11 (see Appendix C) would tend to increase and could eventually compromise the mission requirements for Hurlburt Field.

5.12.3.5 General Flora and Fauna

Alternative 1—As with most General Plan projects, the projects encompassed within Sub-Basin 11 are already within Hurlburt Field's developed areas or in areas scheduled for redevelopment. Therefore, for these projects there are few impacts on flora and fauna, except for impacts on mature trees. However, Project 11-13 would impact the natural vegetation in an undeveloped area of Hurlburt. Although no mature trees are known to be removed for this project: some clearing and grubbing of existing vegetative areas will be necessary resulting in a long-term, minor, adverse impact. Project 11-02 is covered under the Hurlburt 10-year wetland permit (see Section 5.12.3.4) and would result in the removal of wetland vegetative species. The other projects in this alternative would result in approximately 32 tree removals.

Cumulatively, the demolition of 40 facilities as part of this alternative in Sub-Basin 11 would not impact existing flora and fauna, due to the developed nature of the sub-basin. Overall, projects within Sub-Basin 11 would have short-term and long-term, moderate, adverse impacts on both landscape trees and on native forest species. Alternative 1 projects would have a short-term, very minor adverse impact on urban wildlife habitat (nest trees, landscape plantings around quarters, and so on), but they would have a short-term and long-term moderate adverse impact on wildlife habitat in undeveloped areas of the sub-basin.

 Alternative 2—The projects encompassed within Alternative 2 as part of Sub-Basin 11 are generally within the already developed areas of Hurlburt Field. As a result, there are few impacts on existing flora and fauna, with the exception of the removal of mature trees for some projects. However, Projects 08-08, 08-09, 11-13, and portions of 11-18 appear to be sited in areas that are not currently developed. Implementing these projects would entail some clearing and grubbing of existing vegetative areas that would result in short-term, minor to moderate, adverse impacts. There would be 13 trees removed as part of this alternative.

Cumulatively, the demolition of 12 facilities as part of this alternative in Sub-Basin 11 would not impact existing flora and fauna, due to the developed nature of the sub-basin. Overall, projects within Sub-Basin 11 would have short-term and long-term, moderate, adverse impact on both landscape trees and on native forest species. Alternative 2 projects would have a short-term, very minor adverse impact on urban wildlife habitat (nest trees, landscape plantings around quarters, and so on), but they would have a short-term and long-term moderate adverse impact on wildlife habitat in undeveloped areas of the sub-basin.

No-Action Alternative—The projects discussed for Sub-Basin 11 would not be pursued under the No-Action Alternative. There would be no additional or new construction under this alternative resulting in minimal impacts to existing flora and fauna. This would have a long-term, minor, beneficial impact on flora and fauna in the area, particularly to mature trees that would not be taken as a result of new construction. However, the problems and needs as outlined under the DD Forms 1391 (see Appendix C) would increase over time and could have a long-term impact on the mission of Hurlburt Field.

5.12.3.6 RTE Species

• Alternative 1—There are no projects located in Sub-Basin 11 associated with Alternative 1 that would impact RTE species or their habitats. However, the actions as part of this alternative could have an indirect, long-term, minor, adverse impact upon pine woods habitats used by the Bachman's sparrow (Aimophila aestivalis) that is more extensive on adjacent areas of Hurlburt Field and Eglin AFB.

- Alternative 2—Project 11-13 in Alternative 2 would impact 39,950 SF (0.92 acre) of RTE habitat. The proposed action would have a long-term, minor, adverse impact upon the Bachman's sparrow as its pine woods habitat is more extensive on adjacent areas of Eglin AFB.
- No-Action Alternative—No projects would be pursued under this alternative other than regular maintenance and upkeep of existing facilities. Consequently, no RTE species would be impacted. However, there could be a long-term, adverse impact over time to the operational capabilities of Hurlburt Field to meet the needs of its mission.

5.12.3.7 Infrastructure and Traffic

• Alternative 1—Utility systems in Sub-Basin 11 would likely have a slightly higher load due to the addition of new facilities with Alternative 1. However, most of the General Plan projects sited in Sub-Basin 11 are within highly developed areas of Hurlburt Field with relatively easy access to utilities.

There will likely be short-term disturbances in the utility system services during construction periods, but the long-term impacts would be minor and beneficial with increased availability and reliability

Roadway improvements and changes associated with Alternative 1 within Sub-Basin 11 are likely to be extensive for this area given the planned improvements to Cruz Avenue. There are two projects scheduled for this sub-basin that deal with Cruz Avenue. Both Projects 11-07 and 11-15 are planned to realign Cruz Avenue. This action would have short-term, minor, adverse impacts on the installation, due to traffic disruptions during the construction period. However, there would be an individual and cumulative, long-term, moderate, beneficial impact on traffic patterns and traffic circulation on Hurlburt from this work.

Project 11-13 also requires some roadway improvements to implement this project. Other roadway projects planned for Sub-Basin 11 include construction of a parking lot or associated roadway improvements for

Projects 11-04, 11-05, 11-06, 11-08, 11-10, and 11-20.

Roadway/parking improvements associated with Alternative 1 would have a short-term, minor to moderate, adverse impact on circulation during construction. However, there would be long-term beneficial impacts with the improved roadways and increase in parking areas from an operational standpoint.

Alternative 2—Utility systems as part of Alternative 2 would likely have a slightly higher load due to the addition of new facilities. However, most of the General Plan projects sited in Sub-Basin 11 area within highly developed areas of Hurlburt Field with relatively easy access to utilities. There will likely be short-term disturbances in the utility system services during construction periods, but the long-term impacts would be minor and beneficial with increased availability and reliability.

Roadway improvements and changes associated with Alternative 2 within Sub-Basin 11 are likely to be extensive for this area given the planned improvements to Cruz Avenue. There are two projects scheduled for this area that deal with Cruz Avenue. Both Projects 11-07 and 11-15 are planned to realign Cruz Avenue. This action would have short-term, minor, adverse impacts on the installation, due to traffic disruptions during the construction period. However, there would be an individual and cumulative, long-term, moderate, beneficial impact on traffic patterns and traffic circulation on Hurlburt from this work.

Project 11-13 also requires some roadway improvements to implement this project. Other roadway projects planned for Sub-Basin 11 include construction of a parking lot or associated roadway improvements for Projects 04-06, 08-08, 07-05, 11-01, 11-05, 11-10, 11-16, 11-17, 11-20, 11-21, and 04-07.

Roadway/parking improvements associated with Alternative 2 would have short-term, minor to moderate, adverse impacts on traffic circulation during construction. However, there would be long-term beneficial impacts with the improved

roadways and increase in parking areas from an operational standpoint.

No-Action Alternative—No additional improvement or new utility lines would be constructed, nor would there be any roadway improvements or additional vehicular parking areas built. This would limit the ability of Hurlburt Field to meet expanding personnel and facility needs. The No-Action Alternative would have a long-term, minor to moderate, adverse impact on infrastructure and roadways at Hurlburt Field.

5.12.3.8 Regulated Special, Solid, and Hazardous Materials and Wastes

• Alternative 1—Substantial solid waste generation (along with the potential for some hazardous waste generation) would occur as part proposed Alternative 1 project work as well as planned facility demolitions in Sub-Basin 11. Some additional solid waste generation would be associated with site clearing and grubbing for some of the new facilities and roadway work included in the General Plan. Most of this waste would be vegetation cleared from the sites prior to construction.

In addition, eight facilities associated with eight Alternative 1 projects in this sub-basin would become satellite accumulation points (SAP) for some hazardous materials after construction.

Individually, this alternative would have a short-term, minor, adverse impact on solid waste generation during the demolition and construction of the proposed projects. Demolitions could also result in the need to remove and dispose of relatively small amounts of asbestos, materials with leadbased paint, etc. Cumulatively, Alternative 1 projects in Sub-Basin 11 would have a short-term, moderate, adverse impact on solid, and possibly special, waste generation.

 Alternative 2—Substantial solid waste generation (along with the potential for some hazardous waste generation) would occur as part proposed Alternative 2 project work as well as planned facility demolitions in Sub-Basin 11. Some additional solid waste generation would be associated with site clearing and grubbing for some of the new facilities and roadway work included in the General Plan. Most of this waste would be vegetation cleared from the sites prior to construction.

In addition, eight facilities associated with Alternative 2 in this sub-basin would become satellite accumulation points for some hazardous materials after construction.

Individually, this alternative would have a short-term, minor, adverse impact on solid waste generation during the demolition and construction of the proposed projects. Demolitions could also result in the need to remove and dispose of relatively small amounts of asbestos, materials with leadbased paint, etc. Cumulatively, Alternative 2 projects in Sub-Basin 11 would have a short-term, moderate, adverse impact on solid, and possibly special, waste generation.

No-Action Alternative—The No-Action Alternative would not generate substantial amounts of solid waste, as none of the projects described Alternatives 1 or 2 would be constructed. Only regular maintenance and upkeep would continue on the existing facilities in Sub-Basin 11. There would be no new additional sites designated as hazardous waste accumulation points. However, the problems and needs as outlined under the DD Forms 1391 (see Appendix C) would increase over time and could have a long-term impact on the mission of Hurlburt Field.

5.12.3.9 IRP

• Alternative 1—Anticipated impacts to IRP sites associated with Alternative 1 are expected to affect sites: SS-125, SS-130, SS-132, SD-212, ST-217, and LF-19 for a total of 103,224.8 SF (2.37 acres). Projects that would impact these areas are: 11-04, 11-05, 11-07, 11-08, 11-12, 11-15, 11-16, 11-17, 11-19, and 11-20. Each of these projects and their proposed impacts are listed as follows:

- Project 11-04: (SOF Engine Maintenance and Storage Shop)— Impacting 5,048.3 SF of IRP Sites SS-130 and 132.
- Project 11-05 (Fire Crash and Rescue Station)—Impacting 8,897.7 SF of IRP Site SS-125.
- Project 11-07 (Realign Cruz Avenue)—Impacting 4,687.8 SF of IRP Site SS-125.
- Project 11-08 (SOF Squadron Operations, Talon II)—Impacting 56.4 SF of IRP Site SS-125.
- Project 11-11 (SOF C-130 Aircraft Apron)—Impacting 7,618.7 SF of IRP Site ST-217.
- Project 11-12 (SOF Survival Equipment Shop) – Impacting 15,516 SF of IRP Site SS-125.
- Project 11-15 (Realign Cruz Avenue)—Impacting 8,837.2 SF of IRP Site LF-19.
- Project 11-16 (SOF DASH-21 Maintenance Facility)—Impacting 10,836.1 SF of IRP Site SS-125.
- Project 11-17 (SOF Maintenance Storage Facility)—Impacting 5,413.3 SF of IRP Site LF-19.
- Project 11-19 (Squadron Operations Facility, 18 FLTS)—Impacting 13,881.3 SF of IRP Site SD-212.
- Project 11-20 (Operations Group/ Operations Plans Facility)—Impacting 22,432 SF of IRP Site SS-125.

Generally, Alternative 1 projects would have a potential short-term and long-term minor to moderate adverse impact on the IRP program from the standpoint of interference with on-going monitoring as well as with future remediation activities. Any project potentially sited on a known IRP site would need to be coordinated through the installation IRP manager and the appropriate regulatory agencies.

 Alternative 2—IRP sites associated with Sub-Basin 11 that are expected to be impacted with the projects described as part of Alternative 2 include: LF-14, LF-15, LF-19, and SS-125 for a total of 149,002 SF (3.42 acres). Projects that would impact these areas are: 04-06, 07-05, 11-04, 11-07, 11-12, 11-15, 11-16, and 11-17. Each of these projects and their proposed impacts are discussed as follows:

- Project 04-06 (Airmen Leadership School)—Impacting 49,043 SF of IRP Site LF-14 and 5,948 SF of IRP Site LF-15.
- Project 07-05 (SOF Weapons and Release Systems Shop)—Impacting 26,736 SF of IRP Site SS-125.
- Project 11-04 (SOF Engine Maintenance and Storage Shop)— Impacting 26,508 SF of IRP Site LF-19.
- Project 11-07 (Realign Cruz Avenue)—Impacting 8,948 SF of IRP Site SS-125.
- Project 11-12 (SOF Survival Equipment Shop)—Impacting 15,516 SF of IRP Site SS-125.
- Project 11-15 (Realign Cruz Avenue)—Impacting 9,917 SF of IRP Site LF-19.
- Projects 11-16 and 11-17 (SOF DASH-21 Maintenance and Storage Facility)—Impacting 6,386 SF of IRP Site LF-19.

Generally, Alternative 1 projects would have a potential short-term and long-term minor to moderate adverse impact on the IRP program from the standpoint of interference with on-going monitoring as well as with future remediation activities. Any project potentially sited on a known IRP site would need to be coordinated through the installation IRP manager and the appropriate regulatory agencies.

No-Action Alternative—The No-Action Alternative would not construct any of the proposed projects. No IRP sites would be impacted. Monitoring and clean up of identified IRP sites would continue as outlined in the Management Action Plan. However, with this alternative, the problems and needs as outlined under the DD Forms 1391 (see Appendix C) would increase over time and could have a long-term impact on the mission of Hurlburt Field.

5.12.3.10 Q/D Arc

• Alternative 1—Alternative 1 would result in 292,565.6 SF (6.72 acres) of Q/D Arc (i.e., airfield stand-off) being encroached upon by Project 11-04 (41,814.2 SF), Project 11-05 (3,266.5 SF), and Project 11-11 (247,484.9 SF). Consequently, this alternative would result in an individual and cumulative long-

- term, moderate, adverse impact to the operations regarding Q/D Arcs.
- Alternative 2—Alternative 2 would result in 124 SF (0.003 acre) of Q/D Arc (i.e., airfield stand-off) being encroached upon by Project 11-05 (45 SF) and Project 11-20 (79 SF). Consequently, this alternative would result in an individual and cumulative long-term, minor, adverse impact operations regarding Q/D Arcs.
- No-Action Alternative—The No-Action Alternative would have no impact on existing Q/D Arcs.



Alternative 1 was selected as the preferred alternative based on its relationship to the General Plan and its cumulative impacts on environment. The benefits derived from implementation of all of the projects as discussed in this EA (and as illustrated through various referenced planning and design documents, particularly the Hurlburt Field General Plan) will increase the efficiency and operational capacity for those working and living at Hurlburt. This increase in efficiency will maintain and enhance long-term productivity at the installation and may even improve AFSOC operational capabilities. Of the two identified feasible alternatives discussed in detail in this EA, Alternative 1 has been chosen as the recommended alternative based on relationship with the General Plan, design parameters, environmental concerns, and ability to meet purpose and need for the project.

Alternative 1 was developed in conjunction with the development of the General Plan and, therefore, was approved by Hurlburt and Air Force leaders with the approval of the General Plan. Alternative 2 was developed as an option as part of the General Plan process, but not incorporated into the final General Plan and not included in the General Plan approval. From an operational stand-point, the No-Action Alternative would not meet the purpose and need of this EA, nor for Hurlburt Field's future growth and development needs and therefore, it was not selected as the preferred alternative.

Alternative 1 calls for complete implementation of the 2002 Hurlburt Field General Plan, as amended. This would be of long-term benefit to the Hurlburt Field mission and to the HQ AFSOC

and would not result in any significant adverse impacts to the natural, cultural, or socioeconomic environments. Therefore, an EIS is not required and will not be prepared in order to implement the projects covered in this EA. This EA may also be used as a tiering document for other Hurlburt Field projects not specifically covered in this document and requiring separate NEPA documentation (40 CFR 1508.28).

6.1 UNAVOIDABLE, DIRECT, ADVERSE EFFECTS FROM THE PROPOSED ACTION

Alternative 1, as the preferred alternative, advocates complete implementation of the Hurlburt Field General Plan (Woolpert, Inc., 2002), as amended. This would result in the following unavoidable, direct, adverse effects:

- Temporary potential increases in soil erosion associated with demolition and construction activities.
- A moderate increase in overall impervious surface area on the installation.
- Loss of some mature trees and other landscape vegetation.
- Temporary traffic delays and detours during construction activities.
- Solid waste generation from construction debris and from demolition activities.

6.2 CUMULATIVE IMPACT SUMMARY

This EA sought to examine the cumulative impacts of both Alternatives 1 and 2 and to compare those results. The cumulative impacts from each alternative and takes into consideration other past, present, and reasonably foreseeable future actions on Hurlburt but not included in the General Plan list of projects. Resource areas that were examined include groundwater, storm water, wetlands, utility infrastructure, traffic, and solid waste, among others.

Tables 30 and 31 show the cumulative impacts of all the projects listed in this report for both Alternatives 1 and 2 by resource area.

In almost every resource area examined, Alternative 1 would have a lesser impact than would Alternative 2. The exceptions to this are with wetlands (both permitted and un-permitted), mature tree removals, and IRP sites where Alternative 2 would have a lesser impact than Alternative 1.

When looking at the two action alternatives, Alternative 1 would also meet Hurlburt Field's operational needs, in addition to having a lesser impact on the environmental resources of the installation.

6.3 MITIGATION MEASURES SUMMARY

Measures that will be taken to minimize short and long-term impacts from the Proposed Action include, but are not limited to:

Use of Best Management Practices regarding appropriate storm water management and erosion and sediment control plans. This could include construction of additional detention/retention basins, modifying existing storm water control structures, installation of additional catch basins, temporary use of silt fencing, and use of vegetated swales to slow and absorb surface sheet flow.

Table 30 Cumulative Impacts for Alternative 1		
Impact Area	Result	
Floodplains	336,354.6 SF (7.72 Acres)	
Un-permitted Wetlands	32,590.6 SF (0.78 Acres)	
Permitted Wetlands	136,397 SF (3.13 Acres)	
RTE Habitat	None	
Cultural Resources	None	
Q/D Arcs	306,551.3 SF (7.03 Acres)	
Within the AICUZ	37 Projects Within the 65 db	
	Contour	
Trees Removed	218 Trees	
Within a Storm-Surge	6 Projects	
Area (Categories 1 to 5)	848,533 SF (19.48 acres)	
IRP/AOC Areas	273,946 SF (6.29 acres)	
Hazardous Materials	Future Satellite	
	Accumulation Point for	
	Projects 07-05, 07-07, 07-	
	08, and 07-09	
Air Emission Permits	1 Project Will Need a	
	Modification to the Air	
	Emissions Permit (11-13)	
New Impervious Surface	3,797,303 SF (87.17 Acres)	
Demolitions	258 Facilities	
	1,195,656 SF (27.44 Acres)	


_		
Table 31 Cumulative Impacts for Alternative 2		
	Result	
Impact Area		
Floodplains	798,567.5 SF (18.33 Acres)	
Un-permitted Wetlands	1,198,626 SF (27.52 Acres)	
Permitted Wetlands	None	
RTE Habitat	71,350 SF (1.64 Acres)	
Cultural Resources	4,021 SF (0.09 Acres)	
Q/D Arcs	528,471 SF (12.13 Acres)	
Within the AICUZ	40 Projects Within the 65 db	
	Contour	
Trees Removed	67 Trees	
Within a Storm-Surge	7 Projects	
Area (Category 1-5)	803,051 SF (18.44 Acres)	
IRP/AOC areas	194,331 SF (4.46 Acres)	
Hazardous Materials	Future Satellite	
	Accumulation Point for	
	Projects 07-07, 07-08, and	
	07-09	
Air Emission Permits	1 Project Will Need a	
	Modification to the Air	
	Emissions Permit (11-13)	
New Impervious Surface	4,163,105 SF (95.57 Acres)	
Demolitions	181 Facilities	
	952,932 SF (21.87 Acres)	

- Use of authorized salvage personnel and/or incorporation of specific deconstruction techniques to minimize solid waste generations during building renovation, construction, or demolition.
- Sale of downed trees and other woody vegetation for firewood and mulch to reduce the amount of woody vegetation in the solid waste stream.

- Revegetation of bare ground would occur with native plants immediately following the construction phase.
- Use of native replacement trees and other plantings in all landscaping activities as defined by Hurlburt Field's Landscape Management Plan and tree replacement policy.
- Current building codes would be incorporated into new structure development in order to maximize energy efficiency.
- Coastal Zone Consistency Certification in order to meet the requirements for construction within the critical area of the coastal zone.
- Choosing energy efficient equipment and utilities when designing facilities in order to decrease energy demand and minimize greenhouse gas emissions.

6.4 RELATIONSHIP OF SHORT-TERM USES AND LONG-TERM PRODUCTIVITY RESULTING FROM THE PROPOSED ACTION

Long-term productivity would be greatly enhanced in terms of accomplishing the special operations mission of Hurlburt Field. The new. relocated, or renovated facilities would improve the quality of life for those working and living on Hurlburt and would provide a highly improved operational platform from which special operations training and deployments could take place. The primary tradeoff associated with the Proposed Action is that there would be shortterm disruptions in overall daily operations on some portions of Hurlburt during the construction phase. These disruptions could cause some temporary delay and/or downturn in productivity, but would lead to long-turn improvements in morale, productivity, and readiness.





SECTION 7.0 PREPARERS

7.1 HURLBURT FIELD

- Carl T. Hoffman, R.A.—Chief, Base Development Section
- Lt. Christopher Wedewer—Base Development Section
- Philip Pruitt—Base Environmental Scientist

7.2 WOOLPERT, INC.

- Jerry Lang, Ph.D.—Senior Environmental Scientist
- Martha Alarie-Harris—Environmental Planner
- Chad Adkins—Planner
- Dave Dister—Environmental Scientist
- Stuart Jennings—Environmental Scientist





AFCEE, 2001.

American Ornithologists' Union (AOU). 1998. "Check-List of North American Birds." 7th Edition, American Ornithologists' Union, Washington, D.C.

Council on Environmental Quality. January 1997. "The National Environmental Policy Act: A Study of its Effectiveness After Twenty-Five Years."

Florida Fish and Wildlife Conservation Commission (FFWCC) 2004. "Florida's Endangered Species, Threatened Species, and Species of Special Concern: Official Lists."

Florida Natural Areas Inventory (FNAI). 1993. "Distribution of the Flatwoods Salamander (*Ambystoma cingulatum*) and the gopher frog (*Rana capito*) on Eglin AFB, Florida, Year I." Florida Department of Natural Resources, Tallahassee, Florida.

Florida Natural Areas Inventory (FNAI). 1994a. "Distribution of the Flatwoods Salamander (*Ambystoma cingulatum*) and the gopher frog (*Rana capito*) on Eglin AFB, Florida, Year II." Florida Department of Natural Resources, Tallahassee, Florida.

Florida Natural Areas Inventory (FNAI). 1994b. "Rare Plant Survey of Eglin AFB: Final Report—Year Two." Florida Department of Natural Resources, Tallahassee, Florida. Florida Natural Areas Inventory (FNAI). 2003. "Rare Plant and Animal Inventory of Air Force Special Operations Command, Hurlburt Field, Florida."

Florida Natural Areas Inventory (FNAI). 2005.
Online: "FNAI Tracking List: Florida-All
Counties" from webpage http://www.fnai.org/bioticssearch.cfm

Hurlburt Field. 2003. "Hazardous Waste Management Plan and Spill Prevention Control and Countermeasures Plan."

Labat-Anderson, Inc. 1994. "Threatened and Endangered Species Survey: Hurlburt Field, Florida. "Bellevue, Nebraska.

MWH Americas, Inc. 2002. "Final Storm Water Pollution Prevention Plan for Hurlburt Field, Florida, Prepared for 16 CES/CEV, Hurlburt Field, Florida 32544."

MWH Americas, Inc. 2004. Update: "Final Storm Water Pollution Prevention Plan for Hurlburt Field, Florida, Prepared for 16 CES/CEV, Hurlburt Field, Florida 32544."

National Hurricane Center. 1995. From webpage http://www.nhc.noaa.gov/

National Hurricane Center. 2001. From webpage http://www.nhc.noaa.gov/


National Hurricane Center. 2005. From webpage http://www.nhc.noaa.gov/

- National Weather Service. 1995. From webpage http://www.nws.noaa.gov/
- Printiss, David J. and Dan L. Hipes. 2000.

 "Flatwoods salamander survey and habitat evaluation of Eglin Air Force Base, Hurlburt Field, and Tyndall Air Force Base." Final Report to U.S. Department of Defense, U.S. Air Force. Florida Natural Areas Inventory, Tallahassee, Florida.
- Pruitt, Philip. June 25, 2004. Personal Communication.
- SAIC. 2003. DRAFT "Environmental Baseline Survey for The Eglin Air Force Base and Hurlburt Field Military Family Housing Privatization Program."
- SAIC. 2004. FINAL "Environmental Baseline Survey for The Eglin Air Force Base and Hurlburt Field Military Family Housing Privatization Program."
- U.S. Army Corps of Engineers; Environmental Resources Planning Section. September 1994. "Archeological Sensitivity Map: Hurlburt Field, U.S. Air Force, Okaloosa County, Florida." Mobile Alabama.
- U.S. Air Force. 1996. "Integrated Natural Resources Management Plan, Hurlburt Field, Florida, 1996." Air Force Special Operations Command.
- Woolpert. 1996. "Hurlburt Field Transportation Plan.
- Woolpert. 1998. "Comprehensive Wetland Delineation. Prepared for: U.S. Army Corps of Engineers, Mobile and 16th Civil Engineer Squadron, Hurlburt Field.
- Woolpert, Inc. 2001. "Integrated Natural Resources Management Plan and Environmental Assessment: Hurlburt Field."
- Woolpert, Inc. 2002. "Hurlburt Field General Plan."




To be provided in the next submittal.





	List of Projects Considered
FTEV#	Description
Sub-Basin	1
N/A	
Sub-Basin	2
02-1001	Construct Outdoor Recreation Center, 16 SVS
Sub-Basin	3
N/A	
Sub-Basins	
04-1072	Add to Fitness Center, Building 90517
95-3013	Temporary Lodging Facility
04-3016	Supply Warehouse
99-3036	Child Development Center
03-3021	16th Contracting Squadron Facility
97-3019	Airmen Leadership School
02-3015	SOF JSOU Library/Education Center Com/Language Lab PH 3
03-3020	Soundside Visiting Quarters (120 pn)
Sub-Basin	
01-5007	Consolidated Club
02-3011	Mission Planning Center
Sub-Basin	
04-3020	ADAL Command Post
96-2010	Realign O'Neil Avenue/ Install Traffic Signal
03-3022	AT/FP Main Gate and Soundside Access Control Facilities
04-5003	Family Camping Facility
04-3006	SOF Weapons & Release Systems Shop
03-3017	STG Headquarters Facility
04-3000	Refueling Vehicle Maintenance Facility
03-3004	Vehicle Operations Administration Facility
96-3008	ADAL Maintenance Operations Squadron Facility
99-3011	Base Roadway Improvements
99-3033	Squadron Operations Facility, 6SOS

	List of Projects Considered				
FTEV#	Description				
Sub-Basin 8					
00-3009	Vehicle Maintenance Facility				
02-3005	RED HORSE Mobility and Training Facility (823 RHS)				
00-5004	Shoppette Facility				
99-3013	Construct Dormitory (144 pn) Eastside				
00-3023	Eastside Fitness Center				
03-3013	Widen Independence Road				
03-3018	AFLD Waiver, Alter Independence Road				
04-3011	SOF UAV Squadron Operations Facility				
04-3012	SOF UAV Maintenance Hangar/Parking Apron				
Sub-Basin	9				
N/A					
Sub-Basin	10				
N/A					
Sub-Basin					
04-5002	Construct Workbays at Auto Hobby Shop, Building 90612				
03-1049	Fill/Clear Wetlands, Helicopter Landing Pad				
94-3001	ADAL Security Forces Operations (Current Mission)				
97-3006	SOF Engine Maintenance and Storage Shop				
97-3018	Fire Crash/Rescue Station				
01-3021	25th Intelligence Squadron Operations Facility				
03-3014	Realign Cruz Avenue				
04-3005	SOF Squadron Opst Talon II				
02-3010	Add to Visiting Quarters				
02-3013	ADAL USAFSOS Facility				
04-3004	SOF C-130 Aircraft Apron				
04-3007	SOF Survival Equipment Shop				
97-3016	Hydrant Fueling System				
03-3006	Visiting Officers Quarters				
03-3015	Realign Cruz Avenue, Phase 2				
04-3008	SOF Dash-21 Maintenance Facility				
04-3009	SOF Maintenance Storage Facility				
04-3010	SOF C-130 Maintenance Hangar				
96-3012	SOF Squadron Operations Facility, 18 Flts				
97-3009	Operations Group/Operations Support Facility				
02-3014	SOF JSOU Headquarters Facility Phase II				
04-3014	SOF CV-22 Aircraft Parking Apron				



Impacts by Project						
1391 Information	Description					
EA Project Number	02-01					
Project Title	Construct Outdoor Recreation Center, 16SVS					
Fiscal Year	FY10					
Funding Source	NAF					
Project Number	FTEV021001					
Project Type	New					
Demolition Linkage	None					
Availability of On-site Utilities						
Working Population						
Impervious Surface Area	Square Footage					
Square Footage of Building Footprint	3,111.0					
Square Footage of Parking Lot or Roadway Improvement	17,904.9					

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	21,015.9
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	2
Storm Surge Category	sq.ft. by category	Category 1, 2, 3 and higher- (55), (576.5), (21,015.9) sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum, pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	2- Marina Road



Environmental Assessment Hurlburt Field Hurlburt Field, Florida

Legend

EA Project

02-01

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands
Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5
Stormwater Ponds


Monitoring_Wells


Trees

Exotic Plants

Rare Animals

Rare Plants





	Impacts by Project		
1391 Information	Description		
EA Project Number	02-01		
Project Title	Construct Outdoor Recreation Center, 16SVS		
Fiscal Year	FY10		
Funding Source	NAF		
Project Number	FTEV021001		
Project Type	New		
Demolition Linkage	None		
Availability of On-site Utilities			
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	3,111.0		
Square Footage of Parking Lot or Roadway Improvement	20,917.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	Category 4 and 5- 24,028 sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	2- Unknown



Environmental Assessment Hurlburt Field Hurlburt Field, Florida

Legend

EA Projects- Alternative Sittings

02-01

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5

Stormwater Ponds


Monitoring_Wells


Trees

Exotic Plants

Rare Animals

Rare Plants





	Impacts by Project	
1391 Information		Description
EA Project Number		04-01
Project Title	ADAL Fitness	s Center, Building 90517
Fiscal Year		FY06
Funding Source		BA01
Project Number	F	TEV041072
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	1,003.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	4&5
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Project

04-01

Other EA Projects

Installation Boundary

Demolitions

Existing Structures

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs
Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	D	Description
EA Project Number		04-01
Project Title	ADAL Fitness	Center, Building 90517
Fiscal Year		FY06
Funding Source		BA01
Project Number	F	TEV041072
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	1,522.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street




Legend

EA Projects- Alternative Sitings




Other Alternative Sitings



Demolitions

AICUZ Noise Contours

100-year Floodplain



IRP

Q/D Arcs Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		04-02
Project Title	Tempora	ary Lodging Facility
Fiscal Year		FY10
Funding Source		NAF
Project Number	FTEV953013	
Project Type	New	
Demolition Linkage	Military Family Housing Demolitions/ Buildings 90345 & 90346	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	45,663.3	
Square Footage of Parking Lot or Roadway Improvement	34,981.2	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	15
Surface Water Sub-Basin	Sub-basin number	4
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Accompanied Housing/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Weaver Avenue, 1- Tully Street, 1- Simpson Avenue



Legend

EA Project

04-02

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

--- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		04-02
Project Title	Tempora	ary Lodging Facility
Fiscal Year		FY10
Funding Source		NAF
Project Number	FTEV953013	
Project Type	New	
Demolition Linkage	Military Family Housing Demolitions/ Buildings 90345 & 90346	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	16,881.0	
Square Footage of Parking Lot or Roadway Improvement	16,718.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	17,673.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	9
Surface Water Sub-Basin	Sub-basin number	4&5
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Tully Street



Legend

EA Projects- Alternative Sitings

04-02

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	The state of the s
1391 Information	Description	
EA Project Number		04-02
Project Title	Tempora	ary Lodging Facility
Fiscal Year		FY10
Funding Source		NAF
Project Number	FTEV953013	
Project Type	New	
Demolition Linkage	Military Family Housing Demolitions/ Buildings 90345 & 90346	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	45,663.3	
Square Footage of Parking Lot or Roadway Improvement	34,981.2	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	15
Surface Water Sub-Basin	Sub-basin number	4
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Accompanied Housing/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Weaver Avenue, 1- Tully Street, 1- Simpson Avenue



Legend

EA Project

04-02

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands
Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		04-02
Project Title	Tempora	ary Lodging Facility
Fiscal Year		FY10
Funding Source		NAF
Project Number	FTEV953013	
Project Type	New	
Demolition Linkage	Military Family Housing Demolitions/ Buildings 90345 & 90346	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	16,881.0	
Square Footage of Parking Lot or Roadway Improvement	16,718.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	17,673.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	9
Surface Water Sub-Basin	Sub-basin number	4&5
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Tully Street



Legend

EA Projects- Alternative Sitings

04-02

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	D	escription
EA Project Number		04-03
Project Title	Supp	oly Warehouse
Fiscal Year		FY10
Funding Source		BA01
Project Number	F	TEV043016
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	227,606.4	
Square Footage of Parking Lot or Roadway Improvement	152,389.2	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	8,297.1
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	42,820.4 sf SD-208
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	26
Surface Water Sub-Basin	Sub-basin number	4&5
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Accompanied Housing/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1-Bakke Street/ 1-Mayo Street



Legend

EA Project

04-03

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands
Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		04-03
Project Title	Supp	ly Warehouse
Fiscal Year		FY10
Funding Source		BA01
Project Number	FI	TEV043016
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	115,947.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	31,400.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	1,233 sq. ft. SS-125
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	None



Legend

EA Projects- Alternative Sitings

04-03

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	D	escription
EA Project Number		04-04
Project Title	Child De	velopment Center
Fiscal Year		FY11
Funding Source		BA01
Project Number	FT	EV993036
Project Type	New	
Demolition Linkage	M ilitary Family Housing Demolitions	
Availability of On-site Utilities	Y	
Working Population	400 children	
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	42,604.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	1
Surface Water Sub-Basin	Sub-basin number	4&5
Storm Surge Category	sq.ft, by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Accompanied Housing
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Schmauss Lane



Legend

EA Project

04-04

Other EA Projects

Installation Boundary

Demolitions

Existing Structures

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs
Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		04-04
Project Title	Child D	evelopment Center
Fiscal Year		FY11
Funding Source		BA01
Project Number	F	TEV993036
Project Type	New	
Demolition Linkage	M ilitary Family Housing Demolitions	
Availability of On-site Utilities	γ γ	
Working Population	400 children	
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	42,604.0	
Square Footage of Parking Lot or Roadway Improvement	33,888.0	* 1

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	10
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Accompanied Housing/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Kanuha Drive



Legend

EA Projects- Alternative Sitings

04-04

Other Alternative Sitings

Installation Boundary
Existing Structures

_____ Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project			
1391 Information	Description		
EA Project Number		04-05	
Project Title	16th Contract	ting Saquadron Facility	
Fiscal Year		FY11	
Funding Source		BA01	
Project Number	FTEV033022		
Project Type	New		
Demolition Linkage	Military Family Housing Demolitions		
Availability of On-site Utilities	Υ		
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building			
Footprint	10,500.1		
Square Footage of Parking Lot or			
Roadway Improvement	22,144.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
	sq.ft.impacted and not covered	
Un-permitted Wetland Impacts	under existing permits	0.0
	sq.ft. impacted and covered under	
Permitted Wetland Impacts	existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	1
Surface Water Sub-Basin	Sub-basin number	4&5
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatability with Adjacent Land	surrounding land use designations	
Uses	from Land Use Plan	Accompanied Housing/ Open Space
	# curb cuts on streets to access	
Adjacent Streets/ Intersections	facility	2- McMillan Street



Legend

EA Project

04-05

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

Q/D Arcs

Wetlands
Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project			
1391 Information	Description		
EA Project Number	04-05		
Project Title	16th Contracting Saqu	adron Facility	
Fiscal Year	FY11		
Funding Source	BA01		
Project Number	FTEV033021		
Project Type	New		
Demolition Linkage	Military Family Housing Demolitions		
Availability of On-site Utilities	Υ		
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building			
Footprint	10,500.1		
Square Footage of Parking Lot or			
Roadway Improvement	22,144.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
	sq.ft.impacted and not covered	
Un-permitted Wetland Impacts	under existing permits	0.0
	sq.ft. impacted and covered under	
Permitted Wetland Impacts	existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	Category 5- 6,051 sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatability with Adjacent Land	surrounding land use designations	
Uses	from Land Use Plan	Open Space
	# curb cuts on streets to access	
Adjacent Streets/ Intersections	facility	2- Independence Road



Legend

EA Projects- Alternative Sitings

04-05

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	D	escription
EA Project Number		04-06
Project Title	Airmen L	eadership School
Fiscal Year		FY11
Funding Source		BA01
Project Number	FT	EV973019
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	20,000.0	
Square Footage of Parking Lot or Roadway Improvement	50,614.7	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	4
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administration/ Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	2- Letourneau Circle



Legend

EA Project

04-06

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands
Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		04-06
Project Title	Airmen	Leadership School
Fiscal Year		FY11
Funding Source		BA01
Project Number	F	TEV973019
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	21,055.0	
Square Footage of Parking Lot or Roadway Improvement	41,288.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	8,533.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	49,043 sq. ft LF-14/ 5,948 sq. ft LF-15
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	1
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	2- Red Horse Road



Legend

EA Projects- Alternative Sitings

04-06

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

--- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number	0	4-07
Project Title	SOF JSOU Library/Education Ce	enter Complex/Language Lab PH 3
Fiscal Year	F	Y12
Funding Source	MF	P-11
Project Number	FTEV02-3015	
Project Type	New	
Demolition Linkage	Building 90337	
Availability of On-site Utilities	Ÿ	
Working Population		1990
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	22,998.7 (SB11)	
Square Footage of Parking Lot or Roadway Improvement	63,623 (SB 4), 42527.9 (SB 7)	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	11
Surface Water Sub-Basin	Sub-basin number	4, 7 & 11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administration/ Community Commercial/ Industrial/ Outdoor Recreation/ Unaccompanied Housing
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1-Cody Avenue/ 2-Tully Street



Legend

EA Project

04-07

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs
Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-21 & 04-07
Project Title	SOF JSOU Hea	adquarters Facility, Phase 2 & 3
Fiscal Year		FY12
Funding Source		MFP-11
Project Number		FTEV023014
Project Type		New
Demolition Linkage	None	
Availability of On-site Utilities		72.0
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	29,000.0	
Square Footage of Parking Lot or Roadway Improvement	60,769.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	43,066.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects- Alternative Sitings

11-21 & 04-07

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		05-01
Project Title	Soundside Visit	ng Quarters (120 rooms)
Fiscal Year		FY06
Funding Source		NAF
Project Number	FTEV033020	
Project Type	New	
Demolition Linkage	Buildings 90909 & 90910	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	13,227.7 (SB4&5)/ 14,714.6 (SB6)	
Square Footage of Parking Lot or Roadway Improvement	43,067.5 (SB4&5)/ 34,286.5 (SB6)	

Site Characteristics	Quantity or Identifier	Description	
Floodplain Impacts	sq.ft.	16,443.8	
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0	
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0	
RTE Habitat	sq.ft.	0.0	
Cultural Resources	NRHP site #	0.0	
IRP	IRP or AOC #	7020.8 sq. ft. SS-214	
Q/D Clear Zone	Source	0.0	
AICUZ	within 65db contour	N	
Tree Removal (>6"dbh)	total number requiring removal	53	
Surface Water Sub-Basin	Sub-basin number	4&5	
Storm Surge Category	sq.ft. by category	Category 1, 2, 3, 4 and higher- (1,147.2), (2,850.1), (102,046.0), (105,296.3) sq.ft.	
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N	
Hazardous Materials	future satellite accum. pt. (y/n)	N	
Air Emissions	permit modification required (y/n)	N	
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial/ Industrial/ Open Space/ Unaccompanied Housing	
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	3-New Road Project # 03-3022	



Legend

EA Project

05-01

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		05-01
Project Title	Soundside Visi	tng Quarters (120 rooms)
Fiscal Year		FY06
Funding Source		NAF
Project Number	E	TEV033020
Project Type	New	
Demolition Linkage	Buildings 90909 & 90910	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	30,620.0	
Square Footage of Parking Lot or Roadway Improvement	41,941.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	60,207.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	8
Surface Water Sub-Basin	Sub-basin number	4&5
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Accompanied Housing/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	None



Legend

EA Project

05-01

Other Alternative Sitings

Installation Boundary

Existing Structures
Demolitions

--- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	1
EA Project Number	06-01	
Project Title	Consolidated (Club
Fiscal Year	FY06	
Funding Source	NAF	
Project Number	FTEV01500	7
Project Type	New	
Demolition Linkage	Buildings 90921, 9092	23 & 99160
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	20,144.0	
Square Footage of Parking Lot or Roadway Improvement	75,994.4	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	11
Surface Water Sub-Basin	Sub-basin number	6
Storm Surge Category	sq.ft. by category	Category 3, 4 and higher- (72,002.7), (96,138.4) sq.ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial/ Industrial/ Open Space/ Unaccompanied Housing
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	5-New Road Project #03-3022



Legend

EA Project

06-01

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number	06-	-01
Project Title	Consolida	ated Club
Fiscal Year	FY	'06
Funding Source	N/	AF .
Project Number	FTEVO	015007
Project Type	New	
Demolition Linkage	Buildings 90921, 90923 & 99160	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	11,058.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	11,058.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	4&5
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Accompanied Housing/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	None



Legend

EA Projects- Alternative Sitings

06-01

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		06-02
Project Title	Missio	n Planning Facility
Fiscal Year		FY07
Funding Source		BA01
Project Number	F	TEV023011
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities	Y	
Working Population	590	
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	17,590.0	
Square Footage of Parking Lot or Roadway Improvement	76,643.3	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	12
Surface Water Sub-Basin	Sub-basin number	6
Storm Surge Category	sq.ft. by category	Category 3, 4 and higher- (33,654.6), (94,233.3) sq.ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Open Space/ Unaccompanied Housing
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	3-New Road Project #03-3022



Legend

EA Projects

06-02

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Descr	iption
EA Project Number	06-	02
Project Title	Mission Plan	ning Facility
Fiscal Year	FY	07
Funding Source	BA	01
Project Number	FTEVO	23011
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities	Y	
Working Population	590	
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	17,590.0	
Square Footage of Parking Lot or Roadway Improvement	80,577.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	Category 4 and higher- 98,167 sq.ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	3- Unknown



Legend

EA Projects- Alternative Sitings

06-02

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds

Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	Control of the Contro
1391 Information	Description	
EA Project Number		07-01
Project Title	ADAL	Command Post
Fiscal Year		FY05
Funding Source		BA01
Project Number	F	TEV043020
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	5,975.1	
Square Footage of Parking Lot or Roadway Improvement		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Terry Avenue



Legend

EA Projects

07-01

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-01
Project Title	ADAL	Command Post
Fiscal Year		FY05
Funding Source		BA01
Project Number	F	TEV043020
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	12,620.0	
Square Footage of Parking Lot or Roadway Improvement	31,706.0	4

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	15,292.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	5
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	None



Legend

EA Projects- Alternative Sitings

07-01

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	D	Description
EA Project Number		07-02
Project Title	Realign O'Neil A	venue/Install Traffic Signal
Fiscal Year		FY06
Funding Source		BA01
Project Number	F	TEV962010
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	26,348.4	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administration/ Community Commercial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Independence Road, O'Niel Avenue, Terry Avenue, McClean Street



Legend

EA Projects

07-02

Other EA Projects

_____Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs
Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project		
1391 Information	Description	
EA Project Number	(07-02
Project Title	Realign O'Neil Ave	nue/Install Traffic Signal
Fiscal Year		FY06
Funding Source		BA01
Project Number	FTE	V962010
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building		
Footprint	0.0	
Square Footage of Parking Lot or	·	
Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
	sq.ft.impacted and not covered	
Un-permitted Wetland Impacts	under existing permits	0.0
	sq.ft. impacted and covered under	
Permitted Wetland Impacts	existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land	surrounding land use designations	Administration/ Community
Uses	from Land Use Plan	Commercial
	# curb cuts on streets to access	Independence Road & Terry
Adjacent Streets/ Intersections	facility	Avenue



Legend

EA Projects- Alternative Sitings

07-02

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs
Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project				
1391 Information		Description		
EA Project Number		07-03		
Project Title	AT/FP Main Gate ar	nd Soundside Access Control Facilities		
Fiscal Year		FY07		
Funding Source		BA01		
Project Number		FTEV033022		
Project Type		New		
Demolition Linkage	None			
Availability of On-site Utilities				
Working Population				
Impervious Surface Area	Square Footage			
Square Footage of Building Footprint	2.630.1	4		
	2,030.1			
Square Footage of Parking Lot or Roadway Improvement	87,235.7			

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	1,352.5
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	13,257.6 sq. ft. SS-214
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	16
Surface Water Sub-Basin	Sub-basin number	4&5
Storm Surge Category	sq.ft. by category	Category 3, 4, 5- (44,585.8), (46,266.8), (67,415.1) sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatability with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Accompanied Housing/ Community Commercial/ Industrial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Campaign Street/ 1-Whitbeck Street



Environmental Assessment Hurlburt Field

Legend Hurlburt Field, Florida

EA Projects

07-03A

///// 07-03B

Other EA Projects

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds

Monitoring_Wells

Trees

Exotic Plants

Rare Animals



Impacts by Project		
1391 Information		Description
EA Project Number		07-03
Project Title	AT/FP Main Gate ar	nd Soundside Access Control Facilities
Fiscal Year		FY07
Funding Source		BA01
Project Number		FTEV033022
Project Type		New
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	2,630.1	
Square Footage of Parking Lot or Roadway Improvement	245,874.0	11

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	39,083.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	4,021.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	Category 3, 4, 5- (39,042), (42,521), (183,312) sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatability with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administration/ Community Commercial/ Industrial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- US-98/ 1- Loop Road



Legend

EA Projects- Alternative Sitings

07-03

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	De	escription
EA Project Number		07-03
Project Title	AT/FP Main Gate and So	undside Access Control Facilities
Fiscal Year		FY07
Funding Source		BA01
Project Number	FT	EV033022
Project Type		New
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		,
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	3,880.9 (SB7)	
Square Footage of Parking Lot or Roadway Improvement	34,999.0 (SB6)/ 117,722.3 (SB7)	1

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	24
Surface Water Sub-Basin	Sub-basin number	6&7
Storm Surge Category	sq.ft. by category	Category 3, 4, 5- (18,788.5), (50,440.6), (82,506.6) sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatability with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Services/ Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Cody Avenue/ 1- McMillan Street



Environmental Assessment Hurlburt Field

Legend Hurlburt Field, Florida

EA Projects

07-03B

07-03A

Other EA Projects

Installation Boundary **Existing Structures**

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4 Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project		
1391 Information		Description
EA Project Number		07-03
Project Title	AT/FP Main Gate ar	nd Soundside Access Control Facilities
Fiscal Year		FY07
Funding Source		BA01
Project Number		FTEV033022
Project Type		New
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	2,630.1	
Square Footage of Parking Lot or Roadway Improvement	245,874.0	11

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	39,083.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	4,021.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	Category 3, 4, 5- (39,042), (42,521), (183,312) sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatability with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administration/ Community Commercial/ Industrial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- US-98/ 1- Loop Road



Legend

EA Projects- Alternative Sitings

07-03

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-04
Project Title	Family Can	nping Facility (24 Sites)
Fiscal Year		FY08
Funding Source		NAF
Project Number		TEV045003
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	67,336.9	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	Category 4 and 5- 67,336.9 sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Unknown



Legend

EA Projects

07-04

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	De	escription
EA Project Number		07-04
Project Title	Family Camp	ing Facility (24 Sites)
Fiscal Year		FY08
Funding Source		NAF
Project Number	FT	EV045003
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	76,491.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	1,152.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	336.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	Category 3 and higher- 76,491 sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Unknown



Legend

EA Projects- Alternative Sitings

07-04

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information		Description
EA Project Number		07-05
Project Title	SOF Weapons	& Release Systems Shop
Fiscal Year		FY08
Funding Source		MFP-11
Project Number	F	TEV043006
Project Type	New	
Demolition Linkage	Builling 90131	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	18,000.0	
Square Footage of Parking Lot or Roadway Improvement	10,732.9	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	28,733.2 sq. ft. ST-123
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	2-Tully Street



Legend

EA Projects

07-05

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-05
Project Title	SOF Weapons	& Release Systems Shop
Fiscal Year		FY08
Funding Source		MFP-11
Project Number	F	ΓΕV043006
Project Type	New	
Demolition Linkage	Builling 90131	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	18,000.0	
Square Footage of Parking Lot or Roadway Improvement	8,746.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	26,736 sq. ft. SS-125
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	1
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1-Bedel Street



Legend

EA Projects- Alternative Sitings

07-05

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information		Description
EA Project Number		07-06
Project Title	SOF Special Taction	s Group Headquarters Facility
Fiscal Year		FY11
Funding Source		MFP-11
Project Number	F	TEV033017
Project Type	New	
Demolition Linkage	Building 90204	
Availability of On-site Utilities	Ÿ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	25,000.0	
Square Footage of Parking Lot or Roadway Improvement	100,568.9	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	18
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Community Service/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Terry Avenue



Legend

EA Projects

07-06

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-06
Project Title	SOF Special Tactics	Group Headquarters Facility
Fiscal Year		FY11
Funding Source		MFP-11
Project Number	FT	EV033017
Project Type	New	
Demolition Linkage	Building 90204	
Availability of On-site Utilities	Ÿ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	6,250.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	12

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	1
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Bartley Street



Legend

EA Projects- Alternative Sitings

07-06

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-07
Project Title	Refueling Veh	icle Maintenance Facility
Fiscal Year		FY10
Funding Source		BA01
Project Number	F	TEV043000
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		W-00-00
Working Population	A	
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	6,296.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	537.1 sq. ft. ST-123 1,401.4 sq. ft. SD-189 4,357.5 sq. ft. ST-68
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	McClean Street/ New Road Project # 99-3011



Legend

EA Projects

07-07

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project		
1391 Information	Description		
EA Project Number		07-07	
Project Title	Refueling Vehi	cle Maintenance Facility	
Fiscal Year		FY10	
Funding Source		BA01	
Project Number	FTEV043000		
Project Type	New		
Demolition Linkage	None		
Availability of On-site Utilities			
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	6,351.0		
Square Footage of Parking Lot or Roadway Improvement	3,657.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	9,929 sq. ft SS-124
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	1
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	McClean Street



Legend

EA Projects- Alternative Sitings

07-07

Other Alternative Sitings

Installation Boundary **Existing Structures**

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

IRP Sites

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project		
1391 Information	Description	
EA Project Number		07-08
Project Title	Vehicle Operati	ions Administration Facility
Fiscal Year		FY10
Funding Source		BA01
Project Number	F	TEV033004
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	8,111.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	21.8 sq. ft. OT-43
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Υ
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	McClean Street



Legend

EA Projects

07-08

Other EA Projects

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information		Description
EA Project Number		07-08
Project Title	Vehicle Operati	ons Administration Facility
Fiscal Year		FY10
Funding Source		BA01
Project Number	F	TEV033004
Project Type		New
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	7,934.0	
Square Footage of Parking Lot or Roadway Improvement	18,268.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	899.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	Category 5- 23,456 sq. ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Unknown



Legend

EA Projects- Alternative Sitings

07-08

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-09
Project Title	SOF Maintenance	Operations Squadron Facility
Fiscal Year		FY12
Funding Source		MFP-11
Project Number	FTEV963008	
Project Type	New	
Demolition Linkage	Building 90137	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	13,965.0	
Square Footage of Parking Lot or Roadway Improvement	14,038.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	26,590.1 sq. ft. ST-123
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	7
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects

07-09

Other EA Projects

____ Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-09
Project Title	SOF Maintenance	Operations Squadron Facility
Fiscal Year		FY12
Funding Source		MFP-11
Project Number	F	TEV963008
Project Type	New	
Demolition Linkage	Building 90137	
Availability of On-site Utilities	Ÿ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	13,965.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	1,649 sq. ft. ST-126
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	4
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Terry Avenue



Legend

EA Projects- Alternative Sitings

07-09

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

: Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-10
Project Title	Base R	loadway Improvements
Fiscal Year		FY12
Funding Source		BA01
Project Number		FTEV993011
Project Type	Improvement	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	15,409.9 (SB3)/ 13,034.3 (SB4&5)	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	15,409.9 (SB3), 13,034.3 (SB4&5)
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	3, 4&5
Storm Surge Category	sq.ft. by category	Category 1, 2, 3 and higher- (422.7), (17,673), (28,494.1) sq.ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Accompanied Housing/ Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	2- Whitbeck Street/ 1-Marina Road



Legend

EA Projects

07-10

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-10
Project Title	Base R	Roadway Improvements
Fiscal Year		FY12
Funding Source		BA01
Project Number		FTEV993011
Project Type	Improvement	
Demolition Linkage	None	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	62,519.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	9,140 sq. ft. ST-123- 4,259 sq. ft. SS-122- 1,713 sq. ft. ST-68
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Industrial/ Operations & Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Terry Avenue/ 1-Tully Street



Legend

EA Projects- Alternative Sitings

07-10

Other Alternative Sitings

Installation Boundary
Existing Structures

Existing Office

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		07-10
Project Title	Base F	Roadway Improvements
Fiscal Year		FY12
Funding Source		BA01
Project Number		FTEV993011
Project Type	Improvement	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	80,883 (SB7)/ 4,878.2 (SB8)	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	23,621.3 sq. ft. LF-20 (SB7); 9,701.2 sq. ft. SD-189 (SB7); 2,944.7 sq. ft. ST-123 (SB7); 4,255 sq. ft. SS-122 (SB7); 4,334.5 sq. ft. LF-20 (SB8)
Q/D Clear Zone	Source	Airfield Stand-Off 5,169.8 sq. ft. (SB7) Airfield Stand-Off 4,878.2 sq. ft. (SB8)
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7&8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Industrial/ Open Space/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Terry Avenue/ 2-Tully Street



Legend

EA Projects

07-10B

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

— AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands
Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 5

Stormwater Ponds

Monitoring_Wells


Trees

Exotic Plants

Rare Animals

Rare Plants
Sub-Basin
Key Map

11
10
2
4
7
8
11
2
3
4
6
7
8
8



	Impacts by Project	
1391 Information	Description	
EA Project Number		07-10
Project Title	Base R	Roadway Improvements
Fiscal Year		FY12
Funding Source		BA01
Project Number		FTEV993011
Project Type	Improvement	
Demolition Linkage	None	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	62,519.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	9,140 sq. ft. ST-123- 4,259 sq. ft. SS-122- 1,713 sq. ft. ST-68
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Industrial/ Operations & Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Terry Avenue/ 1-Tully Street



Legend

EA Projects- Alternative Sitings

07-10

Other Alternative Sitings

Installation Boundary
Existing Structures

Existing Office

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	De	escription
EA Project Number		07-10
Project Title	Squadron Ope	erations Facility 6 SOS
Fiscal Year		FY12
Funding Source		MFP-11
Project Number	FT	EV993033
Project Type		New
Demolition Linkage	Building 90140	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	18,716.3	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	18,716.3 sq. ft. ST-123
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects

07-11

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	D	escription
EA Project Number		07-10
Project Title	Squadron Op	erations Facility 6 SOS
Fiscal Year		FY12
Funding Source		MFP-11
Project Number	Fi	TEV993033
Project Type	New	
Demolition Linkage	Building 90140	
Availability of On-site Utilities	Ÿ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	18,716.3	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	6,570 sq. ft. ST-123
Q/D Clear Zone	Source	14,261 sq. ft. Airfield and Aircraft Stand-Off
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects- Alternative Sitings

07-11

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project		
1391 Information	Description	
EA Project Number		-01
Project Title	RED HORSE Vehicle	Maintenance Facility
Fiscal Year	FY	(07
Funding Source	BA	NO1
Project Number	FTEV003009	
Project Type	New	
Demolition Linkage	Buildings 91127, 91128 & 91132	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building		
Footprint	25,818.8 (SB8), 6,677.5 (SB11)	
Square Footage of Parking Lot or		
Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	4,167.8 (SB11)
	sq.ft.impacted and not covered	
Un-permitted Wetland Impacts	under existing permits	0.0
	sq.ft. impacted and covered under	
Permitted Wetland Impacts	existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8 & 11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Υ
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land	surrounding land use designations	
Uses	from Land Use Plan	Industrial
	# curb cuts on streets to access	Brimms Road/
Adjacent Streets/ Intersections	facility	Golf Course Road



Legend

EA Projects

08-01

Other EA Projects

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone
100-year Floodplain

IRP Sites

Q/D Arcs Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 5


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project		
1391 Information	Description		
EA Project Number	(08-01	
Project Title	RED HORSE Vehi	cle Maintenance Facility	
Fiscal Year		FY07	
Funding Source		BA01	
Project Number	FTE	FTEV003009	
Project Type	New		
Demolition Linkage	Buildings 91127, 91128 & 91132		
Availability of On-site Utilities	Y		
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building			
Footprint	32,496.0		
Square Footage of Parking Lot or			
Roadway Improvement	0.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	32,496.0
	sq.ft.impacted and not covered	
Un-permitted Wetland Impacts	under existing permits	32,380.0
	sq.ft. impacted and covered under	
Permitted Wetland Impacts	existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	10
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Υ
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land	surrounding land use designations	
Uses	from Land Use Plan	Industrial/ Open Space
	# curb cuts on streets to access	
Adjacent Streets/ Intersections	facility	Golf Course Road



Legend

EA Projects- Alternative Sitings

08-01

Other Alternative Sitings

Installation Boundary

Existing Structures

AICUZ Noise Contours

Airfield Clear Zone

Demolitions

100-year Floodplain

IRP Sites

Q/D Arcs
Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project		
1391 Information	Desc	ription
EA Project Number	30	3-02
Project Title	RED HORSE Mobility and	Training Facility (823 RHS)
Fiscal Year	F`	Y08
Funding Source	Ba	A01
Project Number	FTEV	023005
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building		
Footprint	9,566.7	
Square Footage of Parking Lot or	_	
Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
	sq.ft.impacted and not covered	
Un-permitted Wetland Impacts	under existing permits	0.0
	sq.ft. impacted and covered under	
Permitted Wetland Impacts	existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land	surrounding land use designations	
Uses	from Land Use Plan	Industrial/ Open Space
	# curb cuts on streets to access	
Adjacent Streets/ Intersections	facility	Independence Road



Legend

EA Projects

08-02

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

---- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain
IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project		
1391 Information	Description	
EA Project Number		08-02
Project Title	RED HORSE Mobility a	nd Training Facility (823 RHS)
Fiscal Year		FY08
Funding Source		BA01
Project Number	FTE	EV023005
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building		
Footprint	9,566.7	
Square Footage of Parking Lot or		
Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
	sq.ft.impacted and not covered	
Un-permitted Wetland Impacts	under existing permits	0.0
	sq.ft. impacted and covered under	
Permitted Wetland Impacts	existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land	surrounding land use designations	
Uses	from Land Use Plan	Open Space
	# curb cuts on streets to access	
Adjacent Streets/ Intersections	facility	Independence Road



Legend

EA Projects- Alternative Sitings

08-02

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3


Category 4


Category 5

Stormwater PondsMonitoring_Wells

Trees

Rare Animals





	Impacts by Project	The second secon
1391 Information	Description	
EA Project Number		08-03
Project Title	Shoppet	te Facility, East Side
Fiscal Year		FY10
Funding Source		NAF
Project Number	F	TEV005004
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	19,328.0	
Square Footage of Parking Lot or Roadway Improvement	7,344.3	4

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1-Loop Road



Legend

EA Projects

08-03

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

--- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		08-03
Project Title	Shoppet	te Facility, East Side
Fiscal Year		FY10
Funding Source		NAF
Project Number	F	TEV005004
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	19,328.0	
Square Footage of Parking Lot or Roadway Improvement	7,283.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	7
Surface Water Sub-Basin	Sub-basin number	9
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1-Independence Road



Legend

EA Projects- Alternative Sitings

08-03

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5
Stormwater Ponds


Monitoring_Wells


Monitoring_vveils

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		08-04
Project Title	Construct Eastsid	de Dormitory (144 Person)
Fiscal Year		FY12
Funding Source		BA01
Project Number	F1	TEV993013
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	20,501.0	
Square Footage of Parking Lot or Roadway Improvement	78,379.3	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft, by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space/ Unaccompanied Housing
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Loop Road



Legend

EA Projects

08-04

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		08-04
Project Title	Construct Eastsi	de Dormitory (144 Person)
Fiscal Year		FY12
Funding Source		BA01
Project Number	F	TEV993013
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	20,501.0	
Square Footage of Parking Lot or Roadway Improvement	20,638.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	29,894.2
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	2- East Road



Legend

EA Projects- Alternative Sitings

08-04

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

IRP Sites

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	A STATE OF THE STA
1391 Information	Description	
EA Project Number		08-05
Project Title	East sid	de Fitness Center
Fiscal Year		FY12
Funding Source		BA01
Project Number	F	TEV003023
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	47,858.4	
Square Footage of Parking Lot or Roadway Improvement	28,256.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space/ Unaccompanied Housing
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1-New Road Project #99-3013



Legend

EA Projects

08-05

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

! Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs
Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	-1	Description
EA Project Number		08-05
Project Title	Eastsi	ide Fitness Center
Fiscal Year		FY12
Funding Source		BA01
Project Number		FTEV003023
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	47,858.4	
Square Footage of Parking Lot or Roadway Improvement	29,899.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Commercial/ Unaccompanied Housing
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Loop Road



Legend

EA Projects- Alternative Sitings

08-05

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain **IRP Sites**

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5 Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		08-06
Project Title	Widen In	idependence Road
Fiscal Year		FY12
Funding Source		BA01
Project Number	F	TEV033013
Project Type	Improvement	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	42,307.2	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial/ Medical/Open Space/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Independence Road/ 1- Loop Road



Legend

EA Projects

08-06

Other EA Projects

____Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3
Category 4

Category 5


Stormwater Ponds

Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		08-06
Project Title	Widen I	ndependence Road
Fiscal Year		FY12
Funding Source		BA01
Project Number	F	TEV033013
Project Type	Improvement	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	51,589.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	10
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Independence Road/ 1- Loop Road



Legend

EA Projects- Alternative Sitings

08-06

Other Alternative Sitings

Installation Boundary **Existing Structures**

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project			
1391 Information		Description	
EA Project Number		08-07	
Project Title	AFLD Waiver,	Alter Independence Road	
Fiscal Year		FY12	
Funding Source		BA01	
Project Number	FTEV033018		
Project Type	Improvement		
Demolition Linkage	None		
Availability of On-site Utilities	Y		
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	0.0		
Square Footage of Parking Lot or Roadway Improvement	97,810.3		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	Category 3, 4, 5- (18,642), (43,139.7), (46,137.4) sq.ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Independence Road/ Loop Road



Legend

EA Projects

08-07

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5


Stormwater Ponds

Monitoring_Wells

Trees

Rare Animals





Impacts by Project			
1391 Information	tion Description		
EA Project Number		08-07	
Project Title	AFLD Waiver,	Alter Independence Road	
Fiscal Year		FY12	
Funding Source		BA01	
Project Number	F	TEV033018	
Project Type	Improvement		
Demolition Linkage	None		
Availability of On-site Utilities	Υ		
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	0.0		
Square Footage of Parking Lot or Roadway Improvement	140,622.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	1,555.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	Category 3, 4, 5- (39,750), (62,687), (67,887) sq.ft.
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Independence Road/ Loop Road



Legend

EA Projects- Alternative Sitings

08-07

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

IRP Sites

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	W. Constant	
1391 Information	1391 Information Description		
EA Project Number		08-08	
Project Title	SOF UAV Squa	adron Operations Facility	
Fiscal Year		FY12	
Funding Source		MFP-11	
Project Number	- F1	ΓEV043011	
Project Type	New		
Demolition Linkage	None		
Availability of On-site Utilities			
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	8,000.0		
Square Footage of Parking Lot or Roadway Improvement	0.0	1	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Independence Road



Legend

EA Projects

80-80

Mar EA Projects

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

Q/D Arcs

Wetlands
Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project		
1391 Information	Des	cription	
EA Project Number	(08-08	
Project Title	SOF UAV Squadr	on Operations Facility	
Fiscal Year		FY12	
Funding Source	M	FP-11	
Project Number	FTE	V043011	
Project Type		New	
Demolition Linkage		Vone	
Availability of On-site Utilities			
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	23,000.0		
Square Footage of Parking Lot or Roadway Improvement	13,586.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	23,000.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	36,496.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	New Aircraft parking Apron- Project # 08-09



Legend

EA Projects- Alternative Sitings

08-08

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Proje	ct
1391 Information		Description
EA Project Number		08-09
Project Title	SOF UAV Ma	intenance Hangar/Parking Apron
Fiscal Year	3,30,000,000	FY12
Funding Source		MFP-11
Project Number		FTEV043012
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		and the second s
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	15,000.0	
Square Footage of Parking Lot or Roadway Improvement	157,523.2	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC#	0.0
Q/D Clear Zone	Source	Airfield Stand-Off: 8,815.9 sq. ft.
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Υ
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Maintenance Haul Road



Legend

EA Projects

08-09

Other EA Projects

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

100-year Floodplain

Airfield Clear Zone

IRP Sites

Q/D Arcs
Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project			
1391 Information	Des	cription	
EA Project Number	(08-09	
Project Title	SOF UAV Maintenan	ce Hangar/Parking Apron	
Fiscal Year		-Y12	
Funding Source	M	FP-11	
Project Number	FTE	V043012	
Project Type	New		
Demolition Linkage	None		
Availability of On-site Utilities			
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	15,000.0		
Square Footage of Parking Lot or Roadway Improvement	368,605.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	383,605.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	383,605.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Υ
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Maintenance Haul Road



Legend

EA Projects- Alternative Sitings

08-09

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

— AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	Carlotte Carlotte
1391 Information	Description	
EA Project Number		11-01
Project Title	Construct Workbays at	Auto Hobby Shop, Building 90612
Fiscal Year		FY05
Funding Source		NAF
Project Number	F	TEV045002
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	2,720.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial/ Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Hamby Place



Legend

EA Projects

11-01

Other EA Projects

Installation Boundary

Existing Structures

AICUZ Noise Contours

Airfield Clear Zone

Demolitions

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-01
Project Title	Construct Workbays at	Auto Hobby Shop, Building 90612
Fiscal Year		FY05
Funding Source		NAF
Project Number	F	TEV045002
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	5,624.0	
Square Footage of Parking Lot or Roadway Improvement	15,676.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	6,605.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	.11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Community Commercial/ Industrial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Hamby Place



Legend

EA Projects- Alternative Sitings

11-01

Other Alternative Sitings

Installation Boundary **Existing Structures**

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project		
1391 Information	Description		
EA Project Number		11-02	
Project Title	Fill/Clear Wetland	ds, Helicopter Landing Pad	
Fiscal Year		FY06	
Funding Source		BA01	
Project Number	= 1.E1	TEV03-1049	
Project Type	New		
Demolition Linkage	None		
Availability of On-site Utilities			
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	0.0		
Square Footage of Parking Lot or Roadway Improvement	130,078.6		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	130,078.6
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	136,388.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Air Safety Zone/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	None



Legend

EA Projects

11-02

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project		
1391 Information	Description		
EA Project Number		11-02	
Project Title	Fill/Clear Wetlan	ids, Helicopter Landing Pad	
Fiscal Year		FY06	
Funding Source		BA01	
Project Number	F.	TEV03-1049	
Project Type	New		
Demolition Linkage	None		
Availability of On-site Utilities			
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	0.0		
Square Footage of Parking Lot or Roadway Improvement	130,078.6		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	Airfield and Aircraft Stand-off- 14,442 sq. ft.
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Air Safety Zone/ Airfield/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Maintenance Haul Road



Legend

EA Projects- Alternative Sitings

11-02

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs
Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project		
1391 Information	Description	
EA Project Number		11-03
Project Title	ADAL Security Force	es Operations (Current Mission)
Fiscal Year		FY07
Funding Source		BA01
Project Number	F	TEV943001
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	4,698.8	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	6
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Cody Avenue



Legend

EA Projects

11-03

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project			
1391 Information	Description		
EA Project Number		11-03	
Project Title	ADAL Security Force	es Operations (Current Mission)	
Fiscal Year		FY07	
Funding Source		BA01	
Project Number		FTEV943001	
Project Type	Addition		
Demolition Linkage	None		
Availability of On-site Utilities	Υ		
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	4,000.0		
Square Footage of Parking Lot or Roadway Improvement	0.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	8
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Cody Avenue



Legend

EA Projects- Alternative Sitings

11-03

Other Alternative Sitings

Installation Boundary **Existing Structures**

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project		
1391 Information	Description		
EA Project Number		11-04	
Project Title	SOF Engine Mair	ntenance and Storage Shop	
Fiscal Year		FY07	
Funding Source		MFP-11	
Project Number	F	TEV973006	
Project Type	New		
Demolition Linkage	None		
Availability of On-site Utilities			
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	21,600.0		
Square Footage of Parking Lot or Roadway Improvement	75,329.4		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	6,755.6
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	5,048.3 sq. ft. SS-130 & 132
Q/D Clear Zone	Source	1,250 ft Stand-Off- 41,814.2 sq. ft.
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	_ 11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	3-Red Horse Road



Legend

EA Projects

11-04

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-04
Project Title	SOF Engine Main	tenance and Storage Shop
Fiscal Year		FY07
Funding Source		MFP-11
Project Number	- 6	TEV973006
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	44,521.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	26,508 sq. ft. LF-19
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Operations Maintenance/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	New Road- Project # 11-15



Legend

EA Projects- Alternative Sitings

11-04

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

— AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Cotogon/ A

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number	1	1-05
Project Title	Fire Crash/F	Rescue Station
Fiscal Year	F	Y07
Funding Source	В	A01
Project Number	FTE	/973018
Project Type	New	
Demolition Linkage	Buildings 90735, 90736, 90737, 90739 & 90749	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	32,863.1	
Square Footage of Parking Lot or Roadway Improvement	66,451.1	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	8,897.7 sq. ft. SS-125
Q/D Clear Zone	Source	Airfield Stand-Off 3,266.5 sq. ft.
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	3
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	- N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administration/ Airfield/ Operations Maintenance/ Community Commercial/ Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	2-Benett Avenue/ 1-Bedel Street



Legend

EA Projects

11-05

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number	11	1-05
Project Title	Fire Crash/F	Rescue Station
Fiscal Year	F	Y07
Funding Source	В	A01
Project Number	FTEV	/973018
Project Type	New	
Demolition Linkage	Buildings 90735, 90736, 90737, 90739 & 90749	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	32,863.1	
Square Footage of Parking Lot or Roadway Improvement	87,019.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	120,329.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	Helicopter Runway Stand-Off- 45 sq. ft.
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Operations Maintenance/ Industrial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Brimms Road



Legend

EA Projects- Alternative Sitings

11-05

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Odicgory 2

Category 3

Category 4

Category 5

Stormwater Ponds


Monitoring_Wells


Trees

Exotic Plants

Rare Animals

- Itale Aminale





Impacts by Project			
1391 Information		Description	
EA Project Number		11-06	
Project Title	25th Intelligence \$	Squadron Operations Facility	
Fiscal Year		FY07	
Funding Source		BA01	
Project Number	F	TEV013021	
Project Type	New		
Demolition Linkage	Buildings 90758, 90760 & 90763		
Availability of On-site Utilities	Y		
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building Footprint	13,300.0		
Square Footage of Parking Lot or Roadway Improvement	29,232.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administration/ Community Commercial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1-Frazier Street/ Cruz Avenue



Legend

EA Projects

11-06

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Descrip	otion
EA Project Number	11-0	6
Project Title	25th Intelligence Squadr	on Operations Facility
Fiscal Year	FY0	7
Funding Source	BA0	1
Project Number	FTEV01	3021
Project Type	Nev	V
Demolition Linkage	Buildings 90758,	90760 & 90763
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	3,325.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	.11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	New Road- Project # 11-07



Legend

EA Projects- Alternative Sitings

11-06

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain
IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information		Description
EA Project Number		11-07
Project Title	Reali	gn Cruz Avenue
Fiscal Year		FY07
Funding Source		BA01
Project Number	F	TEV033014
Project Type	New	
Demolition Linkage	Building 90604	
Availability of On-site Utilities	Ϋ́	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	34,149.5	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	4,687.8 sq. ft. SS-125
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	4
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Frazier Street/ 2- Bedel Street/ 1 Cody Avenue



Legend

EA Projects

11-07

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5

Stormwater Ponds


Monitoring Wells


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Des	cription
EA Project Number		11-07
Project Title	Realign	Cruz Avenue
Fiscal Year		FY07
Funding Source		BA01
Project Number	FTE	V033014
Project Type	New	
Demolition Linkage	Building 90604	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	33,712.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	8,948 sq. ft. SS-125
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Frazier Street/ 2- Bedel Street/ 1 Cody Avenue



Legend

EA Projects- Alternative Sitings

11-07

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project		
1391 Information	Description		
EA Project Number		11-08	
Project Title	SOF Squad	dron Operations, Tallon II	
Fiscal Year		FY07	
Funding Source		MFP-11	
Project Number	FTEV043005		
Project Type	New		
Demolition Linkage	Buildings 90726 & 90728		
Availability of On-site Utilities	Y		
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building			
Footprint	15,903.0		
Square Footage of Parking Lot or			
Roadway Improvement	25,888.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	56.4 sq. ft. SS-125
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	-11
Storm Surge Category	sq.ft. by category	N
Feet from Potable Water Well	within 200 ft (y/n)	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Bedel Street



Legend

EA Projects

11-08

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project		
1391 Information	Description		
EA Project Number		11-08	
Project Title	SOF Square	dron Operations, Talon II	
Fiscal Year		FY07	
Funding Source		MFP-11	
Project Number		FTEV043005	
Project Type	New		
Demolition Linkage	Buildings 90726 & 90728		
Availability of On-site Utilities	Υ		
Working Population			
Impervious Surface Area	Square Footage		
Square Footage of Building			
Footprint	3,901.0		
Square Footage of Parking Lot or			
Roadway Improvement	0.0		

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	7
Storm Surge Category	sq.ft. by category	N
Feet from Potable Water Well	within 200 ft (y/n)	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects- Alternative Sitings

11-08

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

100-year Floodplain

Airfield Clear Zone

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project				
1391 Information	Description			
EA Project Number		11-09		
Project Title	Addition	to Visiting Quarters		
Fiscal Year	- 10-20-20-20-20-20-20-20-20-20-20-20-20-20	FY08		
Funding Source		BA01		
Project Number	F	TEV023010		
Project Type	Addition			
Demolition Linkage	None			
Availability of On-site Utilities	Y			
Working Population	332			
Impervious Surface Area	Square Footage			
Square Footage of Building Footprint	4,592.7			
Square Footage of Parking Lot or Roadway Improvement	0.0			

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	-11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects

11-09

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Monitoring_Wells


Stormwater Ponds

Trees

Exotic Plants

Rare Animals





Impacts by Project		
1391 Information Description		
EA Project Number	11	1-09
Project Title	Addition to V	isiting Quarters
Fiscal Year	F	Y08
Funding Source	B	A01
Project Number	FTEV	023010
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population	332	
Impervious Surface Area	Square Footage	
Square Footage of Building		
Footprint	19,935 (SB 4)	
Square Footage of Parking Lot or	13,462 sq. ft. (SB 4)/	
Roadway Improvement	76,538 sq. ft. (SB 11)	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
	sq.ft.impacted and not covered	
Un-permitted Wetland Impacts	under existing permits	1,264.0
	sq.ft. impacted and covered under	
Permitted Wetland Impacts	existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land	surrounding land use designations	
Uses	from Land Use Plan	Open Space
	# curb cuts on streets to access	
Adjacent Streets/ Intersections	facility	2- Tully Street



Legend

EA Projects- Alternative Sitings

11-09

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4


Category 5 Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-10
Project Title	ADAL	USAFSOS Facility
Fiscal Year		FY09
Funding Source		BA01
Project Number	- (I	FTEV023013
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	13,094.0 (SB11)	
Square Footage of Parking Lot or Roadway Improvement	4,579.8 (SB4)/ 19,018.0 (SB11)	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	1
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administrative/ Industrial/ Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects

11-10

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

! Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-10
Project Title	ADA	L USAFSOS Facility
Fiscal Year		FY09
Funding Source		BA01
Project Number		FTEV023013
Project Type	Addition	
Demolition Linkage	None	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	29,793.0	
Square Footage of Parking Lot or Roadway Improvement	61,055.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	6,869.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects- Alternative Sitings

11-10

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-11
Project Title	SOF C-	-130 Aircraft Apron
Fiscal Year		FY09
Funding Source		MFP-11
Project Number	FTEV043004	
Project Type	New	
Demolition Linkage	Building 90823	
Availability of On-site Utilities	Ÿ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	416,459.3	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	21,074.3
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	7,618.7 sq. ft. ST-217
Q/D Clear Zone	Source	1250 ft Standoff 226,665.1 sq. ft. Airfield Stand-Off 20,819.8 sq. ft.
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Red Horse Road



Legend

EA Projects

11-11

Other EA Projects

_____Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Descri	ption
EA Project Number	11-	11
Project Title	SOF C-130 A	ircraft Apron
Fiscal Year	FY	09
Funding Source	MFP	-11
Project Number	FTEV0	43004
Project Type	Ne	w
Demolition Linkage	Building	90823
Availability of On-site Utilities	Ŷ	37737
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	499,644.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	Airfield Stand-Off- 499,644 sq. ft.
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	7
Surface Water Sub-Basin	Sub-basin number	8
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Operations Maintenance/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects- Alternative Sitings

11-11

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

IRP Sites

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-12
Project Title	SOF Surviv	al Equipment Shop
Fiscal Year		FY09
Funding Source		MFP-11
Project Number	FT	EV043007
Project Type	New	
Demolition Linkage	Building 90731	
Availability of On-site Utilities	Ÿ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building		
Footprint	15,516.0	
Square Footage of Parking Lot or	420954	
Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	15,516 sq. ft. SS-125
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sg.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Bennett Avenue/ Bedel Stree



Legend

EA Projects

11-12

Other EA Projects

Installation Boundary

Existing Structures

- AICUZ Noise Contours

Airfield Clear Zone

Demolitions

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-12
Project Title	SOF Survi	val Equipment Shop
Fiscal Year		FY09
Funding Source		MFP-11
Project Number	F1	TEV043007
Project Type	New	
Demolition Linkage	Building 90731	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	15,516.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	15,516 sq. ft. SS-125
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Bennett Avenue/ Bedel Street



Legend

EA Projects- Alternative Sitings

11-12

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

IRP Sites

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-13
Project Title	Hydra	nt Fueling System
Fiscal Year		FY10
Funding Source		DLA
Project Number	F	TEV973016
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Linear Footage	10,000.0	
Square Footage of Building Footprint	3,150.0	
Square Footage of Parking Lot or Roadway Improvement	44,657.3	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	27,128.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	4,760.7
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	Y
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Industrial/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1-Brimms Road



Legend

EA Projects

11-13

Other EA Projects

_____Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project		
1391 Information	Description	
EA Project Number	1	1-13
Project Title	Hydrant F	ueling System
Fiscal Year	F	Y10
Funding Source		DLA
Project Number	FTE	/973016
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building		
Footprint	3,919.0	
Square Footage of Parking Lot or		
Roadway Improvement	36,031.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	39,661.0
·	sq.ft.impacted and not covered	
Un-permitted Wetland Impacts	under existing permits	33,529.0
	sq.ft. impacted and covered under	
Permitted Wetland Impacts	existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	N
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Υ
Air Emissions	permit modification required (y/n)	Υ
Compatibility with Adjacent Land	surrounding land use designations	
Uses	from Land Use Plan	Industrial/ Open Space
	# curb cuts on streets to access	
Adjacent Streets/ Intersections	facility	1-Brimms Road



Legend

EA Projects- Alternative Sitings

11-13

Other Alternative Sitings
Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-14
Project Title	Visiting	Officers Quarters
Fiscal Year		FY10
Funding Source		BA01
Project Number		TEV033006
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population	40	
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	10,913.3	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects

11-14

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

---- AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-14
Project Title	Visiting	Officers Quarters
Fiscal Year		FY10
Funding Source		BA01
Project Number	F	TEV033006
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities	Υ	
Working Population	40	
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	10,913.3	
Square Footage of Parking Lot or Roadway Improvement	0.0	4 1

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	3,831.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	2
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects- Alternative Sitings

11-14

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

— AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-15
Project Title	Realign Cr	uz Avenue Phase 2
Fiscal Year		FY10
Funding Source	MIL	CON BA01
Project Number	FT	EV033015
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		4
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	57,457.5	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	8,837.2 sq. ft. LF-19
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	- 11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Open Space/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Red Horse Road/ 1- Frazier Street



Legend

EA Projects

11-15

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5

Stormwater Ponds


Monitoring Wells


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Descrip	tion
EA Project Number	11-19	5
Project Title	Realign Cruz Ave	enue Phase 2
Fiscal Year	FY10)
Funding Source	MILCON	BA01
Project Number	FTEV033	3015
Project Type	New	1
Demolition Linkage	None	Э
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	0.0	
Square Footage of Parking Lot or Roadway Improvement	52,421.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	9,917 sq. ft. LF-19
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Red Horse Road/ 1- Frazier Street



Legend

EA Projects- Alternative Sitings

11-15

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands
Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	De	escription
EA Project Number		11-16
Project Title	SOF DASH-21	Maintenance Facility
Fiscal Year		FY10
Funding Source		MFP-11
Project Number	FT	EV043008
Project Type		New
Demolition Linkage	Builling 90743	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	10,836.1	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	10,836.1 sf SS-125
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Ŷ
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Operations Maintenance/ Industrial
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Bennett Avenue/ Bedel Street



Legend

EA Projects

11-16

Other EA Projects

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number	11	-16 & 11-17
Project Title	SOF DASH-21 Maintenance	Facility & Maintenance Storage Facility
Fiscal Year		FY10
Funding Source		MFP-11
Project Number	FTEV043008 & FTEV 04-3009	
Project Type	New	
Demolition Linkage	Builling 90743	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	10,836.0	
Square Footage of Parking Lot or Roadway Improvement	5,589.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	6,386 sq. ft. LF-19
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Operations Maintenance/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- New Road- Project # 11-15



Legend

EA Projects- Alternative Sitings

11-16 & 11-17

Other Alternative Sitings
Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

IRP Sites

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	De	escription
EA Project Number		11-17
Project Title	SOF Mainten	ance Storage Facility
Fiscal Year		FY10
Funding Source		MFP-11
Project Number	FT	EV043009
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	5,413.3	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	5,413.3 sf LF-19
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	New Road Project #03-3015



Legend

EA Projects

11-17

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number	11	-16 & 11-17
Project Title	SOF DASH-21 Maintenance	Facility & Maintenance Storage Facility
Fiscal Year		FY10
Funding Source		MFP-11
Project Number	FTEV043008 & FTEV 04-3009	
Project Type	New	
Demolition Linkage	Builling 90743	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	10,836.0	
Square Footage of Parking Lot or Roadway Improvement	5,589.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	6,386 sq. ft. LF-19
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Operations Maintenance/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- New Road- Project # 11-15



Legend

EA Projects- Alternative Sitings

11-16 & 11-17

Other Alternative Sitings
Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

IRP Sites

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds

Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information		Description
EA Project Number		11-18
Project Title	SOF C-130 Tal	lon II Maintenance Hangar
Fiscal Year		FY11
Funding Source		MFP-11
Project Number	FTEV043010	
Project Type	New	
Demolition Linkage	Buildings 90812 & 90815	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	41,062.8	
Square Footage of Parking Lot or Roadway Improvement	31,270.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfield/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1-Frazier Street



Legend

EA Projects

11-18

Other EA Projects

Installation Boundary

Existing Structures

- AICUZ Noise Contours

Airfield Clear Zone

Demolitions

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Di	escription
EA Project Number		11-18
Project Title	SOF C-130 Talo	n II Maintenance Hangar
Fiscal Year		FY11
Funding Source		MFP-11
Project Number	FTEV043010	
Project Type	New	
Demolition Linkage	Buildings 90812 & 90815	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	41,063.0	
Square Footage of Parking Lot or Roadway Improvement	721,608.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	691,101.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	446,560.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Air Safety Zone/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Bennett Avenue/ Bedel Street



Legend

EA Projects- Alternative Sitings

11-18

Other Alternative Sitings

Installation Boundary **Existing Structures**

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

IRP Sites

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information		Description
EA Project Number		11-19
Project Title	Squadron Ope	erations Facility. 18 FLTS
Fiscal Year		FY12
Funding Source		MFP-11
Project Number	F	TEV963012
Project Type		New
Demolition Linkage	Building	gs 99134 & 99135
Availability of On-site Utilities		Υ
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	49,380.6	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	13,881.3 sf SD-212
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	6
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Industrial/ Open Space/ Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Red Horse Road



Legend

EA Projects

11-19

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain
IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4
Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-19
Project Title	Squadron Ope	erations Facility. 18 FLTS
Fiscal Year		FY12
Funding Source		MFP-11
Project Number	FTEV963012	
Project Type	New	
Demolition Linkage	Buildings 99134 & 99135	
Availability of On-site Utilities	Y	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	49,380.6	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	46,930.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Red Horse Road



Legend

EA Projects- Alternative Sitings

11-19

Other Alternative Sitings

Installation Boundary
Existing Structures

Existing Office

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	Description	
EA Project Number		11-20
Project Title	Operations Grou	p/Operations Plans Facility
Fiscal Year		FY12
Funding Source		BA01
Project Number	FTEV973009	
Project Type	New	
Demolition Linkage	Buildings 90748 & 90755	
Availability of On-site Utilities	Υ	
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	27,000.0	
Square Footage of Parking Lot or Roadway Improvement	32,768.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	22,432 sf SS-125
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	12
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Administration/ Industrial/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	2- Cruz Avenue/ 1-Bedel Street



Legend

EA Projects

11-20

Other EA Projects

_____Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds

Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information	De	scription
EA Project Number		11-20
Project Title	Operations Group/	Operations Plans Facility
Fiscal Year		FY12
Funding Source		BA01
Project Number	FTE	EV973009
Project Type		New
Demolition Linkage	Buildings	90748 & 90755
Availability of On-site Utilities		Υ
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	27,000.0	
Square Footage of Parking Lot or Roadway Improvement	33,117.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft, impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	Airfield Stand-Off- 79 sq. ft.
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	-1
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	1- Bennett Avenue



Legend

EA Projects- Alternative Sitings

11-20

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2 Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information		Description
EA Project Number		11-21
Project Title	SOF JSOU H	leadquarters Facility, Phase 2
Fiscal Year		FY12
Funding Source		MFP-11
Project Number		FTEV023014
Project Type		New
Demolition Linkage		None
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	6,000.0	
Square Footage of Parking Lot or Roadway Improvement	0.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects

11-21

Mother EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours
Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





	Impacts by Project	
1391 Information		Description
EA Project Number		11-21 & 04-07
Project Title	SOF JSOU Hea	adquarters Facility, Phase 2 & 3
Fiscal Year		FY12
Funding Source		MFP-11
Project Number	_	FTEV023014
Project Type	New	
Demolition Linkage	None	
Availability of On-site Utilities		
Working Population		
Impervious Surface Area	Square Footage	
Square Footage of Building Footprint	29,000.0	
Square Footage of Parking Lot or Roadway Improvement	60,769.0	

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	43,066.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	N
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Outdoor Recreation
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	Tully Street



Legend

EA Projects- Alternative Sitings

11-21 & 04-07

Other Alternative Sitings

Installation Boundary
Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites
Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals





Impacts by Project					
1391 Information	, c	Description			
EA Project Number		11-22			
Project Title	SOF CV-22	Aircraft Parking Apron			
Fiscal Year		FY12			
Funding Source		MFP-11			
Project Number	FTEV043014				
Project Type	New				
Demolition Linkage	None				
Availability of On-site Utilities					
Working Population					
Impervious Surface Area	Square Footage				
Square Footage of Building Footprint	0.0				
Square Footage of Parking Lot or Roadway Improvement	129,223.6				

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	129,223.4
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Υ
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	11
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfleid/ Open Space
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	None



Environmental Assessment Hurlburt Field Hurlburt Field, Florida

Legend

EA Projects

11-22

Other EA Projects

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

AICOZ Noise Contours

Airfield Clear Zone
100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5
Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals

Rare Plants





	Impacts by Project	The state of the s			
1391 Information	D	escription			
EA Project Number		11-22			
Project Title	SOF CV-22	Aircraft Parking Apron			
Fiscal Year		FY12			
Funding Source		MFP-11			
Project Number	FTEV043014				
Project Type	New				
Demolition Linkage	None				
Availability of On-site Utilities					
Working Population					
Impervious Surface Area	Square Footage				
Square Footage of Building Footprint	0.0				
Square Footage of Parking Lot or Roadway Improvement	129,728.0				

Site Characteristics	Quantity or Identifier	Description
Floodplain Impacts	sq.ft.	0.0
Un-permitted Wetland Impacts	sq.ft.impacted and not covered under existing permits	0.0
Permitted Wetland Impacts	sq.ft. impacted and covered under existing permits	0.0
RTE Habitat	sq.ft.	0.0
Cultural Resources	NRHP site #	0.0
IRP	IRP or AOC #	0.0
Q/D Clear Zone	Source	0.0
AICUZ	within 65db contour	Y
Tree Removal (>6"dbh)	total number requiring removal	0
Surface Water Sub-Basin	Sub-basin number	
Storm Surge Category	sq.ft. by category	N
Pre-Construction Permit Issues	list - NPDES, PTC, etc	N
Hazardous Materials	future satellite accum. pt. (y/n)	Y
Air Emissions	permit modification required (y/n)	N
Compatibility with Adjacent Land Uses	surrounding land use designations from Land Use Plan	Airfleid/ Operations Maintenance
Adjacent Streets/ Intersections	# curb cuts on streets to access facility	None



Environmental Assessment Hurlburt Field Hurlburt Field, Florida

Legend

EA Projects- Alternative Sitings

11-22

Other Alternative Sitings

Installation Boundary

Existing Structures

Demolitions

AICUZ Noise Contours

Airfield Clear Zone

100-year Floodplain

IRP Sites

Q/D Arcs

Wetlands

Sub-Basins

Storm Surge Category

Category 1

Category 2

Category 3

Category 4

Category 5


Stormwater Ponds


Monitoring_Wells

Trees

Exotic Plants

Rare Animals







This page intentionally left blank.

1. COMPONENT	FY 2007 MILITARY CONSTRUCTION PROJECT DATA						2. DATE
AIR FORCE		(compu	iter gen	erate	d)		
3. INSTALLATION AND LOCATION 4. PROJECT TITLE						TLE	
HURLBURT FIELD	, FLORI	DA		ADAL	SECURITY	FORCE OPERA	TIONS
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)
27596		730-835	FT	EV943	001	1	,900
	 ,	9. COS	T ESTI	ATES			
				T .		UNIT	COST
		ITEM		U/M	QUANTITY		
ADAL SECURITY FO	RCES OPE	RATIONS					1,343
ADDITION				SM	536	1,655	(887)
ALTERATIONS				SM	622	720	(448)
ANTITERRORISM I	FORCE PRO	DIECTION		SM	1,158	7	(8)
SUPPORTING FACII	ITIES				j		365
UTILITIES				ıs	}		(100)
SITE IMPROVEME	NTS			LS			(35)
PAVEMENTS				LS			(85)
COMMUNICATION	System			LS			(145)
SUBTOTAL				1			1,708
CONTINGENCY	(5.0	\$)			Ì		85
TOTAL CONTRACT COST						·	1,793
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %)							102
TOTAL REQUEST				4			1,896
TOTAL REQUEST ()	ROUNDED)		1		.		1,900
EQUIPMENT FROM	OTHER AP	PROPRIATIONS (NON-ADD)				}	(110.0)

10. Description of Proposed Construction: Reinforced concrete foundation and floor slab, masonry walls, and sloped metal roof. Functional areas include administration, quardmount, conference, locker and shower rooms, and a temporary holding cell. Alter interior of existing facility to accommodate addition. Comply with DoD force protection requirements per unified facilities criteria.

Air Conditioning: 30 Tons

11. REQUIREMENT: 1,851 SM ADEQUATE: 693 SM SUBSTANDARD: 622 SM

PROJECT: ADAL Security Forces Operations. (Current Mission).

REQUIREMENT: This project is required to provide space for administration functions, guardmount and conference room, lockers and shower rooms due to increases from 80 to 223 personnel. In addition, 60 Army National Guard personnel have been deployed to Hurlburt Field to augment security forces in support of Global War on Terrorism. Comply with DoD force protection requirements per unified facilities criteria.

CURRENT SITUATION: The existing facility was constructed in 1979 for 80 personnel. There is insufficient space in the existing facility for administrative personnel, guardmount or locker/shower rooms to accommodate the increases in unit manning. Daily guardmount briefings and squadron training compete for the same 400 SF training room. In addition, lack of holding cells have forced the security personnel to use office space to separate witnesses from suspects. Due to lack of space, the security forces analysis section is operating out of temporary space away from the operations facility. IMPACT IF NOT PROVIDED: Security forces will continue to be operate in a poorly

IMPACT IF NOT PROVIDED: Security forces will continue to be operate in a poorly configured and inadequately sized facility. As the additional personnel are assigned to the unit, this will further decline the morale and performance of these personnel.

1. COMPONENT AIR FORCE	FY 2007 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)				
3. INSTALLATION HURLBURT FIELD	ATION AND LOCATION 4. PROJECT TITLE				
5. PROGRAM ELE	MENT 6. CATEGORY CODE	7. PROJECT NUMBER	8. FROJECT COST (\$000)		
27596	730-835	FTEV943001	1,900		

ADDITIONAL: This project does meet the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements". A preliminary analysis of reasonable options was done and indicates only one-option meets operational requirements. Base Civil Engineer: Jeffrey L. Pitchford, Lt Col, 850-884-7701. Addition: 536 SM = 5,768 SF; Alterations: 622 SM = 6,693 SF.

JOINT USE CERTIFICATION: This facility can be used by other components on an "as available" basis; however, the scope of this project is based on Air Force requirements.

1. COMPONENT FY 2007 MILITARY CONSTRUCTION PROJECT DATA 2. DATE AIR FORCE (computer generated)						
3. INSTALLATIO	ON AND LO	CATION		4. PROJECT I	TITLE	
HURLBURT FIEL	D, FLORII	DA		ADAL SECURIT	TY FORCE OPERA	TIONS
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PRO	ECT NUMBER	8. PROJECT CO	ST (\$000)
27596		730-835	FT	EV943001	1,	900
12. SUPPLEMEN	TAL DATA	•				
a. Estimate	ed Design	Data:				
(1) State						
	-	m Started			15	5-APR-05
		Cost Estimates used		relop costs		YES
• •		amplete as of 01 JAN	2006			15%
	ate 35% I	-				5-SEP-05
(e) Date Design Complete (f) Energy Study/Life-Cycle analysis was/will be performed					5-SEP-06 YES	
	tandard o	or Definitive Design on Was Most Recentl		_		NO
		c) = (a) + (b) or (d)	•			(\$000)
• •	-	of Plans and Speci				114
-		Design Costs				57
(c) T						171
• •	ontract					150
(e) I	n-house					21
(4) Cons	truction	Contract Award				06 DEC
(5) Cons	truction	Start				07 JAN
(6) Cons	truction	Completion				07 DEC
which	is compa	letion of Project De rable to traditional tability.				

b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
SYSTEM FURNITURE	3400	2007	50
COMMUNICATION EQUIPMENT	3400	2007	60

				1
				I
				ı
				ı
				1
				1
				1
				1
				1
				I
				1
				1
	•			

1. COMPONENT		FY 2010 MILITARY CO	NSTRUC'	ric	ON PROJECT I	DATA	2. DATE	
AIR FORCE		(compute	r gener	ra	ted)			
3. INSTALLATI	3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
HURLBURT FIEL	D, FLORIDA	A		1:	TEMPORARY L	IVING FACILI	TY	
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PRO	JE	CT NUMBER	8. PROJECT	COST (\$000)	
		740-457	F	re	v953013		1,950	
		9. COST	ESTIMA:	Æ	5			
		ITEM	U/I	М	QUANTITY	UNIT	COST	
PRIMARY FACILIT	IES						1,430	
TEMPORARY LIVI	NG FACILIT	Y	SD	1	1,300	1,100	(1,430)	
SUPPORTING FACI	LITIES		\	1			320	
UTILITIES			LS	3			(80)	
PAVEMENTS			LS	3			(80)	
SITE IMPROVEME	ints	·	L	3			(80)	
DEMOLITION			L	3			(80)	
SUBTOTAL				١			1,750	
CONTINGENCY (5.0 %)			İ				88	
TOTAL CONTRACT COST						<u> </u>	1,838	
SUPERVISION, INSPECTION AND OVERHEAD (6.0%				ļ		[110	
TOTAL REQUEST						{	1,948	
TOTAL REQUEST (TOTAL REQUEST (ROUNDED)						1,950	

10. Description of Proposed Work: Construct a 24 unit Temporary Living Facility (TLF) with kitchenettes, service unit/linen room, and storage/utility room. Includes asphalt drive and parking area, landscaping, concrete sidewalks, demolition of Bldgs 90344 & 90345, utilities and all necessary support. Provide individual heating and airconditioning for each unit.

Air Conditioning: 36 Tons

11. REQUIREMENT: 1,324 SM ADEQUATE: 24 SM SUBSTANDARD: 0 SM

PROJECT: Construct Temporary Living Facility.

<u>REQUIREMENT:</u> This facility is required to provide temporary living quarters for incoming and outbound families at this location.

CURRENT SITUATION: There are currently 24 TLF units at Hurlburt Field. Temporary off-base living quarters are non-existant in the Fort Walton Beach area during the tourist season, May through September, which is the same period that TLFs are in highest demand. Contract quarters are extremely limited to supplement on-base transient quarters. During the tourist season, the average hotel/motel room exceeds \$60.00 per day for a family of four, creating an extreme burden on a typical Air Force family. Most hotels/motels are considered inadequate for families due to location and economic factors. Not only do the rates vary during the tourist season, but travel time is also increased. The hotels/motels that are 20 minutes away in the off season, may require 30-40 minutes travel time during the tourist season due to congestion and limited access. The Fort Walton Beach area is designated a "high cost of living" area during the summer season. The Canadian tourist flow into this area in the winter months has been increasing about 10 percent per year in the past few years. Indications are that this area will soon have a summer and winter tourist season. Long-range projections indicate that hotel/motel rooms will not be able to support military family PCS to this

1. COMPONENT	FY 2010 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE		(compute	r gener	ated)		
3. INSTALLATION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIEL	D, FLORIDA	A		TEMPORARY L	IVING FACILITY	
5. PROGRAM EI	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	OST (\$000)
	740-457 FTEV953013 1,950					950

area in the next five years. There are no suitable private facilities conducive to government leasing within 30 minutes of Hurlburt Field.

IMPACT IF NOT PROVIDED: The lack of sufficient temporary living facilities to support PCS families to and from Hurlburt Field is having a negative impact on mission performance. If this TLF is not provided we can expect military personnel morale to continually regress.

1. COMPONENT			2. DATE						
AIR FORCE		-							
3. INSTALLATI	ON AND	LOCATION	4.	PROJECT 1	TLE				
HURLBURT FIEL	D, FLOR	IDA	1	i-realign Affic Ligi	O'NEILL AVENU	e/Install			
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PR				JEC:	NUMBER	8. PROJECT C	OST (\$000)		
22176		851~147	F1	EV9	EEIC 529 EV962010 413.0				
		9. cos	r ESTIM	ATES	 3				
		ITEM		U/M	QUANTITY	UNIT	COST		
PRIMARY FACILIT	IES						311.5		
CLEARING				LS		ĺ	(5.0)		
FILL AND COMPA	ACT			CY	3,500	25	(87.5)		
CULVERTS AND	HEADWALL	s		LS]]	(18.0)		
PRIME COAT AND	ASPHAL	T PAVEMENT		SY	3,000	10	(30.0)		
STRIPING				LS	ţ	}	(1.0)		
TRAFFIC LIGHT	s			LS			(110.0)		
METAL POLES A	ND CONTR	OL SYSTEMS		LS			(60.0)		
SUPPORTING FACI	LITIES				Ì		15.0		
RELOCATE UTILITIES							(15.0)		
SUBTOTAL							326.5		
PROFIT AND OVERHEAD (26.5 %)							86.5		
TOTAL FUNDED CO	ost						413.0		
UNFUNDED COST	(:	LO %)		1	1		41.3		

- 10. Description of Proposed Work: Clear area, fill and compact base material, install culverts and headwalls, prime coat and place 2" asphalt pavement. Install traffic signals at intersection of Independence Road and O'Neill/Terry Avenues. Includes metal poles, cross arms, control system, semi-actuated detectors in pavement and pedestrian pushbuttons. Includes relocation of utilities and pavement striping as required.
- 11. Requirement: As Required.

TOTAL REQUEST

<u>PROJECT:</u> Realign O'Neill Avenue at the intersection of Terry Avenue and Independence Road and install traffic signals.

<u>REQUIREMENT:</u> This project is required to provide a ninety degree intersection with Terry Avenue and Independence Road. It will provide a left turn lane onto Independence Road to eliminate an unsafe condition that causes traffic backups during rush hours. Traffic signals are required at this new intersection to permit safe and efficient traffic flow.

CURRENT SITUATION: Currently the intersections of O'Neill Avenue and Terry Avenue with Independence Road are only 300 feet apart. Due to heavy traffic on Independence Road personnel making a left turn from O'Neill Avenue have a difficult time merging onto Independence Road safely.

IMPACT IF NOT PROVIDED: Without this project this intersection will continue to be unsafe, contributing to traffic backups and a potential accident site.

1. COMPONENT		2. DATE					
USSOCOM		(computer generated)					
3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
HURLBURT FIELD	, FLORI	DA		SOF MAINTENAN FACILITY	CE OPERATIONS	SQUADRON	
5. PROGRAM ELE	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)	

211 - 154

FTEV963008

COST ESTIMATES 9. COST UNIT TTEM IJ/M **CHANTITY** SOF MAINTENANCE OPERATION SQD FACILITY 3,834 MAINTENANCE OPERATIONS SQD FACL (28394 SF) 2,638 SM 1,446 (3,815) FORCE PROTECTION @ 0.5% OF STRUCTURE LS (19) SUPPORTING FACILITIES 530 UTILITIES T.S (150) PAVEMENTS (160) LS SITE IMPROVEMENTS LS (120) COMMUNICATIONS LS (100) SUBTOTAL 4,364 CONTINGENCY (5.0 %) 218 TOTAL CONTRACT COST 4,582 SUPERVISION, INSPECTION AND OVERHEAD (5.7 %) 261 TOTAL REQUEST 4,843 TOTAL REQUEST (ROUNDED) 4,850 EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD) (450.0)

10. Description of Proposed Construction: Concrete foundation and floor slab, masonry walls and sloping metal roof. Functional areas include administrative areas, classrooms, quality assurance, analysis and maintenance operations areas. Includes utilities, parking and all other support. Force protection includes structural reinforcement of exterior walls and tempered glass windows

Air Conditioning: 70 Tons

11205

11. REQUIREMENT: 6,840 SM ADEQUATE: 4,202 SM SUBSTANDARD: 0 SM

PROJECT: Construct a Maintenance Operations Squadron Facility. (Replacement & Deficit Solution)

REQUIREMENT: This project is required to provide an adequate facility for the Maintenance Operations Squadron command section and orderly room, maintenance operations, maintenance training, Logistics Group quality assurance and the base master technical order (TO) library. Force protection measures will be incorporated IAW Installation Force Protection Guide.

CURRENT SITUATION: The Maintenance Operations Squadron functions and maintenance operations functions are located in facilities with totally inadequate space. The quality assurance and maintenance training functions are located in inadequate office space in the main hangar. The training function is expanding, which will require larger classroom space. No other facility exists that could be used or converted for these requirements. The training functions are located in three facilities, inadequate in size and configuration.

IMPACT IF NOT PROVIDED: The Maintenance Operations Squadron will continue to be housed in inadequate facilities which will affect the morale and productivity of the personnel.

4,850

1. COMPONENT		DATA	2. DATE			
USSOCOM	(computer generated)					
3. INSTALLATION HURLBURT FIELD				4. PROJECT TO SOF MAINTENAN FACILITY	ITLE	SQUADRON
5. PROGRAM ELI	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
11205		211-154 FTEV963008 4,8			50	

ADDITIONAL: There is no criteria/scope for this project in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, this project does meet the criteria/scope specified in Air Force Handbook 32-1024, "Standard Facility Requirements." All known alternative options were considered during the development of this project. No other options could meet the mission requirements; therefore, no economic analysis was needed or performed. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701.

JOINT USE CERTIFICATION: IAW DoD Financial Management Regulation 7000.14-R, Vol 2B, Chapter 6, Joint Use was considered. Unilateral construction is recommended based on the special operations mission to be performed in this facility.

·						
1. COMPONENT		FY 2012 MILITAR	Y CONSTRUC	TION PROJECT	DATA	2. DATE
USSOCOM		(com	puter gene	rated)		1
3. INSTALLATIO	ON AND LA	CATION		4. PROJECT 1	TITLE	
HURLBURT FIEL	D, FLORI	DA		SOF MAINTENA FACILITY	ANCE OPERATION	S SQUADRON
5. PROGRAM EL	EMENT	6. CATEGORY CO	DE 7. PRO	JECT NUMBER	8. PROJECT CO	OST (\$000)
11205		211-154	FI	EV963008	4,	850
12. SUPPLEMEN	TAL DATA	:				
a. Estimate	ed Design	Data:				
(1) Statu						
1	· ·	n Started : Cost Estimates	used to de	velop costs		YES
1		omplete as of 01		70-0F 00-10		
	ate 35% I	=				
	-	m Complete udy/Life-Cycle an	alysis was	/will be perf	ormed	NO
(2) Basis	a:					
1		or Definitive Des	ign -			NO
(b) W	here Des:	ign Was Most Rece	ently Used	-		
		(a) + (b) ox				(\$000)
		n of Plans and Sp Design Costs	ecilicatio	ns		
(c) T	otal	_				
1	ontract					
(e) I:	n-house					
(4) Const	truction	Contract Award				
(5) Const	truction	Start				
(6) Const	truction	Completion				
which:	is compa	letion of Project cable to tradition tability.				
b. Equipme	nt assoc	iated with this p	project pro	vided from of	ther appropria	tions:
EQUIPMEN	T NOMENO	LATURE	PROCURI APPROPRII	NG APPR	CAL YEAR OPRIATED EQUESTED	COST (\$000)
PREWIRE	WORK ST	ation	3400)	.2010	450

1. COMPONENT FY 2012 MILITARY CONSTRUCTION PROJECT DATA							2. DATE
USSOCOM		(comp	uter ger	erate	ed)		
3. INSTALLATIO	3. INSTALLATION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELD	, FLORI	DA	Į	SOF S	QUADRON (PS, 18 FLTS	
5. PROGRAM ELI	ement	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT (COST (\$000)
11205		141-753	FI	EV963	012	7	500
		9. cos	T EST	MATES			
		TTEM		11 /M	OUANTITY	UNIT	COST
					-		
SOF SQ OPS FAC	(18 FLTS)						5,761
SQUADRON OPERA	TIONS FAC	CILITY (44,715 SF)		SM	4,154	1,380	(5,733)
FORCE PROTECTION	ON 0 0.59	STRUCTURE COST		LS	Į		(29)
SUPPORTING FACIL	LITIES					}	1,008
UTILITIES				IS		1 1	(290)
SITE IMPROVEME	nts			LS	1	1 1	(212)
PAVEMENTS				LS	1		(218)
DEMOLITION/ASB	ESTOS RE	MOVAL (BLDG 90343)		SM	1,053	84	(88)
COMMUNICATION	SYSTEM			LS			(200)
SUBTOTAL				1			6,770
CONTINGENCY	(5.0	%)					338
TOTAL CONTRACT	COST				1	ţ	7,108
SUPERVISION, IN	SPECTION	AND OVERHEAD (5.7 %)	1	Į.	1	405

10. Description of Proposed Construction: Concrete foundation and floor slab, steel frame, masonry walls and sloped metal roof. Functional areas include administration, planning and briefing areas to plan, conduct and report on developmental, qualification and operational testing, as well as the development of flight crew tactics for HQ AFSOC's fixed wing, vertical lift and tilt-rotor aircraft systems. Includes demolition of one building, utilities, parking and all other necessary support. Force protection includes structural reinforcement of exterior walls and fully tempered glass windows.

Air Conditioning: 112 Tons

TOTAL REQUEST

TOTAL REQUEST (ROUNDED)

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

11. REQUIREMENT: 17,091 SM ADEQUATE: 12,937 SM SUBSTANDARD: 1,053 SM

PROJECT: Construct a Squadron Operations Facility (Current Mission).

REQUIREMENT: A combined test facility for the 18th Flight Test Squadron (18 FLTS), Detachment 1 of the 46th Operations Group (Det 1, 46 OG) and HQ AFSOC/XPTT to plan, brief, conduct and report on developmental, qualification and operational testing of all Air Force Special Operations aircraft. The building design must address unique facility requirements such as classified Local Area Network, classified cells for data processing, data analysis, tactics development, mission planning, as well as briefing rooms certified for classified briefings. An industrial shop and equipment storage space is required for combined airborne instrumentation flight. The new building design needs to incorporate the common needs of two squadrons (18 FLTS and Det 1, 46 OG) as well as HQ AFSOC/XPTT and the peculiar needs of the Tactics Development Flight, Airborne Instrumentation Flight, Flight Operations Center, Life Support Shop and Data Management offices. Standard office space is required for unit commanders and their support staffs to conduct command and squadron duties. An auditorium is required for large-scale

7.513

7,500

(440.0)

1. COMPONENT USSOCOM	FY 2012 MILITAR	DATA 2. DATE				
3. INSTALLATION HURLBURT FIELD	ON AND LOCATION D, FLORIDA	4. PROJECT TITLE SOF SQUADRON OPS, 18 FLTS				
5. PROGRAM ELE	EMENT 6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)			
11205	141-753	FTEV963012	7,500			

briefings and Tactics Development conferences and conference rooms are needed for commander's staff meetings, Test Readiness Reviews and Test Planning Working Group meetings. Force protection will be incorporated IAW Installation Force Protection Guidance.

CURRENT SITUATION: The existing squadron operations facilities currently being used are inadequate for the expanded size of the 18 FLTS. The squadron is spread between three buildings, making day-to-day squadron operations extremely difficult and delaying the accomplishment of the aircraft test mission. The squadron was forced to lease office and storage space downtown to prevent additional overcrowding. Transition from downtown offices while conducting flight test operations causes delays with test planning, equipment and personnel transition times and test execution, which ultimately reduces operational availability of low density, high demand SOF aircraft. Not having adequate environmentally controlled shop/shelf space means exposing expensive, unique electronic equipment to Florida's high-humidity environment. This induces and accelerates component corrosion and deterioration of equipment and shipping containers. Being forced to use off-base storage also means that additional man-hours are consumed when transporting to temporary storage. Shop space for the instrumentation flight is also totally inadequate. There are no facilities on base that could be improved or converted for this requirement.

IMPACT IF NOT PROVIDED: The lack of an adequate combined test operations facility for the 18 FLTS, Det 1, 46 OG and HQ AFSOC/XPTT, will prolong testing, hinder communications, and finally delay critical test results to multiple ACAT I programs and to Special Operations forces training and fighting worldwide. The lack of such a facility will seriously hamper the USAF's and DoD's efforts to conduct combined developmental and operational testing that maximizes the use of scarce assets and test ranges. Using dilapidated facilities costs the organizations time and money in research, planning, instrumentation, execution and reporting on tests with direct impact on combat capability. Continued use of the old facilities requires piecemeal, and costly repairs and updating of electrical systems, heating and air conditioning, communication technology like SIPRNET connections, security improvements and satellite links used for testing. Being forced to rent space downtown for storage is a waste of money better used for direct testing support. Sensitive electronic equipment critical to test data collection will incur increased rates of damage from excessive transportation and handling, as well as from increased exposure to high humidity. Failure of these systems during testing will cause loss of data. They will have to be replaced and missions re-flown, increasing the operational down time of the aircraft. The bottom line is that the test organizations are wasting prodigious amounts of time, money and keeping AFSOC's LD/HD critical assets in a test status and delaying the fielding of new and upgraded weapon systems to the warfighter by being forced to use outdated, overcrowded and over utilized facilities.

ADDITIONAL: There is no criteria/scope for this project in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, this project does meet the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." All known alternative options were considered during the development of this project. No other option could meet the mission requirements; therefore, no economic analysis was needed or performed. A Certificate of Exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701.

1. COMPONENT	FY	FY 2012 MILITARY CONSTRUCTION PROJECT DATA					
USSOCOM		(computer generated)					
3. INSTALLATION AND LOCATION 4. PROJECT TITLE					TLE	_	
HURLBURT FIELD, FLORIDA SOF SQUADRON OPS, 18 FLTS							
5. PROGRAM ELE	MENT 6. 0	CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)	
11205 141-753 FTEV963012 7,500						00	
JOINT USE CERTIFICATION: IAW DoD Financial Management Regulation 7000.14-R, Vol 2B,							

JOINT USE CERTIFICATION: IAW DoD Financial Management Regulation 7000.14-R, Vol 2B, Chapter 6, Joint use construction has been considered. Unilateral construction is recommended based on the special operations mission to be performed in this facility.

					<u>'</u>	
1. COMPONENT		FY 2012 MILITARY	CONSTRUC	TION PROJECT	DATA	2. DATE
USSOCOM		(combra	ter gene	rated)		[
3. INSTALLATIO	ON AND LO	CATION		4. PROJECT	TITLE	
HURLBURT FIELD	D. FLORTI	na.		SOF SOUADRO	N OPS, 18 FLTS	1
	7, 12014.		T	TOT DESIED	1	
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
11205		141-753	FT	EV963012	7,	,500
12. SUPPLEMEN	TAL DATA	:				
a. Estimate	d Design	Data:				
(1) Statu	ıs:					
• •		m Started			3	0-DEC-04
	_	Cost Estimates use	ed to de	relop costs		YES
* (c) Pe	ercent Co	omplete as of 01 JA	7 2011	_		15%
* (d) Da	ate 35% I	Designed			0	1-APR-05
(e) Da	ate Desig	n Complete			0	1-SEP-05
(f) Er	nergy Sti	dy/Life-Cycle analy	ysis was	/will be per	formed	NO
(2) Basis	3:					
(a) S	tandard d	or Definitive Design	n -			NO
(b) W	here Desi	ign Was Most Recent	ly Used	-		
(3) Total	L Cost (d	e) = (a) + (b) or (d	i) + (e)	•		(\$000)
(a) P:	roduction	n of Plans and Spec	ificatio	ns		503
• •		Design Costs				247
(c) T						750
• •	ontract					563
(e) I	n-ponse					187
(4) Const	truction	Contract Award				05 NOV
(5) Cons	truction	Start				06 JAN
(6) Cons	truction	Completion				07 JAN
which	is compa	letion of Project D rable to traditiona tability.				
b. Equipme	nt assoc	iated with this pro	ject pro	vided from o	other appropria	tions:
equipmen	VI NOMENO	CLATURE A	PROCURI PPROPRIA	NG APP	CAL YEAR ROPRIATED REQUESTED	COST (\$000)
PREWIRE	WORK ST	PATIONS	3400		2007	440

1. COMPONENT	·	FY 2007 MILITARY	CONSTRU	CTION	PROJECT	DATA	2. DATE
USSOCOM	(computer generated)						
3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
HURLBURT FIELD	, FLORI	DA		SOF E	ingine ma	INTENANCE ANI	STORAGE
				FACII	ITY		
5. PROGRAM ELE	ement	6. CATEGORY CODE	7. PROC	ECT 1	NUMBER	8. PROJECT (COST (\$000)
11205		211-157	FT	EV973	006	8	,500
		9. cos	T ESTIN	ATES			
		TTEM		U/M	QUANTITY	UNIT	COST
SOF ENGINE MAINTENANCE AND STORAGE FACILITY							5,597
ENGINE MAINT &	STRG SHO	OP (44,260 SF)		SM	4,112	1,351	(5,556)
FORCE PROTECTION	ON			LS			(41)
SUPPORTING FACI	Lities				1	1	2,062
UTILITIES				LS		ļ	(352)
PAVEMENTS				LS			(361)
SITE IMPROVEME	nts			LS	ļ	1	(255)
RELOCATE ENGIN	E TEST S	TANDS		LS	1		(444)
COMMUNICATION	System			LS			(133)
DEMOLITION		a establishmen		LS			(295)
ASBESTOS/LEAD	PAINT AB	ATEMENT		123	{		(222)
SUBTOTAL							7,658
CONTINGENCY	•	%)		-	1		383
TOTAL CONTRACT							8,041
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %)						}	458
TOTAL REQUEST							8,500
TOTAL REQUEST ((KOUNDED)						8,500

10. Description of Proposed Construction: Concrete foundation and floor slab, structural steel frame, masonry walls and sloping metal roof. Includes fire suppression, access road, removal of concrete and earth mound, relocation of engine test stands and all necessary support. Demolish one building (B/90131) for a total of 2418 SM and one structure (firing-in-buttress). Includes minimum DoD force protection standards.

Air Conditioning: 110 Tons

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

11. REQUIREMENT: 4,409 SM ADEQUATE: 297 SM SUBSTANDARD: 2,418 SM

<u>PROJECT:</u> Construct an aircraft engine inspection and repair shop combined with an aircraft accessories repair shop (Replacement/Deficit Solution).

REQUIREMENT: An adequate facility is required to inspect, repair, maintain and store aircraft engines, propellers, various stands, racks and kits to support the SOF aircraft at Hurlburt Field and other locations. This facility is also required to house the 16 CRS Accessories Flight which performs disassembly, inspection, repair, and storage of aircraft accessories and components to support the SOF aircraft at Hurlburt Field and other locations. Force protection will comply with minimum DoD standards.

<u>CURRENT SITUATION:</u> The existing facility provides only about half of the space required to adequately support engine inspection and repair operations. The engine shop was built in the mid 1950's, added to in 1992, but is still severely undersized and cannot support the additional workload generated by the beddown of SOF aircraft at Hurlburt

(935)

1. COMPONENT	FY 2007 MILITARY CONSTRUCTION PROJECT DATA 2. I				2. DATE		
USSOCOM			(combn	ter ger	erated)		
3. INSTALLATION	N AND LO	CATION			4. PROJECT TI	TLE	
HURLBURT FIELD	, FLORID	A		SOF ENGINE MAINTENANCE AND STORAGE FACILITY			
5. PROGRAM ELE	MENT	6. CATEGORY	CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
11205		211-157		FI	EV973006	8,5	00

Field. There are no facilities on base that can be altered to accommodate this function. The 16 CRS Accessories Flight is currently occupies 5,000sf of space in building 90700 (Eason Hangar) and storage space in other various facilities on base. A common walkway passes directly through the existing high pressure test stand area of the Accessory Flight. Make shift work areas such as this create dangerous work environments and effects the morale of these highly skilled military personnel performing mission critical maintenance work.

IMPACT IF NOT PROVIDED: Vital equipment and supplies will continue to deteriorate prematurely from outside storage. Inadequate material controls will persist and excessive maintenance time will result due to inability to issue parts in a timely manner. No other storage facilities are available to solve this space deficiency. This problem is compounded by the requirement to maintain and repair other worldwide SOF engine assets and associated equipment.

<u>ADDITIONAL:</u> This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates there is only one option that will meet operational requirements. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701. 4,112 SM = 44,260 SF

Anti-terrosism/force protection measures will be included in accordance with the Unified Facilities Criteria (UFC) 4-010-01, DoD Minimum Anti-Terrorism Standards for Buildings dated 8 October 2003, and updates as applicable. This project will comply with U. S. Army Corps of Engineers Technical Instruction 800-01, dated 20 July 1998 or later, and the Installation Design Guide.

JOINT USE CERTIFICATION: Mission requirements, operational considerations and location are incompatible with use by other components. N/A. USSOCOM budgets only for those facilities specifically for SOF use. Common support facilities are budgeted by the military departments. Reference Title 10, Section 165.

1. COMPONENT USSOCOM	FY 2007 MILITARY CONSTRUCTION PROJECT DATA (computer generated)		
3. INSTALLATION AND HURLBURT FIELD, FLO		4. PROJECT TI SOF ENGINE MP FACILITY	TLE LINTENANCE AND STORAGE
5. PROGRAM ELEMENT 11205	6. CATEGORY CODE 211-157	7. PROJECT NUMBER FTEV973006	8. PROJECT COST (\$000) 8,500

12. SUPPLEMENTAL DATA:

- a. Estimated Design Data:
 - (1) Project to be accomplished by design-build procedures

(7) Energy Study/Life-Cycle analysis was/will be performed

- (2) Basis:
 - (a) Standard or Definitive Design -
 - (b) Where Design Was Most Recently Used -

(3) All Other Design Costs 310

06 DEC

(4) Construction Contract Award

07 FEB (5) Construction Start

(6) Construction Completion 08 MAY

b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPRO	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
COLLATERAL EQUIPMENT	3400	2008	481
COMMUNICATIONS EQUIPMENT	3400	2008	454

NO

NO

								
1. COMPONENT		FY 2012 MILITARY	CONSTRU	CTION	PROJECT	DATA	2. DATE	
AIR FORCE		(combr	iter ger	erate	ed)			
3. INSTALLATIO	M. WID I	OCATION		4. PF	ROJECT TIT	LE		
HURLBURT FIELD	, FLORI	DA		IMPRO	VE WATER	System		
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)	
27596		842-245	FI	EV973	008	3,550		
		9. cos	T ESTI	MATES				
		TTEM		II /M	OUANTITY	UNIT	COST	
}		11199		10/10	Anemitte			
IMPROVE WATER DI	STRIBUTI	ON		}			2,665	
WATER DISTRIBUT	TION MAIN	i s		м	3,650	423	(1,544)	
WATER TANK, 250) KG			EA	1	******	(1,121)	
SUPPORTING FACIL	ITIES			1			545	
UTILITIES				LS	ĺ		(246)	
PAVEMENTS				LS		{	(187)	
FIRE HYDRANTS				EA	20	5,600	(112)	
SUBTOTAL					į		3,210	
CONTINGENCY	(5.0	%)					160	
TOTAL CONTRACT (COST			į	ļ		3,370	
SUPERVISION, INS	SPECTION	AND OVERHEAD (5.7 %)				192	
TOTAL REQUEST				İ	}	}	3,563	
TOTAL REQUEST (I	ROUNDED)			<u> </u>			3,550	

10. Description of Proposed Construction: Install a 250,000 gallon elevated steel tank, install 10 inch PVC water maines, including fire hydrants and valves. Includes paverment repair, utilities relocation and other necessary support.

11. REQUIREMENT: LS

ADEQUATE: LS

SUBSTANDARD: LS

PROJECT: Improve water distribution system (Current Mission).

REQUIREMENT: An additional elevated base water tank and associated distribution system is required to provide adequate fire protection, to meet peak flow demand and to correct environmental problems.

CURRENT SITUATION: Increased water consumption has resulted from base population growth and mission expansion. The existing base water distribution system is inadequate to meet current peak flow demands for both consumption and fire protection. Additionally, the current system has a problem meeting Safe Drinking Water Act (SDWA) criteria for lead and copper. The new system must bring the base's potable water into compliance with SDWA, eliminate several dead end water mains, and eliminate some old asbestos cement water pipes.

IMPACT IF NOT PROVIDED: The water distribution system will continue to be inadequate, exposing the base to water shortages and possible fire protection risks.

ADDITIONAL: There is not criteria/scope for this project in Part II of Military Handbook 1190, "Facility Flanning and Design Guide." However, this project does meet the criteria/scope specified in Air Force Handbook 32-1084, "Standard Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates there is only one option that will meet operational requirements. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850-884-7701.

JOINT USE CERTIFICATION: This is an installation utility/infrastructure project and does

COMPONENT		FY 2012 MILITARY			DATA	2. DATE
IR FORCE			uter ge	nerated)		<u> </u>
. INSTALLATIO				4. PROJECT TI		
URLBURT FIELD		_ 	T	IMPROVE WATER		
. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CC	ST (\$000)
27596		842-245	F	TEV973008	3,5	50
ot qualify for re benefited 1		use at this locati project.	on. How	ever, all tena	nts on this in	stallation
·						
					•	

. COMPONENT LIR FORCE	FY 2012 MILITARY CONSTRUCTION PROJECT DATA 2. DAY (computer generated)				2. DATE
3. INSTALLATION AND LA			4. PROJECT 7	אַזייני	
HURLBURT FIELD, FLORI		1	IMPROVE WATE		
HURLIBURI FIELD, FIORI	DA .	<u> </u>	IMPROVE WAIT	A SISIEM	
5. PROGRAM ELEMENT	6. CATEGORY CODE	7. PROJE	ECT NUMBER	8. PROJECT CO	ST (\$000)
27596	842-245	FTE\	v973008	3,	550
12. SUPPLEMENTAL DATA	·:				
a. Estimated Design	Data:				
(1) Status:					
(a) Date Desig	n Started			06	-JUL-04
(b) Parametrio	Cost Estimates used	d to deve	elop costs		YES
* (c) Percent Co	omplete as of 01 JAN	2011		•	35 %
* (d) Date 35% I	Designed			01	1- Jan -06
(e) Date Desig	-				3-JUL-05
(f) Energy St	udy/Life-Cycle analy:	sis was/w	will be perf	ormed	Ю
(2) Basis:					
• •	or Definitive Design				NO
(b) Where Des	ign Was Most Recently	y Used -			N/A
(3) Total Cost ((a) = (a) + (b) or (d)) + (e):			(\$000)
(a) Production	n of Plans and Speci:	fications	S		141
(b) All Other	Design Costs				94
(c) Total					235
(d) Contract					176
(e) In-house					59
(4) Construction	Contract Award				05 OCT
(5) Construction	Start				05 DEC

- cost and executability.
- b. Equipment associated with this project provided from other appropriations:

1. COMPONENT		FY 2012 MILITARY	CONSTRU	CTION	PROJECT	DATA	2. DATE	
AIR FORCE		(comp	uter ger	erate	ed)			
3. INSTALLATIO	N AND L	OCATION		4. PI	OJECT TI	PLE		
HURLBURT FIELD	, FLORI	DA	į	opera Facil		OUP/OPERATION	is plans	
5. PROGRAM ELE	EMENT	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT	OST (\$000)	
11205		141-454	FI	EV973	009	5,400		
		9. cos	T ESTI	MATES				
		ITEM		U/M	QUANTITY	UNIT	COST	
SOF OPS GROUP/OF							3,675	
-		NS FACL (19600 SF)		SM	1,820	1 1	(2,282)	
COMMAND/SUPPOR	T STAFF	(11060 SF)		SM	1,030	1,254	(1,292)	
FORCE PROTECTION	ON (0.5%)	•		LS	}		(18)	
SUSTAINABILITY	CONSTRUC	CTION @ 5%		LS	ļ		(83)	
SUPPORTING FACIL	LITIES					1	1,180	
UTILITIES/SITE	IMPROVE	MENTS .		LS	Ì		(480)	
PAVEMENTS				LS			(240)	
DEMOLITION/ASB	ESTOS RE	MOVAL		SM	1,952	95	(185)	
LEASE RELOCATA	BLE BUIL	DING		SM	1,030	150	(155)	
COMMUNICATIONS	System			LS			(120)	
SUBTOTAL					1		4,855	
CONTINGENCY	(5.0	%)					243	
TOTAL CONTRACT	COST					1	5,097	
SUPERVISION, IN	SPECTION	AND OVERHEAD (5.7 %)			j	291	
TOTAL REQUEST							5,388	
TOTAL REQUEST (ROUNDED)					1	5,400	

10. Description of Proposed Construction: Concrete foundation and floor slab, masonry walls and metal roof. Commander's and administrative offices, plans offices, crypto and WWMCS rooms, briefing, testing and equipment rooms. Includes a leased temporary facility, demolition of two buildings, utilities, parking and all other support. Force protection includes structural reinforcement of exterior walls and tempered insulated glass windows.

Air Conditioning: 268 Tons

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

11. REQUIREMENT: 83,932 SM ADEQUATE: 53,272 SM SUBSTANDARD: 2,500 SM

PROJECT: Construct an Operations Group/Operations Support Squadron Facility. (Current Mission)

REQUIREMENT: This project is required to provide an adequate facility for the 16th Operations Group Command, Training and Operations Plans functions. A modern, secure facility is needed for effective command and control of the wing's resources. A secure special plans facility is needed to plan and conduct clandestine special operations. This project will consolidate the functions in one facility. Force protection measures will be incorporated IAW Installation Force Protection Guide.

CURRENT SITUATION: The Operations Group and Operations Support Squadron are currently housed in facilities that are inadequate in size and function. These functions are now in four buildings spread throughout the base.

IMPACT IF NOT PROVIDED: The Operations Group and Operations Support Squadron will

(500.0)

1. COMPONENT AIR FORCE	FY 2012 MILITARY	DATA 2. DATE	
	ON AND LOCATION	4. PROJECT TI OPERATIONS GR FACILITY	TILE ROUP/OPERATIONS PLANS
5. PROGRAM ELE	6. CATEGORY CODE	7. PROJECT NUMBER FTEV973009	8. PROJECT COST (\$000) 5,400

continue to be housed in inadequate facilities which will affect the morale and productivity of the personnel. The special plans function will be unable to take on some missions due to lack of space and security. The 16 Operations Group will continue to operate in inadequate facilities spread throughout the base.

ADDITIONAL: There is no criteria/scope for this project in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, this project does meet the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." All known alternative options were considered during the development of this project. No other option could meet the mission requirement; therefore, no economic analysis was needed or performed. Base Civil Engineer: Jeffery L. Pitchford, Lt Col, USAF, 850/884-7701.

JOINT USE CERTIFICATION: IAW DoD Financial Management Regulation 7000.14-R, Vol 2B, Chapter 6, Joint Use construction has been considered. Unilateral construction is recommended based on the special operations mission to be performed in this facility.

1. COMPONENT		FY 2012 MILI	TARY C	ONSTRUC!	rion project	DATA	2. DATE
AIR FORCE	<u> </u>	(comput	er gene	rated)		<u> </u>
3. INSTALLATIO	ON AND LO	CATION			4. PROJECT	TITLE	
HURLBURT FIEL	D, FLORII	DA.			OPERATIONS FACILITY	GROUP/OPERATIO	ns plans
5. PROGRAM EL	EMENT	6. CATEGORY	CODE	7. PRO	DECT NUMBER	8. PROJECT CO	OST (\$000)
11205		141-45	4	FT	EV973009	5,	400
12. SUPPLEMEN	ITAL DATA	:					
a. Estimate	ed Design	Data:					
(1) Statu	ıs:						
	_	n Started					
1		: Cost Estimat amplete as of			verop costs		YES
1	ate 35% I	_	OI OIL				
(e) Da	ate Desig	n Complete					
(f) E	nergy St	dy/Life-Cycle	analy	sis was,	/will be per	formed	NO
(2) Basis	3:						
		or Definitive	_				NO
(a) W	nere ves:	ign Was Most F	ecent1.	y usea	_		
Y	-	e) = (a) + (b)	-	-			(\$000)
1		n of Plans and Design Costs	l Speci	ficatio	ns		
(c) T		Debig. Costo					
(d) C	ontract						
(e) I	n-house						
(4) Cons	truction	Contract Awar	d				
(5) Cons	truction	Start					
(6) Cons	truction	Completion					
Which	is compa	=				metric Cost Est ure valid scope	
b. Equipme	nt assoc	iated with thi	is pr oj	ect pro	wided from	other appropria	tions:
					FI:	SCAL YEAR	
PORTEN	NT NOMENO	ים מוזייה ג. די		PROCURI	NG API	ROPRIATED REQUESTED	COST (\$000)
1			M			2010	500
SKEMTKE!	D WORKSTA	TTOM2		3400		2010	300
		•					

1. COMPONENT	FY 2010 MILITARY CONSTRUCTION PROJECT DATA		I DATA 2. DATE
AIR FORCE	(computer generated)		
3. INSTALLATION AND I		4. PROJECT T	
5. PROGRAM ELEMENT	6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)
27596	121-115	FTEV973016	17,500
	9. COS	T ESTIMATES	

UNIT COST U/M QUANTITY TTEM HYDRANT FUELING SYSTEM 14,462 284,000 HYDRANT FUELING SYSTEM (76 LITERS/SEC) ΩT. 4 (1,136) FORCE PROTECTION @.5% OF STRUCTURE LS (8) 10,000 TRANSFER FUEL PIPELINE LF 258 (2.580) 20,000 54 (1,080) STORAGE TANKS (2-10 MBBL) BL 4,456 DISTRIBUTION PUMP HOUSE (2400 GPM) 4456 SF SF 586 (2,611) 1,000 BULK STORAGE PUMP HOUSE (1200 GPM) 1000 SF 1,020 (1,020) SF FILLSTANDS EA 2 205,500 (411) HYDRANT LOOP AND PIPING 6,200 807 LF (5,003) FILLSTAND PIPING LF 1,000 612 (612) SUPPORTING FACILITIES 1,187 UTILITIES LS (931) OPERATIONS FACILITY SF 1,000 256 (256) SUBTOTAL 15,649 CONTINGENCY 782 (5.0 %) TOTAL CONTRACT COST 16,431 SUPERVISION, INSPECTION AND OVERHEAD (5.7 %) 937

10. Description of Proposed Construction: Type III constant pressure JP-8 hydrant fuel system in compliance with current Air Force and American Petroleum Institute (API) standards. Supported by two 10 MMBL, above ground fuel storage tanks with concrete containment berms, isolation valves, drains and all other compliance appurtenances. Construct a 1,200 gpm bulk storage transfer pumphouse and a 2,400 gpm distribution pumphouse with current safety/emergency features, oil-water separators, backup generators, product recovery systems, and receipt filter separators with product flow meters and associated hardware. Construct dual truck fill stand island equipped with spill containment, emergency shut-off switches/current safety features, and pumphouse control room with microprocessor controls protected in an area adjacent to hydrant outlets to establish fuel servicing safety zones with paved road for accessibility of refueling equipment and fire protection units/personnel. Includes piping loop connecting receipt lines to existing bulk storage facilities located in the bulk fuel storage area to enable hydrant stock replenishment, and commercial/miliatry truck offloading headers to facilitate secondary receipt mode. Includes utilities, cathodic protection and leak detection systems.

Air Conditioning: 3 Tons

11. REQUIREMENT: 2,400 GM ADEQUATE: 0 GM SUBSTANDARD: 0 GM

PROJECT: Install 4- outlet Type III hydrant fueling system to comply with paragraph

TOTAL REQUEST

TOTAL REQUEST (ROUNDED)

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

17,368

17,500

(527.0)

1. COMPONENT		FY 2010 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)				2. DATE
AIR FORCE		(compr	iter ge	nerated)		
3. INSTALLATIO	N AND LO	CATION	-	4. PROJECT T	ITLE	
HURLBURT FIELD	, FLORID	A	HYDRANT FUELING SYSTEM			
5. PROGRAM ELE	CMENT	6. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT COST			ST (\$000)
27596		121-115	FTEV973016 17,500			500

3.3 of AFH 32-1084 This project complies with DPG & deliberate planning factors. A separate classified page outlining references & specifics (marked with an asterisk*) is available at the Air Force SCP.

REQUIREMENT: MISSION: STRATEGIC: Immediate deployment for AFSOC low-density, highdemand resources tasked for joint operations identified in DPG and multiple CONFLANs/OPLANs. Primary Forward Area Refueling Point unit; C-130 series aerial refueling, gunship support, commando solo and psychological operations; pararescue and combat air control; short notice humanitarian missions; shipboard naval operations; unconventional warfare, counter proliferation, direct action, special reconnaissance, civil affairs, combating terrorism, foreign internal defense and information operations. Supports ACC associate unit, 823rd Red Horse Squadron in ready to deploy status. GWOT/OIF missions originated directly from Hurlburt. MISSION SUCCESS: MODERATE: This project will increase fuel throughput capability by 100% from the two additional fillstands, reduce ground refueling time by 80%, and provide adequate fuel supply for wide-body traffic using the hydrant outlets. Additional fuel storage capacity will sustain IMP POS/BPWRS* requirement. Compliance with DPG & deliberate planning factors will definitely increase probability of mission success. COMMAND PRIORITY: COMPLIES WITH NATIONAL GUIDANCE*, DPG, and is AFSOC's #1 priority project for fueling support infrastructure. INFRASTRUCTURE: NO FACILITY. Facility is required, but increased demand with MDS conversion to CV-22 and bottleneck at existing fillstands during widebody aircraft deployment preparation time constraints will result in mission failure. Currently average 210 MH-53 fuel servicings per month; expect 196 CV-22 fuel servicings per month; up to 300% fuel requirement increase; can only service three CV-22's per R-11 refueler vice four MH-53's; will increase turn time. At least one-year lag time for current refueling unit validation process to catch up to CV-22 transition, however, the bottleneck at the existing fillstands will negate increased number of fuel trucks under OPLAN time constraints. PROJECT TYPE: FUEL HANDLING.

CURRENT SITUATION: Hurlburt is authorized only nine R-11 refueling units. One truck is normally dedicated to JP-5 support for MH-53 shipboard operations. Upon receipt of deployment orders, our fleet of 17 MH-53s immediately requires two dedicated defuel units for teardown preparations and airlift to the AOR. This represents an increase of 300% in defuel requirements. The potential strongly exists where Hurlburt Field is left with only 7 refueling units (77%), after converting the JP-5 unit to JP-8 service, to support 30-40 home station aircraft as well as a steady flow of wide-bodies to airlift deploying MH-53s, support equipment, and personnel. There is no alternative means of fuel delivery other than by truck. The two fillstands are not capable of turning trucks in time to meet wide-body aircraft fuel and ground time deliberate planning factors, and the bulk storage system does not meet IMP reserve requirements. A bottleneck develops at the JP-8 fillstands after the first turn of two trucks which takes 60 minutes; thereafter, the time increases to upwards of 75 minutes. Futhermore, ability to service deploying C-130's will be extremely limited. Average response time will climb to several hours, depending on wide-body fuel needs. Ordering more R-11's is not the answer since existing parking space is at a premium both in the fuel yard and on the east ramp. Assigned fuels personnel may be required to simultaneously deploy on arriving aircraft. The bydrant system will minimize the impact of that potential. In recent months, OIF aircraft were diverted due to our refueling situation. This is unacceptable

1. COMPONENT		FY 2010 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)				
AIR FORCE]
3. INSTALLATIO	ON AND LOCATION 4. PROJECT TITLE					
HURLBURT FIELD	, FLORI	DA		HYDRANT FUEL	ing system	
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT COST (\$000)			
27596		121-115	FTEV973016 17,500			

during CONPLAN/OPLAN support.

IMPACT IF NOT PROVIDED: Hurlburt Field cannot meet existing deliberate plans or increased future GWOT mission requirements with present refueling and storage capability. Mission degradation will increase exponentially as CV-22 MDS conversion begins in FY07. AFSOC operates in the joint operations realm on a daily basis with a large presence in GWOT/OIF regions. Lack of timely and adequate fuel support will result in mission-crippling domino effect for joint SOF response to CINC/Combatant Commander orders.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." An economic analysis has been performed. CONPLANS must be considered in Hurlburt Field's project considerations.* ECONOMIC BENEFITS: The hydrant fueling system will reduce the recurring cost of providing fuel to the East Apron by truck considerably. The proposed system will pay for itself by the end of the seventh year. Reduce refueling time by 75% (hydrant vice truck servicing); reduce East Ramp servicing response time by 90%; simultaneously refuel two wide-body aircraft or four small-bodied aircraft; increase fuel pumping capability by 400% based on 2400 GPM hydrant system, four times faster than one fuel truck can pump; provide uninterruped C-130 ramp support with remaining R-11 trucks; reduce traffic congestion on East Ramp; meet MDS conversion requirements; become self-sufficient in POS/BFWRS storage ability; AFSOC will comply with DPG/OPLAN MTW fuel requirements and CINC expectations of SOF. ENVIRONMENTAL CRITERIA: Project has no impact on environmental compliance issues. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701.

1. COMPONENT AIR FORCE						
3. INSTALLATIO	ON AND TO	ACT TO TO		4 222		
				4. PROJECT T		
HURLBURT FIEL	D, FLORII)A		HYDRANT FUEL	ing system	
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
27596	5 121-115 FTEV973016 17,5			500		
12. SUPPLEMEN	TAL DATA	:				<u> </u>
a. Estimate	ed Design	Data:				
(1) Statu	15:					
(a) Da	ate Desig	n Started			15	-MAY-07
(b) Pa	erametric	Cost Estimates used	d to der	relop costs		YES
* (c) Pe	ercent Co	mplete as of 01 JAN	2009			35 %
* (d) Da	ate 35% D	esigned			01	L-JAN-08
(e) Da	ate Desig	n Complete			1!	5-AUG-08
(f) E	nergy Stu	dy/Life-Cycle analy	sis was,	/will be perf	ormed	МО
(2) Basis	s:	•				
(a) S	tandard o	or Definitive Design	-			NO
(b) W	here Desi	gn Was Most Recentl	y Used	_		
(3) Total	l Cost (c	:) = (a) + (b) or (d) + (e)	a 9		(\$000)
(a) P	roduction	of Plans and Speci	ficatio	ns		1,000
•		Design Costs			-	600
(c) T	otal					1,600
(d) c	Contract					
(e) I	n-house					
(4) Cons	truction	Contract Award				08 DEC
(5) Cons	truction	Start				09 FEB

- * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability.
- b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
PREWIRED WORKSTATIONS	3400	2010	20
R-12 FUEL CARTS (4)	3400	2010	507

(6) Construction Completion

10 MAY

							· · · · · · · · · · · · · · · · · · ·	
1. COMPONENT		FY 2007 MILITARY	CONSTRU	CTION	PROJECT	DATA	2. DATE	
AIR FORCE		(comp	ıter gei	erate	ed)			
3. INSTALLATIO	N AND L	OCATION		4. PI	ROJECT TI	TLE		
HURLBURT FIELD	, FLORI	DA	ļ	FIRE CRASH/RESCUE STATION				
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)	
27596		130-142	F.	TEV973018 6,0			5,000	
		9. COS	T ESTI	MATES				
Ì						UNIT	COST	
		TTEM		U/M	QUANTITY		 	
FIRE CRASH/RESCU	JE STATIC	en e			ŀ		4,123	
FIRE STATION				SM	3,040	1,350	(4,104)	
ANTITERRORISM :	FORCE PRO)TECTION		SM	3,040	6	(19)	
SUPPORTING FACII	LITIES						1,275	
COMMUNICATION	SYSTEM			LS	j		(170)	
UTILITIES				LS			(350)	
PAVEMENTS				LS			(400)	
SITE IMPROVEME	nts			LS			(150)	
OIL/WATER SEPA	RATOR			EA	1	34,000	(34)	
DEMOLITION				SM	3,055	56	(171)	
SUBTOTAL							5,398	
CONTINGENCY	(5.0	%)		ĺ		-	270	
TOTAL CONTRACT	COST						5,668	
SUPERVISION, IN	SPECTION	AND OVERHEAD (5.7 %)				323	
TOTAL REQUEST							5,991	
TOTAL REQUEST (ROUNDED)						6,000	
EQUIPMENT FROM	OTHER AP	PROPRIATIONS (NON-ADD))				(115.0)	

10. Description of Proposed Construction: Foundation and floor slab, masonry walls, steel frame and sloping metal roof. Functional areas include admin space, bunk, locker, fitness, conference, alarm, dayroom, kitchen, extinguisher maint, storage, oil/water separator, and vehicle bays. Includes utilities pavement and all other support. Comply with DoD force protection requirements per unified facilities criteria. Demolish four facilities (3,055 SM).

Air Conditioning: 105 Tons

11. REQUIREMENT: 3,040 SM ADEQUATE: 0 SM SUBSTANDARD: 3,055 SM

PROJECT: Construct a fire crash/rescue station. (Current Mission).

REQUIREMENT: This project is required to provide an adequate crash/rescue operation, located on the flight line to protect 56 permanently assigned and 13 additional C-130 aircraft schedule to arrive in FY07.

CURRENT SITUATION: The existing wood frame structure built in 1956 is inadequate and poorly configured to support 72 personnel and 16 pieces of major fire protection equipment. In addition, the mechanical, and electrical systems are old and antiquated and and can not be economically upgraded. The mechanical system does not provide adequate heating/cooling to fireman's quarters and the administrative office areas. The electrical system is insufficient to support existing loads. Electrical circuit breaker are reset frequently due to high demands of office computers and equipments. In the vehicle bay area, the concrete floor is sinking due to age of concrete floor slab and heavy weight of new fire protection equipment.

IMPACT IF NOT PROVIDED: Firemen will continue to operate in a facility that is poorly

AIR FORCE (computer generated) 3. INSTALLATION AND LOCATION 4. PROJECT TITLE SURLEURT FIELD, FLORIDA 5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. FROJECT COST (\$000) 27596 130-142 FTEV973018 6,000 configured and with deteriorated structural, mechanical, and electrical systems. This iill impact the morale and well being of the personnel working under such conditions. DDITIONAL: This project does meet the criteria/scope specified in Air Force Handbook 12-1084, "Facility Requirements". A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done, it indicates only one-option meets operational requirements. A certificate of exception has been prepared. BASE CIVIL ENGINEER:: Jeffrey L. Pitchford, Lt Col, (850 884-7701. Fire Station: 3,040 SM = 32,710 SF. FOINT USE CERTIFICATION: This facility can be used by other components on an "as available" basis, however, the scope of the project is based on Air Force requirements.	1. COMPONENT		FY 2007 MILITARY			DATA	2. DAT	E
FIRE CRASH/RESCUE STATION 5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000) 27596 130-142 FTEV973018 6,000 configured and with deteriorated structural, mechanical, and electrical systems. This will impact the morale and well being of the personnel working under such conditions. DDITIONAL: This project does meet the criteria/scope specified in Air Force Handbook 12-1084, "Facility Requirements". A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done, it indicates only one-option meets operational requirements. A certificate of exception has been prepared. BASE CIVIL ENGINEER:: Jeffrey L. Pitchford, Lt Col, (850) 184-7701. Fire Station: 3,040 SM = 32,710 SF. DOINT USE CERTIFICATION: This facility can be used by other components on an "as								
6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000) 27596 130-142 FTEV973018 6,000 configured and with deteriorated structural, mechanical, and electrical systems. This will impact the morale and well being of the personnel working under such conditions. DDITIONAL: This project does meet the criteria/scope specified in Air Force Handbook 12-1084, "Facility Requirements". A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) as done, it indicates only one-option meets operational requirements. A certificate of exception has been prepared. BASE CIVIL ENGINEER:: Jeffrey L. Pitchford, Lt Col, (850) 184-7701. Fire Station: 3,040 SM = 32,710 SF. DOINT USE CERTIFICATION: This facility can be used by other components on an "as	3. INSTALLATIO	N AND LOC	ATION		4. PROJECT TI	ITLE		
27596 130-142 FTEV973018 6,000 configured and with deteriorated structural, mechanical, and electrical systems. This mill impact the morale and well being of the personnel working under such conditions. DDITIONAL: This project does meet the criteria/scope specified in Air Force Handbook 12-1084, "Facility Requirements". A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done, it indicates only one-option meets operational requirements. A certificate of exception has been prepared. BASE CIVIL ENGINEER:: Jeffrey L. Pitchford, Lt Col, (850 884-7701. Fire Station: 3,040 SM = 32,710 SF. FOINT USE CERTIFICATION: This facility can be used by other components on an "as	HURLBURT FIELD	, FLORIDA	<u> </u>		<u> </u>	SCUE STATIO	N	
configured and with deteriorated structural, mechanical, and electrical systems. This ill impact the morale and well being of the personnel working under such conditions. DDITIONAL: This project does meet the criteria/scope specified in Air Force Handbook 12-1084, "Facility Requirements". A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done, it indicates only one-option meets operational requirements. A certificate of exception has been prepared. BASE CIVIL ENGINEER:: Jeffrey L. Pitchford, Lt Col, (850 884-7701. Fire Station: 3,040 SM = 32,710 SF.	5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT	T COST (\$000)	
ill impact the morale and well being of the personnel working under such conditions. DDITIONAL: This project does meet the criteria/scope specified in Air Force Handbook 2-1084, "Facility Requirements". A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done, it indicates only one-option meets operational requirements. A certificate of exception has been prepared. BASE CIVIL ENGINEER:: Jeffrey L. Pitchford, Lt Col, (850 884-7701. Fire Station: 3,040 SM = 32,710 SF.	27596		130-142	F	rev973018		6,000	
	will impact the aDDITIONAL: Tage 1084, "Faci accomplishing was done, it is exception has a second of the accomplishing to the accomplishing as done."	e morale a his proje lity Requ this proj ndicates been prep e Station	and well being of ct does meet the irements". A pro- ect (status quo, only one-option : ared. BASE CIVI :: 3,040 SM = 32	f the per criteri eliminar renovat meets op L ENGINE ,710 SF.	rsonnel workin a/scope specif y analysis of ion, upgrade/ erational requ ER:: Jeffrey	ng under such fied in Air reasonable removal, new nirements. L. Pitchfor	h condition Force Handk options for constructi A certifica d, Lt Col,	s. oook oon)
			_		_	-		ents.
			_		_	-		ents.
			_		_	-		ents.
			_		_	-		ents.
			_		_	-		ents.
			_		_	-		ents.
			_		_	-		ents.
			_		_	-		ents.
			_		_	-		ents.

1. COMPONENT		FY 2007 MILITARY CO	ONSTRUC!	tion project	DATA	2. DATE
AIR FORCE		(compute	er gene	rated)		
3. Installati	ON AND LO	CATION		4. PROJECT T	TITLE	
HURLBURT FIEL	D, FLORI	DA		FIRE CRASH/	RESCUE STATION	
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
27596		130-142	FT	EV973018	6,	000
12. SUPPLEMEN	TAL DATA	:				
a. Estimate	ed Design	Data:				
(1) Statu						
	-	n Started	_		30	-APR-05
•		Cost Estimates use		velop costs	•	YES
		omplete as of 01 JAN	2006			15%
	ate 35% I	-				5-SEP-05
		n Complete	• _			5-SEP-06
(I) E	nergy st	udy/Life-Cycle analy	sis was	/WIII be peri	Ormed	YES
(2) Basis						
· •		or Definitive Design ign Was Most Recentl		_		NO
(3) Tota	l Cost (c) = (a) + (b) or (d) + (e)	:		(\$000)
		n of Plans and Speci				360
(b) A	11 Other	Design Costs				180
(c) T	otal					540
(d) C	contract					450
(e) I	n-house					90
(4) Cons	truction	Contract Award				06 DEC
(5) Cons	truction	Start				07 JAN
(6) Cons	truction	Completion				08 MAR
	_	letion of Project De				
	_	rable to traditional tability.	. კე ზ OJE	sign to ensu	re varid acobe	,
b. Equipme	ent assoc	iated with this proj	ect pro	vided from o	ther appropria	tions:
				FISC	CAL YEAR	

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
PREWIRED WORK STATION	3400	2007	55
COMMUNICATION EQUIPMENT	3400	2007	60

		ı
		1
		1
		,
		i i
		1
		1
		I .
		1
		1
		1
		1
		,
		i I

				<u> </u>				
1. COMPONENT		FY 2011 MILITARY				DATA	2. DATE	
AIR FORCE	AIR FORCE (computer generated)							
3. INSTALLATIO	N AND L	OCATION		4. PROJECT TITLE				
HURLBURT FIELD	, FLORI	DA		AIRMAN LEADERSHIP SCHOOL				
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PRO			7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)	
27596		171-815	FI	FTEV973019 3,100			,100	
		9. COS	T ESTI	MATES				
		TTEM		п/м	OUANTITY	UNIT	COST	
AIRMAN LEADERSH FORCE PROTECTI AIRMAN LEADERS SUSTAINABILITY	ON/ANTITE	ERRORISM (.5%) DL (13,770 SF)		LS SM LS	1,280	1,500	2,019 (9) (1,920) (90)	
SUPPORTING FACI	LITIES			LS			769 (120)	
PAVEMENTS				LS			(135)	
SITE IMPROVEME	nts			LS			(140)	
COMMUNICATION SYSTEM			LS			(150)		
DEMOLITION (6,632 SF)			SM	616	120	(74)		
RELOCATE SOFTE	ALL FIEL	D		LS			(150)	
SUBTOTAL							2,788	
CONTINGENCY	(5.0	%)		1		1	139	
TOTAL CONTRACT	COST						2,927	

10. Description of Proposed Construction: Concrete foundation and floor slab, memory walls and sloping metal roof. Functional areas include seminar rooms, auditorium, learning resource center, administrative offices, instructor offices and lounges. Includes utilities, parking, site improvements and demolition of one facility (616 SM). Includes minimum DoD interim force protection standards.

(5.7 %)

Air Conditioning: 35 Tons

SUPERVISION, INSPECTION AND OVERHEAD

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

TOTAL REQUEST

TOTAL REQUEST (ROUNDED)

11. REQUIREMENT: 1,280 SM ADEQUATE: SM SUBSTANDARD: 616 SM

PROJECT: Airman Leadership School (Current Mission)

REQUIREMENT: An energy efficient, properly configured Airman Leadership School building is required. This facility will house adminstrative offices, seminar rooms, auditorium, learning resource center/heritage room, instructor offices and instructor and student lounges. The new facility will provide a proper educational environment. Force protection will comply with minimum DoD standards.

CURRENT SITUATION: Currently the airman leadership school is operating out of a 1950's vintage church facility that has been converted to meet minimum requirements. This facility is inadequately sized, poorly configured and costly to maintain. One facility will be demolished as a result of this project for a total of 616 SM.

IMPACT IF NOT PROVIDED: Without this project the Airman Leadership School will continue to operate out of an old, inadequate facility. Student and staff growth will be limited to space availability, therefore course expansion and subject improvement will be delayed.

167

3,094

3,100

(240.0)

1. COMPONENT		CONSTRUCTION PROJECT DATA 2. DATE uter generated)				
AIR FORCE	(comp	uter generated)				
3. INSTALLATIO	ON AND LOCATION	4. PROJECT TI	er i s			
HURLBURT FIELD), FLORIDA	AIRMAN LEADERSHIP SCHOOL				
5. PROGRAM ELI	MENT 6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)			
27596	171-815	FTEV973019 3,100				

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Engineer: Jeffrey L. Pitchford, Lt Col, 850/884-7701. Airman Leadership School: 1296 SM = 13,958 SF. JOINT USE CERTIFICATION: This facility can be used by other components on an "as available" basis; however, the scope of the project is based on Air Force requirements.

1. COMPONENT						2. DATE
AIR FORCE		(comput	er gene	rated)		<u> </u>
3. INSTALLATIO HURLBURT FIELD		- · -		4. PROJECT 'AIRMAN LEAD	TITLE ERSHIP SCHOOL	
5. PROGRAM ELE 27596						• •

12. SUPPLEMENTAL DATA:

- a. Estimated Design Data:
 - (1) Status:
 - (a) Date Design Started
 - (b) Parametric Cost Estimates used to develop costs

ed to develop costs YES

- * (c) Percent Complete as of 01 JAN 2010
- * (d) Date 35% Designed
 - (e) Date Design Complete
 - (f) Energy Study/Life-Cycle analysis was/will be performed

NO

(2) Basis:

(a) Standard or Definitive Design -

NO

(b) Where Design Was Most Recently Used -

(3) Total Cost (c) = (a) + (b) or (d) + (e):

(\$000)

(a) Production of Plans and Specifications

(b) All Other Design Costs

0

(c) Total

0

(d) Contract(e) In-house

Ŏ

- (4) Construction Contract Award
- (5) Construction Start
- (6) Construction Completion
- * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability.
- b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
FURNITURE	3400	2008	215
REWIRED WORKSTATIONS	3400	2008	25

1. COMPONENT	. COMPONENT FY 2012 MILITARY CONSTRUCTION PROJECT DATA						
AIR FORCE		(comb.	uter ge	nerate	ed)		
3. INSTALLATION AND LOCATION 4. PROJECT TITLE						TLE	
HURLBURT FIELD	, FLORI	OA.		REAL:	GN ROADS		
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)
27596		851-147	F:	EV993	011	5	,400
		9. cos	T ESTI	MATES			
	··· <u>·</u>	TTEM		T7 /W	OUANTITY	UNIT	COST
				14/14	QUANTITI		
PRIMARY FACILITI	ES						2,304
REALIGN ROADS				LS	}	1	(2,304)
SUPPORTING FACIL	LITIES						2,304
UTILITIES				LS]	İ	(768)
PAVEMENTS				LS	}	}	(768)
SITE IMPROVEMEN	nts			LS		ţ	(768)
SUBTOTAL				1		1	4,608
CONTINGENCY	(10.0	%)		ļ			461
TOTAL CONTRACT O	COST					1	5,069
SUPERVISION, INS	SPECTION .	AND OVERHEAD (5.7 %)				289
TOTAL REQUEST							5,358
TOTAL REQUEST (ROUNDED)				j		5,400

10. Description of Proposed Construction: Realign intersections, widen roads, construct new roads and extend existing roads. Work includes demolition of structures, relocation of utilities, refuge lanes, curb and gutters, base work, cut and fill, new driveway accesses from side streets. Includes utilities/lift station relocation, demolition and all necessary support.

11. REQUIREMENT: LS ADEQUATE: LS SUBSTANDARD: LS

PROJECT: Improve base road network.

REQUIREMENT: Base road network improvements are needed to support the increased traffic flow which has resulted from Congressionally supported Speciail Operations Forces (SOF) revitalization. Additionally, Okaloosa County has constructed a new 4 lane corridor to the base's east entrance but traffic flow is constricted at the gate since only two lanes currently exist. The lack of adequate refuge lanes and signalization result in significant traffic delays during rush hour. These delays require the use of personnel to direct traffic in order to prevent gridlock.

CURRENT SITUATION: The existing road system was constructed in the 1950's and was designed for a base population of between 2000 to 3000 personnel. Base population has tripled since then and the Community Center has been moved to the east side of the base with no improvements to the basic road system. The new east side Community Center consists of a 76,000 SF Commissary, a 52,000 SF AAFES Shopping Center and a 35,000 SF Clinic which have attracted many retired and active duty patrons and increased traffic flow dramatically. The present road network cannot support the increased traffic flows. Traffic flow through both entrances reduces from four lanes to two lanes, thus creating bottlenecks at the entrances. Congestion and delays occur during normal duty hours. Traffic counts have increased by 22 percent at the Main gate and over 190 percent at the East gate since the SOF build up has occurred. The intersection at Bartley and O'Neil Avenue must have traffic safety improvements done to support existing base development. Existing level of service on Cody and Independence Road is "F", traffic flow is near gridlock during peak periods. The Base Comprehensive Plan Traffic Master Plan

1. COMPONENT	FY 2012 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE		(com	puter ge	nerated)		
3. INSTALLATION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELD	, FLORID	A		REALIGN ROADS		
5. PROGRAM ELE	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
27596		851-147	F	rEV993011	00	

identifies these two roads as deficient and in need of realignment.

IMPACT IF NOT PROVIDED: Traffic will continue to back up on at the various intersetion due to increased traffic. Traffic will continue to back up on various roads due to a lack of adequate left turn lanes. SOF mission delays will occur on base because of inadequate roads and poor access.

ADDITIONAL: Thre is no criteria/scope for this project in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, this project does meet the criteria/scope specified in Air Force Instruction 32-1924, "Standard Facility Requirements." All known alternative options were considered during the development of this project. No other option could meet the mission requirements; therefore, no economic analysis was needed or performed.

1. COMPONENT FY 2012 MILITARY CONSTRUCTION PROJECT DATA 2. DATE AIR FORCE (computer generated)							
3. INSTALLATIO	ON AND LO	CATION		4. PROJECT T	PITLE	<u> </u>	
HURLBURT FIEL	D, FLORII)A		REALIGN ROAL	os		
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJE						ST (\$000)	
27596	ļ	851-147	851-147 FTEV993011				
12. SUPPLEMEN	TAL DATA	<u> </u>					
a. Estimate	ed Design	Data:			•		
(1) Statu	ıs:						
(a) Da	ate Desig	n Started			04	1-AUG-05	
(b) Pa	arametric	Cost Estimates used	d to dev	velop costs		YES	
* (c) Pe	ercent Co	mplete as of 01 JAN	2011			35 %	
* (d) Date 35% Designed						L-JAN-07	
(e) Date Design Complete 0						1-AUG-06	
(f) Er	nergy Stu	dy/Life-Cycle analys	sis Was,	/will be perf	ormed	NO	
(2) Basis	s:						
(a) St	tandard c	r Definitive Design	-			МО	
(b) W	here Desi	gn Was Most Recently	y Used ·	-			
(3) Total	l Cost (c	a(a) = (a) + (b) or (d)) + (e):	:		(\$000)	
(a) P	roduction	of Plans and Speci:	fication	ns		0	
(b) A	11 Other	Design Costs				0	
(c) To	otal					0	
(d) C	ontract					0	
(e) I:	n-house					0	
(4) Const	truction	Contract Award				06 OCT	
(5) Const	truction	Start				06 DEC	
(6) Cons	truction	Completion				08 JAN	
which:	is compa	letion of Project De cable to traditional cability.					

b. Equipment associated with this project provided from other appropriations: $\ensuremath{\mathtt{N/A}}$

		,					
1. COMPONENT		FY 2012 MILITARY	CONSTRU	CTION	PROJECT	DATA	2. DATE
AIR FORCE	<u>. </u>	(comp	uter ger	erate	ed)		
3. INSTALLATION	3. INSTALLATION AND LOCATION					TLE	
HURLBURT FIELD,	HURLBURT FIELD, FLORIDA				IGN ROADS		
5. PROGRAM ELEM	ENT	6. CATEGORY CODE	7. PRO	JECT I	NUMBER	8. PROJECT	COST (\$000)
27596		851-147	FI	EV993	011	. 5	,400
		9. cos	T ESTI	MATES			
		TTEM		77./34	YFITMAUO	UNIT	COST
		14000		10/84	QUANTITY	<u> </u>	
PRIMARY FACILITIE	s				<u> </u>		2,304
REALIGN ROADS				LS	1	ļ	(2,304)
SUPPORTING FACILI	TIES						2,304
UTILITIES				LS	İ		(768)
PAVEMENTS				LS			(768)
SITE IMPROVEMENT	:S			LS			(768)
SUBTOTAL					1	[4,608
CONTINGENCY	(10.0	%)		1			461
TOTAL CONTRACT CO	ST			}		<u> </u>	5,069
SUPERVISION, INSP	ECTION 1	AND OVERHEAD (5.7 %)				289
TOTAL REQUEST							5,358
TOTAL REQUEST (ROUNDED)				1			5,400

10. Description of Proposed Construction: Realign intersections, widen roads, construct new roads and extend existing roads. Work includes demolition of structures, relocation of utilities, refuge lanes, curb and gutters, base work, cut and fill, new driveway accesses from side streets. Includes utilities/lift station relocation, demolition and all necessary support.

11. REQUIREMENT: LS ADEQUATE: LS SUBSTANDARD: LS

PROJECT: Improve base road network.

REQUIREMENT: Base road network improvements are needed to support the increased traffic flow which has resulted from Congressionally supported Speciail Operations Forces (SOF) revitalization. Additionally, Okaloosa County has constructed a new 4 lane corridor to the base's east entrance but traffic flow is constricted at the gate since only two lanes currently exist. The lack of adequate refuge lanes and signalization result in significant traffic delays during rush hour. These delays require the use of personnel to direct traffic in order to prevent gridlock.

CURRENT SITUATION: The existing road system was constructed in the 1950's and was designed for a base population of between 2000 to 3000 personnel. Base population has tripled since then and the Community Center has been moved to the east side of the base with no improvements to the basic road system. The new east side Community Center consists of a 76,000 SF Commissary, a 52,000 SF AAFES Shopping Center and a 35,000 SF Clinic which have attracted many retired and active duty patrons and increased traffic flow dramatically. The present road network cannot support the increased traffic flows. Traffic flow through both entrances reduces from four lanes to two lanes, thus creating bottlenecks at the entrances. Congestion and delays occur during normal duty hours. Traffic counts have increased by 22 percent at the Main gate and over 190 percent at the East gate since the SOF build up has occurred. The intersection at Bartley and O'Neil Avenue must have traffic safety improvements done to support existing base development. Existing level of service on Cody and Independence Road is "F", traffic flow is near gridlock during peak periods. The Base Comprehensive Plan Traffic Master Plan

1. COMPONENT AIR FORCE		FY 2012 MILITARY Co	D ATA	2. DATE		
3. INSTALLATIO	N AND LO			4. PROJECT 1		
HURLBURT FIEL				REALIGN ROAL		
	,		<u> </u>	JECT NUMBER	<u> </u>	
5. PROGRAM EL	EMENT	6. CATEGORY CODE	8. PROJECT CO	ST (\$000)		
27596		851-147	7 FTEV993011			400
12. SUPPLEMEN	TAL DATA	;				
a. Estimate	d Design	Data:				
(1) Statu	ıs:					
(a) Da	ite Desig	m Started			04	1-AUG-05
(b) Pa	arametric	: Cost Estimates used	i to dev	velop costs		YES
* (c) Percent Complete as of 01 JAN 2011						35 %
* (d) Date 35% Designed					0:	L- JAN- 07
(e) Date Design Complete					04	4-AUG-06
(f) E	nergy Sto	dy/Life-Cycle analy	sis was,	/will be perf	Formed	NO
(2) Basis	3 :					
• •		or Definitive Design				NO
(b) Wi	here Desi	ign Was Most Recentl	y Used	-		
(3) Total	Cost (c	(a) = (a) + (b) or (d)) + (e)	:		(\$000)
(a) P:	roduction	n of Plans and Speci	ficatio	ns .		0
(b) A	ll Other	Design Costs				0
(c) Te	otal					0
(d) C	ontract					0
(e) I	n-house					0
(4) Const	truction	Contract Award				06 OCT
(5) Const	truction	Start				06 DEC
(6) Cons	truction	Completion				08 JAN
which:	is compa:	letion of Project De rable to traditional tability.				

b. Equipment associated with this project provided from other appropriations: N/A

		. 12					
1. COMPONENT		FY 2005 MILITARY	CONSTRU	CTION	PROJECT	DATA	2. DATE
AIR FORCE		(comp	iter ger	erate	ed)	·····	
3. INSTALLATIO	3. INSTALLATION AND LOCATION				ROJECT TI	CLE.	
HURLBURT FIELD, FLORIDA				DORMI	TORY		
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJ			JECT 1	NUMBER	8. PROJECT	COST (\$000)	
27596	!	721-312	FI	EV993	013	9	,300
		9. COS	T ESTI	MATES			
		ITEM		U/M	OUANTITY	UNIT	COST
DORMITORY (144 P	DORMITORY (144 RM)						6,601
DORMITORY				SM	4,752	1,375	(6,534)
ANTITERRORISM :	FORCE PRO	TECTION		SM	4,752	14	(67)
SUPPORTING FACIL	lties				1		1,810
UTILITIES				LS	1		(775)
PAVEMENTS				LS	-		(650)
SITE IMPROVEME	nts			LS			(350)
COMMUNICATION	System			LS			(35)
SUBTOTAL						1	8,411
CONTINGENCY	(5.0	%)			1		421
TOTAL CONTRACT	COST					Į	8,831
SUPERVISION, IN	SPECTION	AND OVERHEAD (5.7 %)			1	503
TOTAL REQUEST					ļ		9,334
TOTAL REQUEST (TOTAL REQUEST (ROUNDED)						9,300
EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)				1 .		}	(550.0)

10. Description of Proposed Construction: A three-story facility with reinforced concrete foundation and floor slabs, masonry walls and roof. Includes roombath/kitchen-room modules, laundry rooms, storage, lounge areas, site preparation, and all other supporting facilities. Force protection includes structural reinforcement of exterior walls and fully tempered insulated glass windows.

Air Conditioning: 450 Tons Grade Mix: E1-E4 144

11. REQUIREMENT: 1,719 RM ADEQUATE: 1,128 RM SUBSTANDARD: 0 RM

PROJECT: Construct a dormitory. (Current Mission)

REQUIREMENT: A major Air Force objective is to provide unaccompanied enlisted personnel with housing conducive to their proper rest, relaxation and personal well-being. Properly designed and furnished quarters providing some degree of individual privacy are essential to the successful accomplishment of the increasingly complicated and important jobs these people must perform. This project is in accordance with the Air Force Dormitory Master Plan. Comply with DoD new Unified Facilities Criteria, "DoD Minimum Antiterrorism Standards for Buildings."

CURRENT SITUATION: The base has insufficient facilities to accommodate the unaccompanied enlisted personnel housing. Local rentals and utilities are so expensive that enlisted personnel cannot afford to live in off base housing. There are no existing facilities on base that could be converted or improved to the new 1+1 standard. IMPACT IF NOT PROVIDED: Adequate living quarters will continue to be unavailable resulting in degradation of morale, productivity, and career satisfaction for unaccompanied enlisted personnel. Lowered morale will contribute to retention difficulties for the Air Force.

ADDITIONAL: This project meets the criteria/scope specified in the new uniform barracks

1. COMPONENT	FY 2008 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE	(computer generated)					
3. INSTALLATION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELD	, FLORI	DA	_	DORMITORY		
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	NUMBER	8. PROJECT CO	ST (\$000)
27596		721-312	F	TEV993013	00	

construction standard known as "one-plus-one" established by OSD. All known alternatives were considered during the development of this project. No other option could meet the mission requirements. Therefore, no economic analysis was needed or performed. FY 2002 Unaccompanied Housing RPM conducted: \$508K. FY 2003 Unaccompanied Housing RPM conducted: \$225K. Future Unaccompanied Housing RPM requirements (estimated): FY04: \$230K; FY05: \$235K; FY06. BASE CIVIL ENGINEER: Michael E. Dejarnette, Lt Col, (850) 884-7701. Dormitory: 4,752 SM = 51,132 SF.

JOINT USE CERTIFICATION: Mission requirements, opertional considerations, and location are incompatible with use by other components.

COMPONENT	12. FY 2005 MTLT	TARY CONSTRUC	TON DRATECT	Dama	2. DATE
IR FORCE		computer gene			
	N AND LOCATION	July 1000 gene			L
			4. PROJECT T	TTLE	
URLBURT FIELD	, FLORIDA		DORMITORY	,	
. PROGRAM ELI			JECT NUMBER	8. PROJECT CO	ST (\$000)
27596	721-312	FT	EV993013	9,	300
.2. SUPPLEMENT	FAL DATA:				
a. Estimate	d Design Data:				
(1) Status	s:				
• •	te Design Started			1!	5-APR-03
(b) Pa	rametric Cost Estimate	as used to de	velop costs		YES
	rcent Complete as of C		_		35 %
* (d) Da	te 35% Designed			0:	1-0CT-03
(e) Da	te Design Complete			19	5-AUG-04
(f) En	ergy Study/Life-Cycle	analysis was	/will be perf	ormed	ио
(2) Basis	:				
(a) St	andard or Definitive I	Design -			YES
(b) Wh	ere Design Was Most Re	acently Used	_		EGLIN
(3) Total	Cost (c) = $(a) + (b)$	or (d) + (e)	:		(\$000)
(a) Pr	oduction of Plans and	Specificatio	ns		372
(b) Al	1 Other Design Costs				232
(c) To	tal				604
• •	ontract				511
(e) In	ı-house				93
(4) Const.	ruction Contract Award	i			04 DEC
(5) Const	ruction Start				05 Jan
(6) Const	ruction Completion				00 JOL
which i	es completion of Proje s comparable to tradi- nd executability.				
b. Equipmen	at associated with this	s project pro	vided from ot	cher appropria	tions:
EQUIPMEN	T NOMENCLATURE	PROCURI APPROPRIA	NG APPR	AL YEAR OPRIATED EQUESTED	COST (\$000
FURNISHI	ngs	3400		2005	550
-				- ·	



1. COMPONENT		FY 2008 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE		(computer generated)					
3. INSTALLATIO	3. INSTALLATION AND LOCATION 4. PR					····	
HURLBURT FIELD, FLORIDA						ONTROL WING ERCISE CONTRO	OL COMPLEX
5. PROGRAM ELI	MENT	6. CATEGORY CODE	7. PRO	JECT 1	TUMBER	8. PROJECT (COST (\$000)
27596 141-454 FT			EV993	031	24	,000	
		9. COS	T ESTI	MATES			
	TTEM				OUANTITY	UNIT	COST
505 CCW HEADQUAI	RTERS/EXE	RCISE CONTROL COMPLEX			-		16,725
EXERCISE CONTR		TY		SM	6,750	1 1	(11,981)
WING HEADQUART ANTITERRORISM/		OFFICET ON		I.S.	2,664	1,750	(4,662) (82)
SUPPORTING FACE		312014UN					4,606
UTILITIES				LS			(1,482)
PAVEMENTS			LS	İ	}	(612)	
SITE IMPROVEMENTS				LS		- [(1,620)
DEMOLITION				SM	5,887	51	(300)
COMMUNICATION SYSTEM				LS			(312)

SM

EA.

1,538

52

100.000

10. Description of Proposed Construction: Construct new Wing Headquarters and Exercise Control Squadron facilities, composed of reinforced concrete foundation and floor slab, masonry walls and sloping metal roof. Includes utilities, pavements, site improvements and all other necessary support. Force protection includes reinforced exterior walls and fully laminated windows. The project requires demolition of three buildings for a total of 5,887 SM.

(5.7 %)

Air Conditioning: 253 Tons

ASBESTOS REMOVAL/LEAD PAINT ABATEMENT

SUPERVISION, INSPECTION AND OVERHEAD

(5.0 %)

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

ELEVATORS

CONTINGENCY

TOTAL REQUEST

TOTAL CONTRACT COST

TOTAL REQUEST (ROUNDED)

SUBTOTAL

11. REQUIREMENT: 19,867 SM ADEQUATE: 10,453 SM SUBSTANDARD: 0 SM

PROJECT: Construct a new Wing Headquarters and Exercise Control/Consolidated Sensitive Compartmented Information Facility (SCIF). (Current Mission)

REQUIREMENT: The CSAF directed the 505th Command and Control Wing to centralize all existing and new command and control systems into a cohesive, state of the art system that will modernize, streamline and improve command and control techniques throughout the Air Force. The Air Operations Center (AOC) was declared a Weapons System and the reengineered 505th CCW has gone from hosting annual Blue Flag exercises, conducting several associated courses with 26 missions, to conducting ten annual flag type exercises, with more than 60 missions and 28 annual in-residence courses. The rise of Joint National Training Capability and Joint Training Transformation Initiative will substantially increase the ops tempo, size and requirements for the 505th EXS and will

(80)

(200)

21,332 1,067

22,398

1,277 23,675

24,000

(6,385.0)

1. COMPONENT	FY 2008 MILITARY CONSTRUCTION PROJECT DATA					2. DATE	
AIR FORCE			(comp	iter gei	nerated)		
3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
HURLBURT FIELD	HURLBURT FIELD, FLORIDA 505 COMMAND CONTROL WING HDQUARTERS/EXERCISE CONTROL						COMPLEX
5. PROGRAM ELE	MENT 6.	6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000)				ST (\$000)	
27596		141-454 FTEV993031 24,000					

expand requirements to support multiple simultaneous events. These will include Army Warfighters, Navy Battle Group In-Port Exercise and JTF EXS and 6 Blue Flags a year. The substantial and increasing role of Distributed Mission Operations will require M&S support to enable near-continuous distributed training events. Major exercises require several events in which architectures are built, tested and sustained well prior to the exercise. As we go to 24 hour exercises, USAFE and PACAF will increasingly rely on the 505th for Modeling and Simulation (M&S) reachback. This represents over a 300% increase in new training and mission requirements in the last four years. The unit now conducts initial qualification training for individuals who have orders to any AF Command and Control Center (AOC, JACC, CAOC, etc) in the world so that upon completion of Mission Qualification training they can receive their special experience identifier. The 505 CCW is charged by OSD with Air Tasking Order (ATO) interoperability training for all DoD. All four services now send students to the C2 Warrier School for process and application training in support of the Joint Force Air Component Commander. Force protection will comply with minimum DoD standards.

CURRENT SITUATION: This is the final phase of a two part MILCON program designed to efficiently reconfigure all associated command and classified functions into two centralized facilities to eliminate severe facility space shortages. Existing exercise facility, headquarters group and SCIF functions do not have sufficient or properly configured space or support control systems to satisfactory accomplish their dynamically expanding missions. These functions share a 50 year old, BOMARC hangar which has been modified and renovated over the past years to support numerous other purposes. This facility has numerous inefficient split-level heating and ventilation support systems and insufficient supporting power systems. Presently, command, control and SCIF functions are scattered in half a dozed other facilities, resulting in lost efficiency and wasted man-hours. The existing secure compartmental/program level informational area is severely limited and forces the relocation of classified courses and seminars to other installations with larger cleared areas. During SCIF related battle staff exercises and training class scenarious over twenty personnel must work out of areas designed to support a maximum of five to six operators. SCIF training seminars have had to be indefinitely postponed because the existing SCIF is not large enough or is overscheduled to meet higher priority requirements. The unit requires a SCIF four times larger than is presently provided. The wing has been forced to continually borrow Eglin AFB facilities and temporary lease a large number of trailers to meet new expanded exercise requirements. The unit will not be able to meet escalating projected mission objectives. Three facilities and a total area of 5887 SM will be demolished.

IMPACT IF NOT PROVIDED: The Air Force will not have sufficient properly trained command and control specialists to accomplish our primary mission. Only 40% of the current and projected student load will be exercised and trained. We will continue to waste valuable man-hours temporarily leasing and setting up trailers with temporary communications and computer systems, and then reconfiguring the support systems to support as many exercises, experiments and students as possible. The exercise squadron will not be able to accomplish related missions such as PACAF Blue Flag, or USAF Blue Flag, as well as Simulator Exercises (SIM EX) and Focus Lens Asian exercises and others. We will not be able to conduct SCIF level activities associated with Homeland Security, CSAF directed SAP/SAR programs, command and control courses in Joint Search/Rescue, Space Basics,

1. COMPONENT AIR FORCE	FY 2008 MILITARY CONSTRUCTION PROJECT DATA (computer generated)					2. DATE
3. INSTALLATION HURLBURT FIELD			4. PROJECT TITLE 505 COMMAND CONTROL WING HDQUARTERS/EXERCISE CONTROL			
5. PROGRAM ELE	EMENT	6. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT COS			OST (\$000)
27596		141-454 FTEV993031 24,000				

Space Advanced, Community College Accreditation, AIA/AMC/AFSPACE/ANG/ESC/AETC/Army/Navy Detachment Integration unless this project is approved.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates there is only one option that will meet operational requirements. A certificate of exception has been prepared. This project is the second phase of a two-phased MILCON program to develop a facility program that will meet the expanded mission of the 505 CCW so that the Air Force/Armed Forces can fight and win decisively in a minimum of time and with minimum losses. Base Civil Engineer: Lt Col William A. Kolakowski, Phone 850/884-7701. (Wing Headquarters/ Exercise Control Complex: 9414 SM = 101.295 SF).

JOINT USE CERTIFICATION: Mission Requirements, operational considerations and location are incompatible with use by other components.

1. COMPONENT AIR FORCE	FY 2008 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)						
3. INSTALLATIO	N AND LOCA	TION		4. PROJECT	PITLE		
HURLBURT FIELD	, FLORIDA		·		CONTROL WING EXERCISE CONTR	ROL COMPLEX	
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	OST (\$000)	
27596		141-454	FT	EV993031	24	,000	
12. SUPPLEMENT	AL DATA:						
a. Estimated	l Design Da	nta:					
(1) Status	s:						

\ - <i>/</i>			
	(a)	Date Design Started	15-APR-04
	(b)	Parametric Cost Estimates used to develop costs	YES
*	(c)	Percent Complete as of 01 JAN 2007	15%
*	(d)	Date 35% Designed	15-AUG-05
	(e)	Date Design Complete	15-AUG-06
	(£)	Energy Study/Life-Cycle analysis was/will be performed	NO

(5) Construction Start

(e) Date Design Complete	13 MOG-00
(f) Energy Study/Life-Cycle analysis was/w	ill be performed NO
(2) Basis:	
(a) Standard or Definitive Design -	NO
(b) Where Design Was Most Recently Used -	
(3) Total Cost (c) = (a) + (b) or (d) + (e):	(\$000)
(a) Production of Plans and Specifications	1,251
(b) All Other Design Costs	834
(c) Total	2,085
(d) Contract	1,564
(e) In-house	521
(4) Construction Contract Award	07 DEC

(6) Construction Completion 10 AUG

b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
FURNISHINGS	3400	2009	4,500
PREWIRED WORKSTATIONS	3400	2009	1,660
COMMUNICATION EQUIPMENT	3400	2009	225

08 FEB

^{*} Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability.

1. COMPONENT	COMPONENT FY 2012 MILITARY CONSTRUCTION PROJECT DATA 2. DATE							2. DATE
AIR FORCE	AIR FORCE (computer generated)							<u> </u>
3. INSTALLATIO	3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
HURLBURT FIEL	, FLORI	DA.			SOF	SQUADRON	N OPS, 6 SOS	
5. PROGRAM EL	EMENT	6. CATEGORY	CODE	7. PRO	ECT 1	NUMBER	8. PROJECT CO	OST (\$000)
11205		141-753	3	FTI	EV993	033	5,	500
12. SUPPLEMEN	TAL DATA	:						
a. Estimate	d Design	Data:						
(1) Statu	ıs:							
1		m Started					1!	5-APR-06
(b) Pa	rametrio	Cost Estimate	es used	i to dev	relop	costs		YES
* (c) Pe	ercent Co	emplete as of (01 JAN	2011				100%
* (d) Da	ate 35% I	esigned					0:	1-0 CT- 06
(e) Da	ate Desig	n Complete					0:	1-0CT-07
(f) Ex	ergy St	dy/Life-Cycle	analy	sis Was/	will	be perf	formed	МО
(2) Basis	::							
1		or Definitive	Design	_				NO
(b) W	nere Des	ign Was Most R	ecently	y Used -	-			
(3) Total	Cost (e) = (a) + (b)	or (d)	+ (e):	:			(\$000)
(a) P	roduction	n of Plans and	Speci	fication	ns			167
1		Design Costs						82
(c) To								249
,	ontract							187 62
(e) 11	n-house							62
(4) Const	ruction	Contract Awar	4					
(5) Const	truction	Start						08 JAN
(6) Const	truction	Completion						
which :	is compa	letion of Proj						
Cost a	na execu	tability.						
b. Equipme	nt assoc	iated with thi	s proj	ect pro	vided	from ot	ther appropria	tions:
EQUIPMEN	IT NOMENO	LATURE		PROCURII PROPRIA		APPR	CAL YEAR OPRIATED EQUESTED	COST (\$000)

PREWIRED WORK STATION

3400

2008

300

1. COMPONENT	FY 2012 MILITARY CONSTRUCTION PROJECT DATA					2. DATE	
AIR FORCE		(computer generated)					
3. INSTALLATIO	ION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELD	ELD, FLORIDA SOF SQUADRON OPS, 6 SOS						
5. PROGRAM ELI	EMENT	6. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT C			ST (\$000)	
11205	141-753 FTEV993033 5,500						

IMPACT IF NOT PROVIDED: Lack of an adequate squadron operations facility will adversely impact the 6 SOS operations at Hurlburt Field.

ADDITIONAL: There is no criteria/scope for this project in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, this project does meet criteria scope specified in Air Force Handbook 32-1084, "Standard Facility Requirments." All known alternative options were considered during the development of this project. No other options could meet the mission requirements; therefore, no economic analysis was needed or performed. Base Civil Engineer: Jeffery L. Pitchford, Lt Col, USAF, 850/884-7701.

JOINT USE CERTIFICATION: IAW DOD Financial Management Regulation 7000.14-R, Vol 2B, Chapter 6, Joint Use construction has been considered. Unilateral construction is recommended based on the special operations mission to be performed in this facility.

,									
1. COMPONENT	FY 2011 MILITARY CONSTRUCTION PROJECT DATA 2. DATE								
AIR FORCE	AIR FORCE (computer generated)								
3. INSTALLATIO	N AND L	OCATION		4. PI	ROJECT TI	TLE			
HURLBURT FIELI	, FLORI	DA		CHILL	DEVELOP	MENT CENTER	į		
5. PROGRAM ELI	MENT	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)		
27596		740-884	FI	EV993	036	7	, 900		
		9. cos	T ESTI	MATES					
		ITEM		U/M	QUANTITY	UNIT	Cost		
CHILD DEVELOPME	CHILD DEVELOPMENT CENTER						6,020		
CHILD DEVELOPM	ENT CENT	ER (38,082 SF)		SM	3,538	1,625	(5,749)		
ANTITERRORISM/	FORCE PR	OTECTION (.5%)		LS	Ĭ	· }	(28)		
SUSTAINABILITY	CONSTRU	CTION (5%)		LS		.	(242)		
SUPPORTING FACT	LITIES]		1,135		
UTILITIES				rs			(400)		
PAVEMENTS				LS			(290)		
SITE IMPROVEME	nts			LS			(285)		
COMMUNICATION	System			LS	{		(160)		
SUBTOTAL					ļ		7,155		
CONTINGENCY (5.0 %)				1	}		358		
TOTAL CONTRACT	COST						7,513		
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %)						1	428		
TOTAL REQUEST						- [7,941		
TOTAL REQUEST (ROUNDED)					1	7,900		
\					1	1	1		

10. Description of Proposed Construction: Concrete foundation and floor slab, massary walls and sloping metal roof. Functional areas include core administration area, staff support area, facility support area and child care areas. Includes utilities, packing and all other necessary support. Includes minimum DoE interim force protection standards.

Air Conditioning: 95 Tons

11. REQUIREMENT: 5,442 SM ADEQUATE: 1,90

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

ADEQUATE: 1,904 SM SUBSTANDARD: 0 SM

PROJECT: Construct a Child Development Center. (Current Mission)

REQUIREMENT: Hurlburt Field has the third largest military population in the Air Force with over 7,000 military assigned in addition to 650 Civil Service employees. Currently 180 families are waiting to receive affordable, childcare in a quality AF Child Care Center. Additional space is required to accommodate infants 6 weeks to 12 months, pre toddlers 13-24 months, toddlers 25-36 months, and preschoolers 3-5 years. Additional space is also needed to accommodate hourly care, part-day preschool, and care while spouses seek employment, volunteers, and short-term care requirements. The total number of childcare spaces required to meet the needs of the Hurlburt Field Community is 400. Demolotion of inadequate family housing units and clearing of site for Child Development Center will be accomplished by Privatization Developer. Force protection will comply with minimum DoD standards.

CURRENT SITUATION: The existing childcare facility's capacity is 172. The facility was constructed in 1982 and the facility was renovated in 1994 that included an addition. Frequent reccurring problems with the HVAC, plumbing, moisture, and moldy odor, lead to costly repairs, unhealthy environment, and moving children. Families have to find care

(130.0)

1. COMPONENT	FY 2011 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE	(computer generated)					
3. INSTALLATION AND LOCATION			4. PROJECT TITLE			
HURLBURT FIELD	IELD, FLORIDA CHILD DEVELOPMENT CENTER					
5. PROGRAM ELE	EMENT 6	. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT COST			ST (\$000)
27596	740-884 FTEV993036 7,900					

in substandard facilities off base and have to pay higher rates because they do not have access to the sliding fee scale. Families using AF Family Child Care homes prefer the subsidized fees in the child development center.

IMPACT IF NOT PROVIDED: The 180 Air Force families will have to use public child care facilities located off-base in the surrounding Ft. Walton Beach, Niceville, Shalimar and Navarre communities. Off-base child care facilities are more expensive and will require additional driving time each day which will have an economic impact to each family as well as extending the time away from home each day which will affect the quality of life for assigned personnel and their families.

ADDITIONAL: This project meets the criteria/scope specified in the new Unified Facilities Criteria 4-740-14, "Child Development Centers." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Engineer: Lt Col, Jeffrey L. Pitchford, (850) 884-7701. Child Development Center: 3,538 SM = 38,082 SF.

JOINT USE CERTIFICATION: This facility can be used by other components on an "as available basis"; however, the scope of the project is based on Air Force requirements.

. COMPONENT	I	Y 2011 MILI				DATA	2. DATE
AIR FORCE (computer generated)							
. INSTALLATIO	ON AND LOCA	ATION		4	. PROJECT !	TITLE	
URLBURT FIEL	D, FLORIDA			c	HILD DEVEL	OPMENT CENTER	ł
5. PROGRAM EL	EMENT	6. CATEGORY	CODE	7. PROJE	CT NUMBER	8. PROJECT	COST (\$000)
27596		740-884	l	FTEV	993036	<u> </u>	7,900
.2. SUPPLEMEN	TAL DATA:						
a. Estimate	d Design D	ata:					
(l) Statu	ıs:						
	te Design						
(b) Pa	rametric (Cost Estimate	es use	d to deve	lop costs		YES
	_	olete as of (01 JAN	2010			
	ate 35% Des	-					
	ate Design	_	_				
(f) Ei	ergy Study	//Life-Cycle	analy	sis was/w	111 be peri	cormed	МО
(2) Basis							
		Definitive I n Was Most R					МО
(3) Total	L Cost (c)	= (a) + (b)	or (d)) + (e):			(\$000)
(a) P:	roduction	of Plans and	Speci	fications	•		0
(b) A	ll Other D	esign Costs					0
(c) T	otal						0
• •	ontract						0
(e) I:	n-house						0
(4) Const	truction Co	ontract Award	ď				
(5) Cons	truction S	tart					
(6) Cons	truction C	ompletion					
* Indica	tes comple	tion of Proi	ect De	finition	with Param	etric Cost Es	timate
	_	-				re valid scor	
cost a	nd executa	bility.					•
b. Equipme	nt associa	ted with thi	s proj	ect provi	ided from o	ther appropr	iations:
	•				FIS	CAL YEAR	
equipme	NT NOMENCL	ATURE		PROCURING PROPRIAT	APPE	ROPRIATED REQUESTED	COST (\$000)
PLAYGRO	UNG EQUIPM	ENT		3400		2008	130
emit and	nug evantem			3400		2000	130

FY 2012 MILITARY CONSTRUCTION PROJECT DATA				
(computer generated)				
AND LOCATION	4. PROJECT TIT	LE		
FLORIDA	MUNITIONS DEL:	IVERY ROAD		
MENT 6. CATEGORY CON	E 7. PROJECT NUMBER	B. PROJECT COST (\$000)		
851-147	FTEV003001	3,600		
	(CONTINUE OF LOCATION FLORIDA 6. CATEGORY CODE	(computer generated) AND LOCATION FLORIDA FLORIDA G. CATEGORY CODE 7. PROJECT NUMBER 6		

project (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701.

JOINT USE CERTIFICATION: This is an installation utility/infrastructure project, and does not qualify for joint use at this installation. However, all tenants on this installation are benefited by this project.

1. COMPONENT	FY 2012 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE						
3. INSTALLATION HURLBURT FIELD				4. PROJECT T MUNITIONS I	PITLE DELIVERY ROAD	
5. PROGRAM EL 11205	EMENT	6. CATEGORY CODE 851-147	7. PROJECT NUMBER FTEV003001		8. PROJECT COST (\$000) 3,600	

12. SUPPLEMENTAL DATA:

- a. Estimated Design Data:
 - (1) Status:
 - (a) Date Design Started
 - (b) Parametric Cost Estimates used to develop costs

YES

- * (c) Percent Complete as of 01 JAN 2011
- * (d) Date 35% Designed
 - (e) Date Design Complete
 - (f) Energy Study/Life-Cycle analysis was/will be performed

NO

(2) Basis:

(a) Standard or Definitive Design -

NO

- (b) Where Design Was Most Recently Used -
- (3) Total Cost (c) = (a) + (b) or (d) + (e):

(\$000)

- (a) Production of Plans and Specifications
- (b) All Other Design Costs
- (c) Total
- (d) Contract
- (e) In-house
- (4) Construction Contract Award
- (5) Construction Start
- (6) Construction Completion
- * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability.
- b. Equipment associated with this project provided from other appropriations: N/A

1. COMPONENT	FY 2007 MILITARY	CONSTRUCTION PROJECT	DATA 2. DA	ATE
AIR FORCE	(comp	uter generated)		
3. INSTALLATION AND	LOCATION	4. PROJECT T	ITLE	
HURLBURT FIELD, FLO	RIDA	VEHICLE MAIN	TENANCE FACILITY (823	RHS)
5. PROGRAM ELEMENT	6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$0	00)
27596	214-425	FTEV003009	7.000	

9. COST ESTIMATES UNIT COST TTEM U/M QUANTITY VEHICLE MAINTENANCE FACILITY 4,225 3.031 1.380 (4,183) VEHICLE MAINTENANCE FACILITY SM 3.031 (42) ANTITERRORISM/FORCE PROTECTION SM 14 SUPPORTING FACILITIES 2,052 OTILITIES (400) LS 17,150 (772) PAVEMENTS SM 45 SITE IMPROVEMENTS SM 19,250 15 (289) 104 DEMOLITION 2,600 SM (270) 1,200 ASBESTOS ABATEMENT SM 140 (168) COMMUNICATION SUPPORT LS (79) TEMPORARY FACILITY T.S (74) SUBTOTAL 6.277 CONTINGENCY (5.0 %) 314 TOTAL CONTRACT COST 6,591 SUPERVISION, INSPECTION AND OVERHEAD (5.7 %) 376 TOTAL REQUEST 6,967 TOTAL REQUEST (ROUNDED) 7,000 EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD) (175.0)

10. Description of Proposed Construction: Reinforced concrete foundation, preengineered steel frame walls, standing seam metal roof, overhead crane, hydraulic lifts, utilities, fire detection/protection, oil/water separator, fuel spill containment area, pavements, site improvements, landscaping and demolition of three facilities (2,600 SM). Includes minimum DoD force protection standards.

Air Conditioning: 140 Tons

11. REQUIREMENT: 3,818 SM ADEQUATE: 818 SM SUBSTANDARD: 2,600 SM

PROJECT: Construct Vehicle Maintenance Facility (Current Mission).

REQUIREMENT: Provide a facility to maintain special purpose heavy construction equipment and general purpose vehicles vital to the RED HORSE mission. Facility will be configured to provide 10 drive through maintenance bays capable of servicing two vehicles at once. One bay must be capable of servicing 80' tractor trailors, two bays will possess hydraulic lifts, and two bays will possess an overhead crane system. Two bays must be equipped to handle tracked vehicles, and possess special loading rails and tool access floor systems. Facility will include exterior and interior compressed air stations, an interior vehicle exhaust system, a fuel spill containment system, mechanical shop ventilation, battery and parts storage areas, and administrative support areas complete with HVAC. Construction phasing will be required. A temporary facility is required to house the vehicle maintenance function during construction. The vehicle maintenance complex is restricted in space so the new facility will go on the footprint of the existing facility. Temporary utilities to support temporary structures are

1. COMPONENT	FY 2007 MILITARY CONSTRUCTION PROJECT DATA				2. DATE	
AIR FORCE	(computer generated)					<u></u>
3. INSTALLATIO	N AND LO	CATION		4. PROJECT T	TLE	
HURLBURT FIELD	, FLORIE)A		VEHICLE MAIN	ENANCE FACILIT	Y (823 RHS)
5. PROGRAM ELE	EMENT	6. CATEGORY CODE	7. PROJECT NUMBER		8. PROJECT COST (\$000)	
27596		214-425	FTEV003009		7,000	

required. Must comply with minimum DoD force protection standards.

CURRENT SITUATION: The vehicle maintenance functions currently operate from three substandard facilities. The primary facility was constructed in 1967 as a temporary helicopter hangar and retrofitted in 1974 for RED HORSE use. All infrastructure systems require immediate replacement. The facility does not properly ventilate harmful fumes and violates current life and industrial safety standards. The lighting, electrical, and heating systems are inadequate. The floor slabs are cracked and uneven, resulting in poor drainage and spill control. The roofs leak and have been patched so many times they need to be replaced. All the doors are out of alignment and are severely deteriorated. The exterior of the facility lacks adequate environmental containment equipment, and as such runs the risk of hazardous spills and environmental fines and penalties. The existing facilities are poorly configured and do not efficiently meet mission requirements. Due to these adverse conditions, personnel are often forced to work outside in extreme temperatures. Consolidating vehicle maintenance activities will improve mission capability by increasing worker efficiency and free valuable real estate for other critical uses. Workers will gain the space and equipment necessary for the safe and professional work environment needed to meet RED HORSE mobility requirements. RED HORSE has seen vehicle fleet growth of approximately 16 vehicles due to the incorporation of airborne operations. The 823rd RED HORSE is also the pilot unit for testing new vehicles and equipment which require additional space for analysis, training and maintenance activities. In addition, they are authorized to acquire "special capaiblity" equipment, known as "X-reg" equipment that accounts for approximately 110 additional items requiring maintenance.

IMPACT IF NOT PROVIDED: Personnel will continue to be subjected to hazardous working conditions, and environmental risks will go unabated. With the expansion of the RED HORSE vehicle fleet and the continued use of oversized pieces of equipment, more mechanics will be forced to work outside in extreme temperatures with reduced accessibility to tools and parts. With the continued facility deterioration and simultaneous vehicle fleet growth, both in size and number, it will become increasingly difficult to satisfactorily perform safe, proper, and efficient maintenance necessary to meet vital mission requirements.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, new construction) was done. It indicates there is only one option that will meet operational requirements. A certificate of exception has been prepared. Base Civil Engineer: Lt Col Jeffrey L. Pitchford; 850-884-7701. (Vehicle Maintenance Facility: 3,000 SM = 32,280 SF)

JOINT USE CERTIFICATION: Mission requirements, operational considerations, and location are incompatible with use by other components.

. COMPONENT	FY 20	007 MILITARY C			DATA	2.	DATE	
IR FORCE		(comput	er generat	ed)		<u></u>		
. INSTALLATIO	N AND LOCATION	₹	4.	PROJECT T	ITLE			
HURLBURT FIELD, FLORIDA VEHICLE MAINTENANCE FA			TENANCE FACIL	ITY (823			
5. PROGRAM ELI	EMENT 6.	CATEGORY CODE	7. PROJEC	. PROJECT NUMBER 8. PROJECT			COST (\$000)	
27596		214-425	FTEV0	03009	7,000			
12. SUPPLEMEN	TAL DATA:	- '						
a. Estimate	d Design Data:							
(1) Statu	s:							
(a) Da	te Design Star	rted			1	5-APR	-05	
(b) Pa	rametric Cost	Estimates use	d to devel	op costs		•	YES	
- •	rcent Complete		2006				L5 ¥	
	te 35% Designo					1-AUG		
	te Design Com	•				1-SEP		
(f) Er	ergy Study/Li:	Ee-Cycle analy	sis Was/Wi	ll be perf	ormed		YES	
(2) Basis		•-•••					***	
	andard or Def ere Design Wa	_					NO	
(3) Total	. Cost (c) = (a	a) + (b) or (d	- l) + (e):			(\$0	00)	
	oduction of P						384	
	1 Other Desig	-					192	
(c) T	-						576	
(d) Ca	ontract						480	
(e) I ₁	n-house						96	
(4) Const	ruction Contra	act Award				07	JAN	
(5) Const	ruction Start					07	FEB	
(6) Const	truction Compl	etion				08	JUN	
which :	tes completion is comparable nd executabili	to traditional						
b. Equipme	nt associated	with this pro	ject provid	led from ot	ther appropria	tions	::	
				FISC	CAL YEAR			
EQUIPMEN	T NOMENCLATUR	E A	PROCURING PPROPRIATION	APPR	OPRIATED EQUESTED	•	COST (\$000)	
FURNITUE	n a		3400		2006		175	

	 				·			
1. COMPONENT	FY 2012	MILITARY	CONSTRI	JCTION	PROJECT	DATA	2. DATE	
AIR FORCE		(comp	iter ge	nerate	d)			
3. INSTALLATION	AND LOCATION			4. PI	ROJECT TI	PLE		
HURLBURT FIELD,	FLORIDA			EAST	SIDE FIT	NESS CENTER		
5. PROGRAM ELEM	ENT 6. CATEG	ORY CODE	7. PRO	JECT 1	TUMBER	8. PROJECT	COST (\$000)	
27596	740	-674	F	EV003	023	9	9,200	
		9. cos	T ESTI	MATES				
	ITEM			U/M	OUANTITY	UNIT	COST	
				T				
EAST SIDE FITNESS	CENTER]	1	6,830	
GYMNASIUM (50,00	0 SF)			SM	4,645	1,463	(6,796)	
FORCE PROTECTION	(.5%)			LS			(34)	
SUPPORTING FACILI	ries						1,434	
UTILITIES				LS	1		(372)	
PAVEMENTS				LS			(348)	
SITE IMPROVEMENT	s			LS	•		(244)	
DEMOLITION (39,2	49 SF)			SM	3,646	129	(470)	
SUBTOTAL					1		8,264	
CONTINGENCY	(5.0 %)			Ì		İ	413	
TOTAL CONTRACT CO	ST					1	8,677	
SUPERVISION, INSP	ection and overhe	AD (5.7 %)				495	
TOTAL REQUEST							9,172	
				i	1	1	1	

10. Description of Proposed Construction: Construct a new 4,645 SM facility of concrete masonry walls with steel trusses and joist, concrete slab and footings. Functional areas include lobby, admin support, locker rooms, group exercise, fitness equipment spaces, racquetball courts, and a Health & Wellness Center (HAWC) with all necessary support. Antiterrorism force protection measures to include reinforced exterior walls and fully tempered glass windows.

Air Conditioning: 125 Tons

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

TOTAL REQUEST (ROUNDED)

11. REQUIREMENT: 8,487 M2 ADEQUATE: 2,874 M2 SUBSTANDARD: 3,636 M2

PROJECT: Construct East Side Fitness Center. (Current Mission).

REQUIREMENT: Because of the mission at Hurlburt Field, physical fitness is a top priority for the active duty personnel. Hurlburt also hosts four ACC flag exercises throughout the year and students at the Joint Special Operations University and the USAF Special Operations School. Consequently the fitness centers are heavily utilized and at times overcrowded. The hours of operation for these facilities have been increased to 20 hours per day to help alleviate the overcrowded conditions.

CURRENT SITUATION: Within the next five years Hurlburt Field will increase in population due to the increase of missions. It is estimated that approximately 1,635 active duty military personnel will impact the base population. Hurlburt Field will be constructing three new domitory facilities on the east side of the base to accommodate the increase in mission and personnel. At present there exists a small dining/fitness center on the east side of the base. This 1,373 SM fitness center is not adequate to support the personnel on the East Side and the CSAF directed physical training program. The current location of the HAWC within the Commando Fitness Center is not ideal. The HAWC areas are not contained within a suite, the functional areas are undersized, and

9,200

(600.0)

1. COMPONENT	FY 2012 MILITARY CONSTRUCTION PROJECT DATA				2. DATE	
AIR FORCE	L	(Compt	iter ge	nerated)		
3. INSTALLATIO	LLATION AND LOCATION 4. PROJECT TITLE					
HURLBURT FIELD	, FLORII	DA		EAST SIDE FI	TNESS CENTER	
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PROJECT NUMBER		8. PROJECT CO	ST (\$000)
27596		740-674 FTEV003023 9,2				00

some functional areas do not exist.

IMPACT IF NOT PROVIDED: Facilities will not be in place to suppport the new mission beddown of CV-22 in concert with AFSOC's concept of operations on Hurlburt Field. Synchronization of this work is crucial to AFSOC's ability to support the US Special Operations mission. Personnel at Hurlburt Field will be forced to use overcrowded fitness facilities, productivity will be lost, disrupting mission essential work accomplishment. This will adversely impact morale, welfrare, and retention of personnel which play a vital role in sustaining overall mission readiness.

ADDITIONAL: This project meets the criteria/scope specified in Part II of Military
Handbook 1190, "Facility Planning and Design Guide" as well as Air Force Handbook 321084 "Facility Requirements." All known alternative options were considered during the
development of this project. No other option could meet the mission requirements;
therefore, no economic analysis was needed or performed. A certificate of exception has
been prepared. Base Civil Engineer: Lt Col , 850-884-7701. Fitness
center: 4,645 SM = 50,000 SF.

JOINT USE CERTIFICATION: This facility can be used by other components on an "as available" basis; however, the scope of the project is based on Air Force requirements.

IR FORCE	. COMPONENT FY 2012 MILITARY CONSTRUCTION PROJECT DATA				
		computer genera			
3. INSTALLATION A		l	4. PROJECT TI		
HURLBURT FIELD,	FLORIDA		EAST SIDE FITH	NESS CENTER	
5. PROGRAM ELEME	NT 6. CATEGORY	CODE 7. PROJ	ECT NUMBER 8	. PROJECT CO	ST (\$000)
27596	740-674	FTE	V003023	9,	200
12. SUPPLEMENTAL	DATA:				
a. Estimated D	esign Data:				
(1) Status:					
	Design Started			15	-APR-02
	etric Cost Estimate		elop costs		
	nt Complete as of 0	1 JAN 2011			100 ₺
	35% Designed			- -	-OCT-02
	Design Complete				OCT-03
(I) Energ	y Study/Life-Cycle	analysis was/	ull be bellor	mec.	МО
(2) Basis:		•			
	lard or Definitive D : Design Was Most Re	-			МО
(D) WINST	: Design was most he	centry used -			
	st (c) = (a) + (b)				(\$000)
	ection of Plans and	Specification	3		2
	Other Design Costs				0
(c) Total					2
(d) Conti					0
(e) In-ho	ouse				2
(4) Construc	tion Contract Award	l			
(5) Construc	tion Start				04 JAN
(6) Construc	ction Completion				
b. Equipment a	associated with this	project prov	ided from othe	er appropriat	ions:
			FISCAL	VEND	
		PROCURING			COST
equipment n	OMENCIATURE	APPROPRIAT	ion or req	UESTED	(\$000

									
1. COMPONENT FY 2010 MILITARY CONSTRUCTION PROJECT DATA 2. DATE									
AIR FORCE (computer generated)									
3. INSTALLATION AND LO	CATION		4	. PROJECT 1	ITLE				
HURLBURT FIELD, FLORIE	A.		1	SHOPPETTE F	CILITY	Ì			
5. PROGRAM ELEMENT	6. CATEGORY CODE	7. PR) OJE	CT NUMBER	8. PROJECT	COST (\$000)			
64239	740-383	F	TE	V005004	<u> </u>	490			
	9. COST	ESTIMA	TE	<u> </u>					
	ITEM	עם	M	QUANTITY	UNIT	COST			
PRIMARY FACILITIES						81			
SHOPPETTE FACILITY		s	м	90	900	(81)			
SUPPORTING FACILITIES						369			
UTILITIES		L	s	'		(78)			
PAVEMENTS		L	s			(88)			
SITE IMPROVEMENTS		I	s			(79)			
GAS DISPENSING		I	s			(124)			
SUBTOTAL		1				450			
CONTINGENCY (5.0 %))	1	Ì			23			
TOTAL CONTRACT COST	TOTAL CONTRACT COST					473			
SUPERVISION, INSPECTION AND OVERHEAD (4.3%)						20			
TOTAL REQUEST						493			
TOTAL REQUEST (ROUNDED)					<u> </u>	490			
UNFUNDED DESIGN		1				(60)			
EXCLUDED EQUIPMENT		- [1	(466)			

10. Description of Proposed Work: Permanent, non-combustible facility including concrete slab, masonry walls, sloping metal roof, above ground gasoline storage tanks and gasoline dispensers with vapor recovery. Exterior support includes utilities, services, communications, paving, walks and storm drainage.

Air Conditioning: 39 Tons

11. REQUIREMENT: 2,100 SM ADEQUATE: 1,300 SM

SUBSTANDARD: 0 SM

PROJECT: Construct Shoppette (AAFES PN).

<u>REQUIREMENT:</u> This project is required to provide a Shoppette and gas dispensing facility with above ground tanks on the east side of Hurlburt Field to meet the demand for services due to the continued growth at Hurlburt Field.

CURRENT SITUATION: Present Service Station cannot meet the current demand for the increased base population. There is no facility on the east side of Hurlburt and all Hurlburt Field personnel must travel an already congested roads to service their vehciles. The existing Shoppette/Class Six facilities on the west side is to small with no room for expansion.

IMPACT IF NOT PROVIDED: Failure to construct this project will impact unfavorably on the AAFES ability to provide adequate service to active and retired military and their dependents-contributing to low morals. Failure will also reduce potential supplemental funds for the Morals, Welfare and Recreation (MWR) Programs.

1. COMPONENT		FY 2007 MILITARY	CONST	RUCTION	PROJECT	DATA	2. DATE
AIR FORCE		(comp	ıter g	enerate	d)		
3. INSTALLATIO	N AND L	OCATION		4. PF	ROJECT TI	TLE	
HURLBURT FIEL	, FLORI	DA		25 IN	FORMATIO	N OPERATIONS	SQUADRON
				FACII	LITY		_
5. PROGRAM ELI	MENT	6. CATEGORY CODE	7. PR	OJECT 1	NUMBER	8. PROJECT	COST (\$000)
27596		141-456		FTEV013	021	6	,800
		9. cos	T EST	IMATES			
		ITEM		77 /14	OUANTITY	UNIT	COST
		1160		10/10	COMMITTE		
25 IO SQUADRON	FACILITY			j			5,201
SQUADRON OPERA	TIONS (24	,330 SF)		SM	2,260	1,299	(2,936)
SCIF SPACE (9,	744 SF)			SM	905	2,478	(2,243)
FORCE PROTECTI	on/antite	ERRORISM		Ls		1	(22)
SUPPORTING FACI	LITIES			1			945
UTILITIES				LS	İ		(81)
PAVEMENTS				LS	,		(135)
SITE IMPROVEME	nts			LS		į	(24)
DEMOLITION				SM	1,324	104	(138)
ASBESTOS/LEAD	PAINT RE	MOVAL		SM	1,324	125	(166)
COMMUNICATION	System (C4)		IS	1	j	(297)
MODULAR FACILI	TY (5,00	0 SF)		SM	46	5 225	(105)
SUBTOTAL						Ì	6,146
CONTINGENCY (5.0 %)				1		ļ	307
TOTAL CONTRACT	COST						6,453
SUPERVISION, IN	SPECTION	AND OVERHEAD (5.7 8	5)			368
TOTAL REQUEST				- 1			6,821
TOTAL REQUEST (ROUNDED)						6,800
EQUIPMENT FROM	OTHER AP	PROPRIATIONS (NON-ADD)				(447.0)

10. Description of Proposed Construction: Reinforced concrete foundation and floor slab, split faced reinforced concrete block exterior walls, steel frame and sloping metal roof. Functional areas include administration, operations, training, fabrication shops, storage and security measures. Includes utilities, parking, demolition of two buildings (1324 SM), lease of a modular facility and all necessary support. Force protection includes reinforced exterior walls and fully laminated windows.

Air Conditioning: 60 Tons

11. REQUIREMENT: 2,260 SM ADEQUATE: 0 SM SUBSTANDARD: 852 SM

PROJECT: Construct 25th Information Operations Squadron Facility (Current Mission).

REQUIREMENT: The 25th Information Operations Squadron (25 IOS) has a 2,260 SM (24,330 SF) space requirement for 102 personnel that includes a command section, administrative space, one mission floor, a flightline maintenenace shop, aircrew life support section, multiple training and language labs, engineering and equipment fabrication shops, material and equipment storage, and Sensitive Compartmented Information (SCI) workspace in support of classified missions and Electronic Systems Security Assessments (ESSA). A consolidated facility is needed to provide greater efficiency of operations for the 25 IOS threat assessment mission in support of the Air Intelligence Agency (AIA), the 16th Special Operations Wing (SOW), and the HQ Air Force Special Operations Command (AFSOC). Force protection will comply with minimum DoD standards.

1. COMPONENT	FY 2007 MILITARY CONSTRUCTION PROJECT DATA				2. DATE	
AIR FORCE		(comp	ıter gei	nerated)		
3. INSTALLATION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELI	HURLBURT FIELD, FLORIDA 25 INFORMATION OPERATIONS SE				QUADRON	
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
27596	141-456 FTEV013021 6,80			00		

CURRENT SITUATION: The 25 IOS has various functions spread throughout three separated facilities. According to the 2004 Infrastructure and Facilities Assessment Team visit, all 25 IOS occupied facilities are degraded. A 2001 HQ AFCEE space design study determined a 1,265 SM (13,606 SF) deficit by FY03. In addition, the 25 IOS currently has a 787 SM (8,463 SF) office space deficit which only allots 28% of the space needed for normal operations, as well as the majority of the work areas having 80% less than the required standard per AFH 32-1084. This shortage of space coupled with the physical separation of the three facilities drastically hampers operational efficiency and impacts day-to-day mission completion. This mission provides combat aircrew defense to all combat aircraft in the AFSOC inventory by integrating all source intelligence, electronic combat and electronic security for Special Operations Forces (SOF).

IMPACT IF NOT PROVIDED: Increase in mission combat hours, storage requirements, and personnel have far exceeded the space availability in the existing facilities. Failure

personnel have far exceeded the space availability in the existing facilities. Failure to provide the 25 IOS a consolidated facility will continue to degrade its ability to provide, maintain and sustain support to combat aircraft, and will also increase maintenance costs for degraded and separated facilities. This scenario will result in inadequate mission, training and intelligence support to the Air Force, AFSOC, ACC, AIA, National Security Agency and deployed locations worldwide.

ADDITIONAL: This project meets the criteria/scope of Air Force Handbook 32-1084, "Facility Requirements". A preliminary analysis of reasonable options for accomplishing the project (status quo, renovation, upgrade/removal, new construction) was done. It indicates there is only one option that will meet the mission requirements. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF; Phone 850-884-7701. (AIO Operations: 2,260 SM = 24,330 SF)

JOINT USE CERTIFICATION: Mission requirements, operational considerations and location are incompatible with use by other components.

1. COMPONENT AIR FORCE	FY 2007 MILITARY CONSTRUCTION PROJECT DATA (computer generated)					
3. INSTALLATION AND HURLBURT FIELD, FLOR	TLE N OPERATIONS SQUADRON					
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000) 27596 141-456 FTEV013021 6,800						

12. SUPPLEMENTAL DATA:

- a. Estimated Design Data:
 - (1) Status:
 - (a) Date Design Started
 - (b) Parametric Cost Estimates used to develop costs

YES

- * (c) Percent Complete as of 01 JAN 2006
- * (d) Date 35% Designed
 - (e) Date Design Complete
 - (f) Energy Study/Life-Cycle analysis was/will be performed

NO

- (2) Basis:
 - (a) Standard or Definitive Design -
 - (b) Where Design Was Most Recently Used -

(3) Total Cost (c) = (a) + (b) or (d) + (e):

(\$000) O

(a) Production of Plans and Specifications(b) All Other Design Costs

0

Ю

(c) Total

0

(d) Contract (e) In-house 0

...

- (4) Construction Contract Award
- (5) Construction Start
- (6) Construction Completion
- * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability.
- b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
NETWORK EQUIPMENT	3400	2009	142
PREWIRED WORKSTATIONS	3400	2009	305

							T	
1. COMPONENT		FY 2006 MILITARY CO				DATA	2. DATE	
AIR FORCE	·	(compute	er ge	nera	ited)			
3. INSTALLATI	ON AND LO	CATION			4. PROJECT TITLE			
HURLBURT FIEL	D, FLORID	A			CONSOLIDATE	D CLUB		
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7.	PROJECT NUMBER 8. PROJECT C			COST (\$000)	
NAF		740-615		FTI	EV015007		7,915	
		9. COST	ESTI	MATE	s			
		ITEM		U/M	QUANTITY	UNIT	COST	
CONSOLIDATED CL	UB				İ		5,694	
CONSOLIDATED (CLUB (23,41	7 SF)		SM	2,176	2,591	(5,638)	
ANTITERRORISM,	FORCE PROT	ECTION		LS	Į.		(56)	
SUPPORTING FACI	LITIES						1,452	
UTILITIES				LS	1		(465)	
PAVEMENTS				LS		}	(581)	
SITE IMPROVEM	ents			LS		Ì	(290)	
COMM				LS	ļ		(116)	
SUBTOTAL						ļ	7,146	
CONTINGENCY	(4.7 %)				1]	336	
TOTAL CONTRACT	COST						7,482	
SUPERVISION, IN	SPECTION A	ND OVERHEAD (5	.7 %)		1		426	
TOTAL REQUEST						}	7,908	
TOTAL REQUEST	(ROUNDED)				1	1	7,915	
UNFUNDED DESIG	3						(254)	
UNFUNDED FFEE						}	(513)	
OTHER APPROPRIATION (NON-ADD)							(115)	
EQUIPMENT FROM	OTHER APPR	ROPRIATIONS (NON-ADD)			L		(223)	

10. Description of Proposed Work: Concrete foundation and floor slab, masonry walls, steel structure and sloped metal roof. Functional areas will include kitchen, dining rooms, lounges and ballrooms, bathrooms and office areas. Includes utilities, landscaping, equipment and all other necessary support. Force protection includes structural reinforcement of exterior walls and fully tempered insulated glass windows. Air Conditioning: 200 Tons

11. REQUIREMENT: 4,179 SM ADEQUATE: 2,039 SM SUBSTANDARD: 1,874 SM

PROJECT: Construct Consolidated Club.

REQUIREMENT: This project is required to improve the operation of the existing consolidated NCO/Officer's Club by replacing it with a new, more functionally efficient consolidated club facility. This can be best accomplished by constructing a new consolidated open mess for all military personnel, dependent spouses and retirees ideally located on Santa Rosa Sound. This facility will be used for combined official functions including shared dining and lounge facility operations. An efficient consolidated facility will allow large group functions to be held on base rather than leasing space off base, which cost approximately \$500,000 per year. Force protection measures will be incorporated IAW Installation Force Protection Guide.

<u>CURRENT SITUATION:</u> The two existing open messes are located 3/4 of a mile apart.

Neither one is large enough to handle the necessary military functions. There are no eating facilities on base to adequately serve transient personnel that come to Hurlburt

1. COMPONENT		DATA	2. DATE				
AIR FORCE	(computer generated)						
3. INSTALLATIO	LATION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELI	, FLORIDA	A		CONSOLIDATE	CLUB	_	
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT C		8. PROJECT CO	OST (\$000)	
NAF		740-615	FTEV015007			915	

Field. There are an estimated number of 18,000 persons per year that cannot be accommodated at special functions due to limited space in both clubs. The existing consolidated club does not have a dining room large enough to handle necessary military functions. The age, number of past additions/alteration, and needed repairs to the existing facility, along with the existing configuration of the consolidated club does not make it economically feasible to renovate or add square footage to the existing footprint to gain the necessary space.

IMPACT IF NOT PROVIDED: The Hurlburt Field club system will continue to operate inefficiently due to lack of space and substandard facilities for hosting joint activities. The cost of operating will increase without added benefits to the club members. Revenue will continue to be lost because large functions are not being booked and programs are not held or limited in scope.

<u>ADDITIONAL:</u> The demolition of one facility, Bldg 90910 shall be accomplished by the companion O&M project FTEV 001123A, Demolish Collocated Club, \$115K.

A Project Validation Analysis has been prepared comparing alternatives for new construction, revitalization, leasing and status quo operations. Based on the present values and benefits of the respective alternative, new construction was found to be cost effective over the life of the project.

Key Milestones: Design Start - 24 Jun 04; 65% Design - 1 Jul 05; 100% Design - Sep 05; Award - Mar 06; Construction Complete - Sep 07

I have reviewed this document and certify it is complete and accurate. I have validated the project's primary classification. It has been coordinated with the user and other appropriate agencies and approved by the Installation Commander.

WILLIAM A. KOLAKOWSKI, Lt Col, USAF Base Civil Engineer (850) 884-7701

					DRAFT	r 1
1. COMPONENT	FY 2010 MILITARY CO	NSTI	RUCT	ON PROJECT 1	DATA	2. DATE
AIR FORCE	(compute	er ge	enera	ited)		1
3. INSTALLATION AND	LOCATION			4. PROJECT T	TITLE	
HURLBURT FIELD, FLOR	IDA		CONST OUTDOOR RECREATION CENTER, 16			
			svs			
5. PROGRAM ELEMENT	AM ELEMENT 6. CATEGORY CODE 7.			ECT NUMBER	COST (\$000) EIC 529	
27576	740-672		FT	V021001		0
	9. COST	EST	MATE	S		
	ITEM		U/M	QUANTITY	UNIT	COST
PRIMARY FACILITIES						1
MWR SUP/NAF C-STOR	\		SM	1	1,000	(1)
SUPPORTING FACILITIES			1			0
SUBTOTAL				1		1
TOTAL CONTRACT COST		8)	1			1
TOTAL5 REQUEST						1
TOTAL REQUEST (ROUNDED)				ļ		0
NAF Variable						(0)
10. Description of	Proposed Work:					
11. REQUIREMENT: 0	ADEQUATE: 0 S	UBSI	ANDA	RD: 0		
space for Equipment portable equipment	DED: To provide offic Checkout and Paintbal such as gas and charco ng bags, coolers, cano	1. al c	Outs rill	ide storage s. Inside s	are is need	led to store

	•	

									
1. COMPONENT	F	Y 2008 MILITARY	CONSTRU	CTION	PROJECT	DATA	2. DATE		
AIR FORCE		(comp	ıter ger	erate	ed)				
3. INSTALLATION	AND LOCAT	TION		4. PI	OJECT TI	rle -			
HURLBURT FIELD,	FLORIDA		1	RED I	IORSE MOB	ILITY AND TR	AINING		
				FACII	LITY (823	RHS)	Į		
5. PROGRAM ELEME	ENT 6.	CATEGORY CODE	7. PRO	PROJECT NUMBER 8. PROJECT COST (\$000)					
27596	1	171-621	FI	EV023	005	. 2	,050		
	9. COST ESTIMATES								
				T		UNIT	COST		
	IT	TEM	, ,	U/M	QUANTITY	<u> </u>			
RED HORSE MOBILITY	E TRAININ	G FACILITY			j		1,432		
TECHNICAL TRAININ	NG CLASSRO	OM:		SM	1,000	1,422	(1,422)		
FORCE PROTECTION				LS			(10)		
SUPPORTING FACILIT	PIES			1	1		394		
UTILITIES				LS	İ	1	(94)		
PAVEMENTS				LS			(135)		
SITE IMPROVEMENTS	s			LS		1	(24)		
DEMOLITION				SM	613	104	(64)		
ASBESTOS ABATEME	NT			SM	613	125	(77)		
SUBTOTAL.				Ì	1	ļ	1,826		
CONTINGENCY	(5.0 %)					1	91		
TOTAL CONTRACT COS	S T			1	1		1,917		
SUPERVISION, INSPE	ECTION AND	OVERHEAD (5.7 %)			ļ	109		
TOTAL REQUEST							2,026		
TOTAL REQUEST (ROL	UNDED)				1		2,050		
EQUIPMENT FROM OTH	HER APPROP	RIATIONS (NON-ADD))				(225.0)		

10. Description of Proposed Construction: Concrete foundation and floor slab, steel structure, masonry walls, and sloping metal roof. Functional areas include a multipurpose classroom, presentation area, conference room, physical training area, and breakroom. Force protection includes structural reinforcement of exterior walls and fully tempered insulated glass windows. Includes all utilities, demolition of a 613 SM facility, and all other necessary support.

Air Conditioning: 27 Tons

11. REQUIREMENT: 1,000 SM ADEQUATE: 0 SM SUBSTANDARD: 613 SM

PROJECT: RED HORSE Mobility and Training Facility (823 RHS) (Current Mission).

REQUIREMENT: Project is required to provide a multipurpose indoor training facility to conduct SORTS reportable and other necessary readiness and professional training for over 400 squadron personnel. This facility is essential to the RED HORSE mobility mission, which mandates unit members are able to deploy on a 12-hour notice. Troops will be assembled here for recalls, bag inspections, predeparture briefings, and other mobility activities. The facility is also needed to support the squadron fitness program and for use as a hurricane shelter for base recovery teams. To support this use, showers and lockers will be provided in the restrooms. One facility, Building 91105, for a total of 613 SM, will be demolished with this project. Force protection measures will be incorporated IAW USAF Installation Force Protection Guide.

CURRENT SITUATION: The existing wood-sided facility (613 SM) was constructed in 1974 as a temporary facility and is no longer adequate to suit the mission. It will be demolished as part of this project. The ACC Commander described this facility as among

1. COMPONENT AIR FORCE	FY 2008 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)						
3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
HURLBURT FIELD	BILITY AND TRAINING 3 RHS)						
5. PROGRAM ELE	MENT 6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)				
27596	171-621	FTEV023005	2,050				

the worst in the Air Force. The building is not large enough to provide training and deployment operations for a 400-person squadron. Over 25 percent of unit personnel must stand along the walls or outside the doors during mass briefings and other large gatherings. The facility does not meet current fire safety codes, ADA standards, or Air Force design criteria. The HVAC and lighting are insufficient, and the plumbing needs to be replaced. The roof leaks near the entrances, and all the doors are deteriorated and need to be replaced. There are no other facilities that can be used or converted for this function.

IMPACT IF NOT PROVIDED: Without this project, RED HORSE personnel will continue to be cramped into a leaky, poorly lit facility with inadequate heat or air conditioning. The building will continue to be excessively hot in the summer and cold in the winter. Inadequate facility size will continue to force over 100 students to stand during training and deployment briefings. Training effectiveness will continue to suffer, as students are unable to hear, see, or concentrate on the instructor due to these adverse learning conditions. All of these factors combined will result in reduced readiness and jeopardize critical mission response times.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements". All known alternative options were considered during the development of this project. No other option could meet the mission requirements; therefore, no economic analysis was needed or performed. Base Civil Engineer: Lt Col William A. Kolakowski, Phone 850/884-7701. (RED HORSE Mobility and Training Facility: 1,000 SM = 10,760 SF)

JOINT USE CERTIFICATION: This facility can be used by other components on an as available basis; however, the scope of the project is based on Air Force requirements.

1. COMPONENT FY 2008 MILITARY CONSTRUCTION PROJECT DATA 2. DATE AIR FORCE (computer generated)								
3. INSTALLATIO	N AND LOCATION		4. PR	DECT TITLE				
HURLBURT FIELD	, FLORIDA			ORSE MOBILITY (823 RH		LINING		
5. PROGRAM ELE	ment 6. categ	ORY CODE 7.	PROJECT N	MBER 8. P	ROJECT CO	ST (\$000)		
27596	171-	-621	FTEV0230	FTEV023005 2,050				
12. SUPPLEMENT	FAL DATA:							
a. Estimated	i Design Data:							
(1) Status	• •							
	te Design Started rametric Cost Esti	mates used t	o develop o	osts	15	-APR-06		
	rcent Complete as		-	_		100%		
	te 35% Designed					-OCT-06		
	te Design Complete			_	-	-OCT-07		
(I) En	ergy Study/Life-Cy	cie analysis	was/will i	e periorme	1	NO		
(2) Basis	: andard or Definiti	Dooles				NO		
	andard of Definiti ere Design Was Mos	_	ised -			NO		
(3) Total	Cost (c) = (a) +	(b) or (d) +	(e):			(\$000)		
	oduction of Plans	-	ations			106		
= =	1 Other Design Cos	ts				52		
(c) To	otal ontract					158		
	n-house					120 38		
(4) Const	ruction Contract A	ward						
(5) Const	ruction Start					08 JAN		
(6) Const	ruction Completion	ı						
b. Equipmen	at associated with	this project	provided	from other a	appropriat	cions:		
equiemen	T NOMENCLATURE		CURING OPRIATION	FISCAL YE APPROPRIA OR REQUES	TED	COST (\$000)		

			1
			1
			I
			I
			I
			I
			1
			1
			i
			I
			1

DRAFT 1

		FY 2009 MILIT	ARY CONS	TRUCTION	PROJECT	DATA	2. DATE
AIR FORCE		(c	computer	generate	d)		
3. INSTALLATIO	N AND LOC	ation		4. PF	OJECT TIT	LE	
HURLBURT FIELD), FLORIDA			RELOC	ATE OUTDO	OR TRAINING	AREA (RHS)
5. PROGRAM ELE	MENT	6. CATEGORY CO	DDE 7. 1	PROJECT 1	IUMBER	8. PROJECT	COST (\$000)
		179-371	1	FTEV023	007		90
		9.	COST E	STIMATES			
						UNIT	COST
		CTPRM		U/M	QUANTITY	 	
RIMARY FACILITI	nes			j			73
TNG AID				SM	1	73,404	(73
SUPPORTING FACIL	LITIES						15
UTILITIES				LS	ŀ		(5
PAVEMENTS				LS	l		(5
SITE IMPROVEME	NTS			LS			(5
SUBTOTAL				ł			88
TOTAL CONTRACT (1		88
SUPERVISION, IN	SPECTION AN	D OVERHEAD	(6.5	*)	1		94
rotal request Potal request ()	DOIMINE'''						94
		posed Constru			L	<u> </u>	
	٠						
	٠						

					DRAFT 1	
1. COMPONENT		FY 2009 MILITARY CO			DATA	2. DATE
AIR FORCE		(compute	er gene	rated)		
3. INSTALLATIO	N AND LO	CATION		4. PROJECT T	TITLE	
HURLBURT FIELD	, FLORII	DA .		RELOCATE OUT	TOOOR TRAINING	AREA (RHS)
5. PROGRAM ELL	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
		179-371	FT	EV023007		90
12. SUPPLEMENT	TAL DATA	:				
a. Estimate	d Design	Data:				
(1) Statu	s:					
(a) Da	te Desig	n Started				
(b) Pa	rametric	Cost Estimates used	d to de	velop costs		YES
· •		omplete as of 01 JAN	2008			
* (d) Da		-				
		yn Complete udy/Life-Cycle analy:	sis was	/will be perf	ormed	NO
				, <u>F</u>		
(2) Basis		- Al III - :				
• •		or Definitive Design ign Was Most Recentl		-		NO
(3) Total	Cost (c	c) = (a) + (b) or (d)) + (e)	•		(\$000)
	_	n of Plans and Speci				0
(b) A	l Other	Design Costs				0
(c) To	tal					0
	ontract					0
. ,	n-house					0
(4) Const	ruction	Contract Award				
(5) Const	ruction	Start				
(6) Const	ruction	Completion				
which :	is compa	letion of Project De rable to traditional tability.				
b. Equipmen	nt assoc	iated with this proj	ect pro	wided from o	ther appropria	tions:
·					· ·	
1						
<u> </u>						
1						
1						

							1	
1. COMPONENT		FY 2008 MILITARY	CONSTRU	CTION	PROJECT	DATA	2. DATE	
AIR FORCE		(compr	ter ger	erate	d)			
3. INSTALLATIO	N AND L	OCATION		4. PF	OJECT TI	TLB		
HURLBURT FIELD, FLORIDA					o visiti	NG QUARTERS		
5. PROGRAM ELI	EMENT	6. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT CO			COST (\$000)		
27596		724-417	FT	EV023	010	2	,800	
9. COST ESTIMATES								
	TTEM					UNIT	COST	
ADD TO VISITING ADDITION (24 R ANTITERRORISM : SUPPORTING FACE:	DOMS) FORCE PRO			SM SM	1,060 1,060	1 -,	1,924 (1,908) (16) 620	
UTILITIES				rs			(250)	
PAVEMENTS	····			LS		}	(200)	
SITE IMPROVEME				LS			(150)	
SUBTOTAL				1			2,544	
CONTINGENCY	(5.0	%)		ļ			127	
TOTAL CONTRACT	COST						2,671	
SUPERVISION, IN	SPECTION	AND OVERHEAD (5.7 %)		}		152	
TOTAL REQUEST					}	}	2,823	
TOTAL REQUEST (ROUNDED)					1	2,800	
EQUIPMENT FROM	OTHER AP	PROPRIATIONS (NON-ADD))			1	(132)	

10. Description of Proposed Construction: Concrete foundation and floor slab, masonry walls and sloped metal roof. Rooms to have combination living/bedroom with bath and support space for housekeeping equipment and storage. Includes utilities, parking and all other necessary support. Comply with DOD force protection requirements per unified facilities criteria.

Air Conditioning: 29 Tons

11. REQUIREMENT: 320 RM ADEQUATE: 133 RM SUBSTANDARD: 108 RM

PROJECT: Construct an addition to Visiting Quarters. (Current Mission).

REQUIREMENT: This project is required to provide adequate living quarters to accommodate transient personnel at Hurlburt Field. HQ AFSOC is located at Hurlburt Field drawing large numbers of officers, NCO's and civilian visitors to the installation. Additionally, the installation is home for the 16th Special Operations Wing, the Air Force Command and Control and Innovation Group (AFC2TIG) and the Special Operations School that conduct numerous training exercises and host numerous mission rehearsals. These activities produce a demand of 355 rooms per day. A Needs Assessment Study completed in August 2003 determined that the requirement for on-base visiting quarters (VQ) is 320 rooms per day (90% of demand). This project will reduce the requirement by adding 24 rooms to Building 90502 which was originally configured to support an addition of this size.

CURRENT SITUATION: Hurlburt Field has a shortage of 187 adequate rooms to accommodate visiting officers and non-commissioned officers. Since 1998, the occupancy rate has consistently been 93%. During peak periods, the lack of adequate on-base quarters forces approximately 150 persons per night to find lodging off-base. The availability and cost of off-base quarters fluctuates dramatically because of the local tourist based

1. COMPONENT		DATA	2. DATE				
AIR FORCE		(computer generated)					
3. INSTALLATION	ION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELD	, FLORII	D A		ADD TO VISIT	ING QUARTERS		
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)	
27596		724-417	FTEV023010 2,			00	

economy. On average, the cost for the base to support personnel in off-base contract quarters exceeds \$1 million per year. Personnel deferred to contract quarters are forced to drive between 10-30 miles from the base. Depending on traffic conditions, travel time from these locations can take between 20-45 minutes.

IMPACT IF NOT PROVIDED: Transient personnel will continue to be housed off-base at a cost exceeding \$1 million per year. Forced use of off-base quarters will have an adverse affect on training and mission rehearsal activities and will degrade morale, productivity and career satisfaction of transient personnel.

<u>ADDITIONAL:</u> This project meets the criteria/scope specified in and Air Force Handbook 32-1084, "Facility Requirements". A preliminary analysis of reasonable options (status quo, leasing, new construction) indicates there is only one option that will effectively meet the operational, statutory, and security criteria of functions required.

Consequently, a full economic analysis was not performed. A Certificate of exception has been prepared. Base Civil Engineer: Lt Col William A. Kolakowski, Phone 850-884-7701. 1,060SM = 11,400SF.

JOINT USE CERTIFICATION: This facility can be used by other components on an "as available " basis; however, the scope of the project is based on Air Force requirements.

. COMPONENT		FY 2008 MILITARY C	ONSTRUCTION PR er generated)	OJECT DATA	2.	DATE
3. INSTALLATIO	א מוח זכ		— - 	CT TITLE		
HURLBURT FIEL			1	VISITING QUARTER	RS	
	<u> </u>		T			
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PROJECT NU		CT COST ((\$000)
27596		724-417	FTEV02301	.0	2,800	
12. SUPPLEMEN	TAL DATA	:				
a. Estimate	d Design	Data:				
(1) Proje	ct to be	accomplished by des	sign-build pro	cedures		
• •	tandard o	or Definitive Design				NO
		ign Costs	-4			66
(4) Const	ruction	Contract Award			07	DEC
						_
(5) Const	ruction	Start			08	JAN
• -		Start Completion				JAN DEC
(6) Const	ruction y Study/		-		08	DEC YES
(6) Const	ruction y Study/ nt associ	Completion Life-Cycle analysis Lated with this proj	-		08	DEC YES s: COST
(6) Const (7) Energ b. Equipmen	ruction y Study/ nt associ	Completion Life-Cycle analysis Lated with this proj	ect provided i	FISCAL YEAR APPROPRIATED	08	DEC YES s:

	•		
			ı
			1 1
			,
			1 1
			1 1 1
			1 1
			1 1 1
			4
			1 1 1
			T.
			i 1
			1

		····					
1. COMPONENT		FY 2007 MILITARY				DATA	2. DATE
AIR FORCE		(Comb	uter ger	erate	ed)		
3. INSTALLATIO	N AND LO	CATION	ł	4. PF	ROJECT TI	TLE	
HURLBURT FIELD	, FLORID	A.		MISSI	ON PLANN	ING FACILITY	
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)
27596		610-284	FT	EV 023	011	7	,800
		9. cos	T ESTI	MATES			
		ITEM ·		U/M	QUANTITY	UNIT	COST
MISSION PLANNING	FACILITY	•			}		4,369
MISSION PLANNIN	NG FACILIT	TY		SM	2,230	1,950	(4,349)
ANTITERRORISM/I	FORCE PROT	TECTION		SM	2,230	9	(20)
SUPPORTING FACIL	LITIES			1		\	2,650
PAVEMENTS				LS		1	(650)
SITE IMPROVEMEN	NTS			LS	}		(450)
UTILITIES				LS			(1,400)
COMMUNICATION		4		IS			(150)
SUBTOTAL							7,019
CONTINGENCY	(5.0 %	b)		1]		351
TOTAL CONTRACT	COST						7,369
SUPERVISION, IN	SPECTION A	AND OVERHEAD	(5.7 %)				420
TOTAL REQUEST						1	7,790
TOTAL REQUEST (ROUNDED)					1	7,800
EQUIPMENT FROM	OTHER APP	ROPRIATIONS (NON-ADD))	1	ł		{ 1,100

10. Description of Proposed Construction: Reinforced concrete slab and foundation, structural steel framing, exterior load-bearing masonry walls and masonry veneer, light gauge metal interior framing and sloped standing seam metal roofing. Functional areas include an Auditorium, Senior Meeting Room, Briefing/Conference Rooms, a Pre-function lobby area, distinguished visitor lobby, D/V breakroom, audio/visual support, administrative areas, restrooms, mechanical, electrical and storage spaces also included. Includes utilities, pavements, site improvements and all other support. Comply with DoD force protection requirements per unified facilities criteria.

Air Conditioning: 60 Tons

11. REQUIREMENT: 14,878 SM ADEQUATE: 12,648 SM SUBSTANDARD: 177 SM

PROJECT: Mission Planning Center. (Current Mission)

REQUIREMENT: An adequate facility is required to host up to 600 USAF, AFSOC, USSOCOM and Joint Unit personnel in a single auditorium for high-level classified and unclassified meetings and briefings. Provide four (4) additional 50-person briefing rooms; the facility will host concurrent meetings and briefings. Provisions for hosting Distinguished Visitors and a 90-person capacity Senior Meeting Room are required. Force protection will comply with minimum DoD standards.

CURRENT SITUATION: Currently, Hurlburt Field has no single facility to accommodate large numbers of Air Force, AFSOC, USSOCOM and Joint Unit personnel for high-level classified and unclassified planning meetings and briefings. AFSOC must compete within the private sector market and economy to locate, schedule and lease large-capacity meeting facilities in the local metropolitan Ft. Walton Beach / Destin area. Locally available off-base facilities, which may be unavailable at critical times, cannot routinely provide adequate (secure) meeting facilities for sensitive classified

1. COMPONENT						2. DATE
AIR FORCE		(computer generated)				
3. INSTALLATION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELD	, FLORIDA	L		MISSION PLANS	ING FACILITY	
5. PROGRAM ELE	EMENT	6. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT CO			ST (\$000)
27596		610-284 FTEV023011 7,800				

briefings and meetings. These venues also do not provide adequate Force Protection measures for military personnel attending such events. Scheduling and conducting such functions in private-sector locations becomes extremely difficult and exposes large gatherings of military personnel to unacceptable risks. Since security measures to conduct a classified briefing in an unsecured area are so involved and manpower intensive, this precludes most classified conferences from being held off base.

IMPACT IF NOT PROVIDED: AFSOC will continue to rely on the availability of private-sector facilities, and pay market rates for the use of such facilities. In situations in which secure briefings must be conducted, meetings will be cancelled or delayed until adequate meeting facilities become available.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements". A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates there is only one option that will meet operational requirements. A certificate of exception has been prepared. Base Civil Engineer: Lt Col Jeffrey L. Pitchford, Phone 850-884-7701. Mission Planning Facility: 2230 SM = 24,000 SF.

JOINT USE CERTIFICATION: This facility can be used by other components on an as available basis; however, the scope of the project is based on Air Force requirements.

COMPONENT			Y CONSTRUCTION Puter generated)		2.	DATE
3. INSTALLATIO	N AND LO			JECT TITLE		
HURLBURT FIEL			1	N PLANNING FA	CILITY	
	·					/¢000\
5. PROGRAM ELI	SMENT	6. CATEGORY CO	i		OJECT COST	(\$000)
27596		610-284	FTEV023) <u></u>	7,800	
12. SUPPLEMEN	TAL DATA:					
a. Estimate	d Design	Data:				
		accomplished by	design-build pr	ocedures		
	andard of	r Definitive Des yn Was Most Rece	_			МО
(3) All 0	ther Desi	gn Costs				390
(4) Const	ruction C	ontract Award			07	JAN
(5) Const	ruction S	tart			07	FEB
(6) Const	ruction C	completion			08	MAY
(7) Energ	y Study/I	ife-Cycle analy	sis was/will be			YES
(7) Energ	y Study/I nt associa	ife-Cycle analy		from other ap	ppropriation AR WED	YES as:
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy	roject provided	from other appropriation request	ppropriation AR WED	YES as: COST (\$000)
(7) Energ	y Study/I at associa r nomenci	ife-Cycle analy	roject provided	from other ap	ppropriation AR WED	YES as:
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy	roject provided	from other appropriation request	ppropriation AR WED	YES as: COST (\$000)
(7) Energ	y Study/I at associa r nomenci	ife-Cycle analy	roject provided	from other appropriation request	ppropriation AR WED	YES as: COST (\$000)
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy	roject provided	from other appropriation request	ppropriation AR WED	YES as: COST (\$000)
(7) Energ	y Study/I at associa r nomenci	ife-Cycle analy	roject provided	from other appropriation request	ppropriation AR WED	YES as: COST (\$000)
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy	roject provided	from other appropriation request	ppropriation AR WED	YES as: COST (\$000)
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy	roject provided	from other appropriation request	ppropriation AR WED	YES as: COST (\$000)
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy	roject provided	from other appropriation request	ppropriation AR WED	YES as: COST (\$000)
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy	PROCURING APPRO	from other appropriation request	ppropriation AR WED	YES as: COST (\$000)
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy ated with this p	PROCURING APPRO	from other appropriate or REQUEST 2008	ppropriation AR WED	YES as: COST (\$000)
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy ated with this p	PROCURING APPRO	from other appropriate or REQUEST 2008	ppropriation AR WED	YES as: COST (\$000)
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy ated with this p	PROCURING APPRO	from other appropriate or REQUEST 2008	ppropriation AR WED	YES as: COST (\$000)
(7) Energ b. Equipmen	y Study/I at associa r nomenci	ife-Cycle analy ated with this p	PROCURING APPRO	from other appropriate or REQUEST 2008	ppropriation AR WED	YES as: COST (\$000)

		A	

1. COMPONENT AIR FORCE		FY 2009 MILITARY	CONSTRU			DATA	2. DATE
			uter ger		OJECT TI		-
3. INSTALLATION	ע מאט א	OCATION		4. Pr	COECT TI	r L.E.	
HURLBURT FIELD	, FLORI	DA		ADAL	USAFSOS I	FACILITY	
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PRO				JECT 1	UMBER	8. PROJECT	COST (\$000)
-							200
27596	27596 141-454 F			EV023	013		,800
		9. cos	T ESTI	MATES			
						UNIT	COST
	-	ITEM		II/M	QUANTITY	<u> </u>	
ADAL USAF SOS FA	CILITY						1,779
ADD TO USAFSOS	FACILITY	r.		SM	1,109	1,600	(1,774
FORCE PROTECTIO	N @ 0.59	F OF STRUCTURE		LS		1	(5
SUPPORTING FACIL	ITIES				1		750
UTILITIES				ıs	į		(150)
SITE IMPROVEMEN	ITS			LS			(150
PAVEMENTS				LS]	(400)
COMMUNICATION S	System			IS		1	(50
SUBTOTAL						-	2,529

10. Description of Proposed Construction: Concrete foundation and floor slab, masonry walls and sloped metal roof. Functional areas include command suite, academic office space, secure seminar- styled classrooms, bathrooms and supplies areas. Includes utilities, parking and all other necessary support. Force protection includes structural reinforcement of exterior walls and fully insulated glass windows.

(5.7 %)

Air Conditioning: 60 Tons

(5.0 %)

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

SUPERVISION, INSPECTION AND OVERHEAD

CONTINGENCY

TOTAL REQUEST

TOTAL CONTRACT COST

TOTAL REQUEST (ROUNDED)

11. REQUIREMENT: 12,503 SM ADEQUATE: 11,394 SM SUBSTANDARD: SM

PROJECT: Construct a Joint Special Operations University/USAF Special Operations School Facility (Current Mission).

REQUIREMENT: Construct a 650 SM energy efficient, properly configured addition to the JSOU/USAFSOS building. This facility will house the command suite, academic office space and seminar-styled secure classrooms. Unforeseen demand for SOF courses and academic programs has steadily increased both JSOU and USAFSOS manning beyond that originally programmed. Additionally, the development of SOF-specific Information Operations, Command and Control, PSYOP, Space Operations and Executive and Strategic level courses has increased the need for secure, seminar-styled classrooms and secure workspaces. Requirement for this project is unforeseen and cannot wait for the next MILCON program. Force protection will comply with minimum DoD standards.

CURRENT SITUATION: The existing building is inadequate for the expanded faculty, staff and student body of the JSOU/USAFSOS programs. The initial JSOU beddown concept was to share with the already established USAFSOS program at Hurlburt Field, FL. This was a temporary solution that worked satisfactorily as the JSOU staff built to full strength. There are no facilities on base that could be improved or converted for this requirement.

126

151

2.656

2,807

2,800

(175.0)

1. COMPONENT	FY 2009 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE		(computer generated)				
3. INSTALLATION AND LOCATION 4. PROJECT TITLE HURLBURT FIELD, FLORIDA ADAL USAFSOS FACILITY						
5. PROGRAM ELE	EMENT	6. CATEGORY CODE	DE 7. PROJECT NUMBER 8. PROJECT (ST (\$000)
27596		141-454	FTEV023013 2,			00

IMPACT IF NOT PROVIDED: Lack of adequate administrative and secure academic space will adversely impact the mission of the Joint Special Operations University. JSOU will be forced to continue use of temporary building to house faculty and staff. Staff growth will be limited to space availability provided in this structure which will be exceeded on or about FYO4. Planned course expansion and SOF subject improvements, primarily for courses requiring secure SCIF classrooms, will be delayed. This shortfall in critical education availability will degrade overall SOF capability and limit its ability to adjust to new global threats and evolving USSOCOM missions supporting the Global War on Terrorism.

ADDITIONAL: This project does not meet the criteria/scope specified in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, it does meet the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." All known alternative options were considered during the development of this project. No other option could meet the mission requirement; therefore, no economic analysis was needed or performed. This project has not been identified in any previous MILCON and cannot wait for the next MILCON program because of emerging requirements. Commander, USSOCOM directed the establishment of JSOU in October 2000 with the intent of housing it in the USAFSOS facility. Rapid growth of both educational commitments and faculty size to meet mission directives was beyond that originally envisioned. Base Civil Engineer: Lt Col Jeffrey L. Pitchford, 850/884-7701.

5. PROGRAM ELEMENT 27596 141-454 141-454 141-454 57596 141-454 141-454 157596 12. SUPPLEMENTAL DATA: a. Estimated Design Data: (1) Status: (a) Date Design Started (b) Parametric Cost Estimates used to develop costs * (c) Percent Complete as of 01 JAN 2008 35% * (d) Date 35% Designed 14-JAN-07 (e) Date Design Complete (f) Energy Study/Life-Cycle analysis was/will be performed (2) Basis: (a) Standard or Definitive Design - (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Contract Award (6) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: **EXCURING** APPROPRIATED CX **EXPLORATION OR REQUESTED (5) CONSTRUCTION OF REQUESTED (6) STORATION OF REQUESTED (6) STORATION OF REQUESTED (6) STORATION OF REQUESTED (6) STORATION OF REQUESTED (6) STORATION OF REQUESTED (6) STORATION OF REQUESTED (7) STORATION OF REQUESTED (8) STORATION OF REQUESTED (9) STORATION OF REQUESTED (9) STORATION OF REQUESTED (9) STORATION OF REQUESTED (9) STORATION OF REQUESTED (1) STORATION OF REQUESTED (1) STORATION OF REQUESTE	. COMPONENT		FY 2009 MILITARY C	ONSTRUCT	ION PROJECT	DATA	2. DATE
ADAL USAFSOS FACILITY 5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 27596 141-454 FTEV023013 2,800 12. SUPPLEMENTAL DATA: a. Estimated Design Data: (1) Status: (a) Date Design Started 13-JAN-07 (b) Parametric Cost Estimates used to develop costs YES 4 (c) Percent Complete as of 01 JAN 2008 358 4 (d) Date Design Complete 25-AUG-06 (f) Energy Study/Life-Cycle analysis was/will be performed NC (2) Basis: (a) Standard or Definitive Design - NC (b) Where Design Was Most Recently Used - NC (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000) (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Completion	IR FORCE	<u> </u>	(comput	er gener	ated)	·	
5. PROGRAM ELEMENT 27596 141-454 141-454 15 FTEV023013 2,800 12. SUPPLEMENTAL DATA: a. Estimated Design Data: (1) Status: (a) Date Design Started (b) Parametric Cost Estimates used to develop costs * (c) Percent Complete as of 01 JAN 2008 358 * (d) Date 35% Designed (e) Date Design Complete (f) Energy Study/Life-Cycle analysis was/will be performed (2) Basis: (a) Standard or Definitive Design - (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award 09 JAI (5) Construction Contract Award 09 JAI (5) Construction Completion 10 FE * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: EQUIPMENT NOMENCLATURE PROCURING APPROPRIATED OR REQUESTED (5) COST (\$000) C	. Installati	ON AND LO	CATION		4. PROJECT	TITLE	
12. SUPPLEMENTAL DATA: a. Estimated Design Data: (1) Status: (a) Date Design Started (b) Parametric Cost Estimates used to develop costs * (c) Percent Complete as of 01 Jan 2008 * (d) Date 35% Designed (e) Date Design Complete (f) Energy Study/Life-Cycle analysis was/will be performed (2) Basis: (a) Standard or Definitive Design - (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award 09 Jan (5) Construction Start 09 FE * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: EQUIPMENT NOMENCLATURE PROCURING APPROPRIATION REQUIPMENT NOMENCLATURE PROCURING APPROPRIATED CX (S) (S) (S)	URLBURT FIEL	D, FLORIE	A		ADAL USAFSO	S FACILITY	
12. SUPPLEMENTAL DATA: a. Estimated Design Data: (1) Status: (a) Date Design Started (b) Parametric Cost Estimates used to develop costs * (c) Percent Complete as of 01 JAN 2008 53	5. PROGRAM EI	EMENT	6. CATEGORY CODE	7. PROJ	ECT NUMBER	8. PROJECT CO	ST (\$000)
(1) Status: (a) Date Design Started (b) Parametric Cost Estimates used to develop costs * (c) Percent Complete as of 01 JAN 2008 * (d) Date 35% Designed (e) Date Design Complete (f) Energy Study/Life-Cycle analysis was/will be performed (2) Basis: (a) Standard or Definitive Design - (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: * FISCAL YEAR APPROPRIATED COR REQUESTED (5) COR REQUESTED (6) COR REQUESTED (7) COR REQUESTED (7) COR REQUESTED (8) COR REQUESTED (9) COR REQUESTED (9) COR REQUESTED (9) COR REQUESTED (9) COR REQUESTED (9) COR REQUESTED (9) COR REQUESTED (9) COR REQUESTED (9) COR REQUESTED (9) COR REQUESTED (9) COR REQUESTED (9) COR R	27596		141-454	FTE	V023013	2,	800
(1) Status: (a) Date Design Started (b) Farametric Cost Estimates used to develop costs * (c) Percent Complete as of 01 JAN 2008 * (d) Date 35% Designed (e) Date Design Complete (f) Energy Study/Life-Cycle analysis was/will be performed (2) Basis: (a) Standard or Definitive Design - (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: **PROCURING** APPROPRIATED** CX APPROPRIATED** CX STATUS OF REQUESTED ** ISCAL YEAR APPROPRIATED CX APPROPRIATED CX APPROPRIATED CX STATUS OF REQUESTED ** ISCAL YEAR APPROPRIATED CX APPROPRIATED CX STATUS OF REQUESTED	12. SUPPLEMEN	NTAL DATA	:				
(a) Date Design Started (b) Parametric Cost Estimates used to develop costs * (c) Percent Complete as of 01 JAN 2008 * (d) Date 35% Designed (e) Date Design Complete (f) Energy Study/Life-Cycle analysis was/will be performed (2) Basis: (a) Standard or Definitive Design - (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (5) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: EQUIPMENT NOMENCIATURE PROCURING APPROPRIATION FISCAL YEAR APPROPRIATED (5) CORREQUESTED (5)	a. Estimate	ed Design	Data:				
(b) Parametric Cost Estimates used to develop costs * (c) Percent Complete as of 01 JAN 2008 35 % * (d) Date 35 % Designed 14-JAN-06 (e) Date Design Complete 25-AUG-08 (f) Energy Study/Life-Cycle analysis was/will be performed NC (2) Basis: (a) Standard or Definitive Design - NC (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000) (a) Production of Plans and Specifications (c) Total (d) Contract (e) In-house (e) In-house (f) In-house (f) Construction Contract Award (f) Construction Completion (f) Construction Completion (f) Fei Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: PROCURING APPROPRIATED (5) (5) (5) (5) (5) (6) (6) (6) (6) (6) (6) (6) (6) (6) (6	• •						
* (c) Percent Complete as of 01 JAN 2008 * (d) Date 35% Designed 14-JAN-08 (e) Date Design Complete 25-AUG-08 (f) Energy Study/Life-Cycle analysis was/will be performed NC (2) Basis: (a) Standard or Definitive Design - NC (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000) (a) Production of Plans and Specifications (c) Total (d) Contract (e) In-house (4) Construction Contract Award 09 JAN (5) Construction Start 09 FE * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: * FISCAL YEAR PROCURING APPROPRIATED COMPLETED (\$1000)		_			_	1:	3-JAN-07
* (d) Date 35% Designed (e) Date Design Complete (f) Energy Study/Life-Cycle analysis was/will be performed (2) Basis: (a) Standard or Definitive Design - (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Start (7) FE * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: PROCURING APPROPRIATED (5) CONSTRUCTION CMENCLATURE PROCURING APPROPRIATED (6) CONSTRUCTION CMENCLATURE PROCURING APPROPRIATED (5) CONSTRUCTION CMENCLATURE PROCURING APPROPRIATED (6) CONSTRUCTION CMENCLATURE (5) CONSTRUCTION CMENCLATURE PROCURING APPROPRIATED (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (6) CONSTRUCTION CMENCLATURE (7) CMENCLATURE (7) CMENCLATURE (8) CONSTRUCTION CMENCLATURE (8) CONSTRUCTION CMENCLATURE (8) CONSTRUCTION CMENCLATURE (8) CONSTRUCTION CMENCLATURE (8) CONSTRUCTION CMENCLATURE (8) CONSTRUCTION CMENCLATURE (8) CONSTRUCTION CMENCLATURE (8) CONSTRUCTION CMENCLATURE (8) CONSTRUCTION CMENCLATURE (8) CONSTRUCTION CMENCLATURE (9) JAMES CMENCLATURE (9) JAMES CMENCLATURE (9) JAMES CMENCLATURE (9) JAMES CMENCLATURE (9) JAMES CMENCLATURE (9) JAMES CMENCLATURE (9) JAMES CMENCLATURE (9) JAMES CMENCLATURE (1) CMENCLATURE (1) CMENCLATURE (1) CMENCLATURE (1) CMENC					elop costs		YES
(e) Date Design Complete (f) Energy Study/Life-Cycle analysis was/will be performed (2) Basis: (a) Standard or Definitive Design - NO (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000) (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: * PROCURING APPROPRIATED OR REQUESTED (5) CORREQUESTED * STORY YEAR APPROPRIATED OR REQUESTED (5) CORREQUESTED (6) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (7) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (8) CORREQUESTED (9) CORREQUESTED (9) CORREQUESTED (9) CORREQUESTED (9) CORREQUESTED (9) CORREQUESTED (9) CORREQUESTED (9) CORREQUESTED (9) CORREQUESTED				2008			35 %
(f) Energy Study/Life-Cycle analysis was/will be performed (2) Basis: (a) Standard or Definitive Design - (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion (7) **Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. (a) **Equipment associated with this project provided from other appropriations: **Equipment NOMENCIATURE** PROCURING APPROPRIATED (SECTION OR REQUESTED) (SECTION OF TRUE OR REQUESTED) (SECTION OR REQUESTED) (SECTION OR REQUESTED)			_				
(2) Basis: (a) Standard or Definitive Design - NO (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000) (a) Production of Plans and Specifications (c) (b) All Other Design Costs (c): Total (d): (c): Total (d): (c): Total (d): (e): Total (d):	* *	_	-	_			
(a) Standard or Definitive Design - (b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000) (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (e) In-house (f) In-house (f) Construction Contract Award (f) Jan (f) Construction Start (f) Jan (f) Fe (f) Construction Completion (f) Fe (f) Construction Completion (f) Fe (f) Construction of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: PROCURING APPROPRIATED (C) (\$600)	(f) E	nergy Stu	dy/Life-Cycle analy	sis was/	will be per:	formed	МО
(b) Where Design Was Most Recently Used - (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000) (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (e) In-house (e) In-house (f) Construction Contract Award (f) Construction Start (f) FE (f) Construction Completion (f) FE (f) Construction Construction Construction Construction (f) FE (f) Construction	,	-					
(3) Total Cost (c) = (a) + (b) or (d) + (e): (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion 10 FE * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: PROCURING APPROPRIATION FISCAL YEAR APPROPRIATED (5) CONSTRUCTION OR REQUESTED (5) CONSTRUCTION OR REQUESTED (6) CONSTRUCTION OR REQUESTED * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. * Equipment associated with this project provided from other appropriations: * FISCAL YEAR APPROPRIATION OR REQUESTED * (5) CONSTRUCTION OR REQUESTED * (5) CONSTRUCTION OR REQUESTED * (5) CONSTRUCTION OR REQUESTED * (5) CONSTRUCTION OR REQUESTED * (5) CONSTRUCTION OR REQUESTED * (6) CONSTRUCTION OR REQUESTED * (6) CONSTRUCTION OR REQUESTED * (6) CONSTRUCTION OR REQUESTED * (7) CONSTRUCTION OR REQUESTED * (7) CONSTRUCTION OR REQUESTED * (7) CONSTRUCTION OR REQUESTED * (8) CONSTRUCTION OR REQUESTED	(a) S	tandard o	r Definitive Design	· -			МО
(a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion (6) Construction Completion (6) Construction Completion (7) Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. (6) Equipment associated with this project provided from other appropriations: (6) Equipment associated with this project provided from other appropriations: (8) FISCAL YEAR APPROPRIATED (8) EQUIPMENT NOMENCLATURE (8) PROCURING APPROPRIATED (8) EQUIPMENT NOMENCLATURE (8) EQUIPMENT NOMENCLATURE (8) Equipment appropriation of Project Provided from OR REQUESTED (8) Equipment NOMENCLATURE	(b) W	here Desi	gn Was Most Recentl	y Used -	•		
(b) All Other Design Costs (c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion (6) Construction Completion (6) Construction Completion (6) Construction Completion (6) Construction Completion (7) FE * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. (6) Equipment associated with this project provided from other appropriations: PROCURING APPROPRIATED COMPLETED (SCAL YEAR APPROPRIATED (S	(3) Tota	l Cost (c	(a) = (a) + (b) or (d)	i) + (e):			(\$000)
(c) Total (d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: * FISCAL YEAR APPROPRIATED COMPARENT NOMENCLATURE PROCURING APPROPRIATED (\$6.50)	(a) P	roduction	of Plans and Speci	fication	ıs		0
(d) Contract (e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: * FISCAL YEAR PROCURING APPROPRIATED COST APPRO	(b) A	11 Other	Design Costs				0
(e) In-house (4) Construction Contract Award (5) Construction Start (6) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: * FISCAL YEAR PROCURING APPROPRIATED COST	(c) T	otal					0
(4) Construction Contract Award (5) Construction Start (6) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: * FISCAL YEAR APPROPRIATED COMPARED CONTRACTOR APPROPRIATED CONTRACTOR APPROPRIA	(d) C	Contract					0
(5) Construction Start (6) Construction Completion * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: * FISCAL YEAR APPROPRIATED COMPARED CONTROL OF REQUESTED (\$6.00)	(e) I	n-house					0
* Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: PROCURING APPROPRIATED COMPARED C	(4) Cons	truction	Contract Award				09 JAN
* Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: PROCURING APPROPRIATED COMPARED APPROPRIATED COMPARED (\$6.00)	(5) Cons	truction	Start				09 FEB
which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: FISCAL YEAR PROCURING APPROPRIATED CO	(6) Cons	struction	Completion				10 FEB
which is comparable to traditional 35% design to ensure valid scope, cost and executability. b. Equipment associated with this project provided from other appropriations: FISCAL YEAR PROCURING APPROPRIATED CO	* Indica	ites compl	letion of Project De	finitio	n with Param	etric Cost Est	imate
b. Equipment associated with this project provided from other appropriations: FISCAL YEAR PROCURING APPROPRIATED CO EQUIPMENT NOMENCLATURE APPROPRIATION OR REQUESTED (\$6		_	_				
FISCAL YEAR PROCURING APPROPRIATED CO EQUIPMENT NOMENCLATURE APPROPRIATION OR REQUESTED (\$6	cost a	ind execut	tability.				
PROCURING APPROPRIATED CO EQUIPMENT NOMENCLATURE APPROPRIATION OR REQUESTED (\$6	b. Equipme	ent assoc	iated with this pro	ject pro	vided from o	ther appropria	tions:
PROCURING APPROPRIATED CO EQUIPMENT NOMENCLATURE APPROPRIATION OR REQUESTED (\$6							
SYSTEM FURNITURE 3400 2004	equipme	NT NOMENO	LATURE A		ig appi	ROPRIATED	COST (\$000
	SYSTEM	FURNITURE		3400		2004	175
·							

1. COMPONENT		FY 2012 MILITARY				DATA	2. DATE
AIR FORCE		(combi	uter ger	erate	ed)	 	
3. INSTALLATIO	N AND L	OCATION		4. PI	ROJECT TI	TLE	
HURLBURT FIELD	, FLORI	DA		SOF-	JSOU HQ F	ACILITY	
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	TECT 1	NUMBER	8. PROJECT	COST (\$000)
		610-243	FI	EV023	014		20
· · · · · · · · · · · · · · · · · · ·		9. cos	T ESTI	MATES			
		ITEM		U/M_	QUANTITY	UNIT	COST
PRIMARY FACILITI	ES						1
HQ GROUP				SM	1	1,000	(1)
SUPPORTING FACII	ITIES			1	ļ		15
UTILITIES				LS	Ì		(5)
PAVEMENTS				LS			(5)
SITE IMPROVEME	nts			LS			(5)
SUBTOTAL				1	1		16
TOTAL CONTRACT (COST			1			16
SUPERVISION, INS	SPECTION	AND OVERHEAD (6.5 %)				1
TOTAL REQUEST							17
TOTAL REQUEST (I	ROUNDED)				<u> </u>		20
10. Descripti	on of P	roposed Constructio	n:				
11. REQUIREMENT	r:	ADEQUATE:	SUBS	TANDA	RD:	· · · · · · · · · · · · · · · · · · ·	
Ì							
ł							
					•		
}							
1							

					DRAFT 1	_
1. COMPONENT AIR FORCE	FY 2012 MILITARY CONSTRUCTION PROJECT DATA (computer generated)					2. DATE
3. INSTALLATION HURLBURT FIELD				4. PROJECT T SOF-JSOU HQ		
5. PROGRAM EL	ement	6. CATEGORY CODE 610-243		DECT NUMBER EV023014	8. PROJECT C	OST (\$000) 20
12. SUPPLEMEN		•				
(b) Pa	te Desig	n Started Cost Estimates used Amplete as of 01 JAN		velop costs		YES

- * (d) Date 35% Designed
 - (e) Date Design Complete
 - (f) Energy Study/Life-Cycle analysis was/will be performed

NO

(2) Basis:

(a) Standard or Definitive Design -

NO

- (b) Where Design Was Most Recently Used -
- (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000) (a) Production of Plans and Specifications (b) All Other Design Costs 0 (c) Total 0 (d) Contract 0 (e) In-house
- (4) Construction Contract Award
- (5) Construction Start
- (6) Construction Completion
- * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability.
- b. Equipment associated with this project provided from other appropriations:

ו יושוגסת

							<u>-</u>
1. COMPONENT FY 2012 MILITARY CONSTRUCTION PROJECT DATA 2. DATE							
AIR FORCE (computer generated)							
3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
HURLBURT FIELD, FLORIDA SOFJSOU EDU/LIBRARY TRNG CENTER							
5. PROGRAM ELEMENT		6. CATEGORY CODE 7. PRO-		JECT 1	NUMBER	8. PROJECT COST (\$000)	
		740-675	FTEV023015		20		
9. COST ESTIMATES							
		TTEM		tī/M	QUANTITY	UNIT	COST
PRIMARY FACILITI					0		
BASE LIB				SM	1	155	(0)
SUPPORTING FACILITIES							
UTILITIES				LS			(5)
PAVEMENTS				IS			(5)
SITE IMPROVEMEN	nts			rs			(5)
SUBTOTAL					Ì		15
TOTAL CONTRACT COST 15							
SUPERVISION, INSPECTION AND OVERHEAD (6.5 %)						1	1
TOTAL REQUEST							16
TOTAL REQUEST (F	ROUNDED)				<u> </u>	<u> </u>	20
10. Description of Proposed Construction:							
11. REQUIREMENT: ADEQUATE: SUBSTANDARD:							
}							
				•			
					•		

: -				•	DRAFT 1	
1. COMPONENT		FY 2012 MILITARY C	ONSTRUC'	TION PROJECT	DATA	2. DATE
AIR FORCE		(comput	er gener	rated)		
3. INSTALLATIO	ON AND LO	CATION		4. PROJECT T	TILE	•
HURLBURT FIELI	D, FLORII	DA.		SOFJSOU EDU/	LIBRARY TRNG	CENTER
5. PROGRAM ELI	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
		740-675	FT	EV023015		20
12. SUPPLEMEN	TAL DATA	:				
a. Estimate	d Design	Data:				
(1) Statu	ıs:					
• •		n Started				
(b) Pa	arametric	Cost Estimates used	d to dev	relop costs		YES
* (c) Pe	ercent Co	omplete as of 01 JAN	2011			
* (d) Da	ate 35% D	esigned				
• •	_	n Complete		_		
(f) Er	nergy Stu	dy/Life-Cycle analy:	sis was,	/will be perf	ormed	NO
(2) Basis	3:					
(a) St	tandard o	or Definitive Design	_			NO
(b) Wi	here Desi	.gn Was Most Recently	y Used ·	-		
(3) Total	L Cost (c	a(a) = (a) + (b) or (d)) + (e):	1		(\$000)
• •	-	of Plans and Speci				0
(b) A	ll Other	Design Costs				0
(c) To	otal					0
(d) Co	ontract					0
(e) I:	n-house					0
(4) Const	truction	Contract Award				
(5) Const	truction	Start				
(6) Const	truction	Completion				
* Indicat	tes compl	letion of Project De	finitio	n with Parame	etric Cost Est	imate
	_	cable to traditional				
	_	ability.				•
-		-				

1. COMPONENT AIR FORCE	FY 2006 MILITAR	Y CONSTRU			DATA	2. DATE
		bacer der				
3. INSTALLATION				ROJECT TI		
HURLBURT FIELD,	FLORIDA		WEAP	ONS INSTR	UCTOR COURSE	FACILITY
5. PROGRAM ELEME	ENT 6. CATEGORY CODE	2 7. PRO	JECT 1	TUMBER	8. PROJECT	COST (\$000)
22176	171-211	FI	EV023	016	2	,540
	9. CC	OST ESTI	MATES			
	ITEM		U/M	OUANTITY	UNIT	Cost
WEAPONS INSTRUCTOR						1,897
-	OR COURSE FACILITY		SM	1,115	1	(1,877)
antiterrorism/for	RCE PROTECTION		SM	1,115	18	(20)
SUPPORTING FACILIT	!IES				1	394
UTILITIES			LS			(200)
PAVEMENTS			LS		1	(25)
SITE IMPROVEMENT:	S		LS			(5)
ELEVATOR			EA	:	L 64,000	(64)
COMMUNICATION SUI	PPORT		LS			(100)
SUBTOTAL				ļ	}	2,291
CONTINGENCY	(5.0 %)					115
TOTAL CONTRACT COS	ST					2,405
SUPERVISION, INSPI	ECTION AND OVERHEAD	(5.7 %)	1	}		137
TOTAL REQUEST						2,542
TOTAL REQUEST (RO	UNDED)				ļ	2,540

10. Description of Proposed Construction: Concrete foundation, standing seam metal roof, split face concrete masonry wall, utilities, fire detection/protection, site improvements, pavements, landscaping, fencing, elevator, communication support, and all other necessary support. Force protection includes structural reinforcement of exterior walls and fully tempered insulated glass windows.

Air Conditioning: 250 Tons

11. REQUIREMENT: 1,115 SM ADEQUATE: 0 SM SUBSTANDARD: 0 SM

PROJECT: Construct Weapons Instructor Course (WIC) Facility. (New Mission)

REQUIREMENT: The Chief of Staff of the Air Force directed Headquarters Air Combat Command to become executive agent for the development of an Air Force Special Operations Weapons Instructor Course (AFSOC) at Hurlburt Field, Florida. The purpose of this school is to integrate all existing AFSOC-type weapon systems into a cohesive, state-of-the-art system that will modernize, streamline, and standardize all weapons command and control techniques throughout the Air Force Special Operations Command. The 16th Special Operations Wing does not possess sufficient facility space to support the efficient establishment of the school, necessitating the requirement to construct a new permanent facility.

CURRENT SITUATION: The AFSOC WIC Detachment (Det 3, United States Air Force Weapons School (USAF WS)) presently has limited personnel assigned and is initiating action to conduct condensed courses in five geographically separated, inadequately sized, and inefficiently configured areas. In FY05, the unit's strength will double and have a requirement to train approximately 25 students at any one time. The 16th Special Operations Wing has indicated that they do not have sufficient facility space to support the function. Det 3, USAF WS is developing a project to lease/purchase a modular

1. COMPONENT AIR FORCE		FY 2006 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)				
	STALLATION AND LOCATION 4. PROJECT TITLE URT FIELD, FLORIDA WEAPONS INSTRUCTOR COURSE FACILITY					ACILITY
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT COS			ST (\$000)
22176		171-211	F.	TEV023016	2,5	40

complex so they can consolidate temporarily and train as many students as possible until the MILCON project described in this document is approved, and the new permanent facility has been constructed.

IMPACT IF NOT PROVIDED: The Detachment will only be able to present the Weapons
Instructor Course to approximately 60% of the students that require the training. The
Special Operations Command will not obtain all the properly trained, experienced weapons
specialists needed to accomplish their primary mission in a timely manner. The
Detachment will not be able to satisfactorily accomplish mission requirements.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements". All known alternative options were considered during the development of this project. No other option could meet the mission requirements; therefore, no economic analysis was needed or performed. A certificate of exception has been prepared. Base Civil Engineer: Lt Col Jeffrey L. Pitchford, (850) 884-7701. (Weapons Instructor Course Facility: 1,115 SM = 11,997 SF).

JOINT USE CERTIFICATION: Mission requirements, operational considerations, and location are incompatible with use by other components.

1. COMPONENT ATR FORCE	FY 2006 MILITARY C	OMSTRUCT er gener		DATA	2. DATE
					<u> </u>
3. INSTALLATION AND LO		1	4. PROJECT T		
HURLBURT FIELD, FLORIS	DA	<u></u>	WEAPONS INST	RUCTOR COURSE	FACILITY
5. PROGRAM ELEMENT	6. CATEGORY CODE	7. PROJ	ECT NUMBER	8. PROJECT CO	ST (\$000)
22176	171-211	FTE	W023016	2,	540
12. SUPPLEMENTAL DATA	:				
a. Estimated Design	Data:				
(1) Status:					
(a) Date Desig	m Started			0:	3-MAY-04
(b) Parametric	Cost Estimates use	d to dev	elop costs		YES
• •	omplete as of 01 JAN	2005			15%
* (d) Date 35% I	-				0-AUG-04
(e) Date Desig	•			_	0-SEP-05
(f) Energy Stu	ndy/Life-Cycle analy	sis was/	will be perf	formed	YES
(2) Basis:					
	or Definitive Design				NO
(D) Where Desi	ign Was Most Recentl	y used -	•		
(3) Total Cost (c	(a) = (a) + (b) or (d)) + (e):			(\$000)
(a) Production	n of Plans and Speci	fication	ıs		150
(b) All Other	Design Costs				75
(c) Total					225
(d) Contract					188
(e) In-house					37
(4) Construction	Contract Award				05 DEC
(5) Construction	Start				06 FEB
(6) Construction	Completion			•	07 FEB
* Indicates comp	letion of Project De	finition	with Parame	etric Cost Est	imate
which is compa cost and execu	rable to traditional tability.	. 35% des	sign to ensu	re valid scope	•

b. Equipment associated with this project provided from other appropriations: N/A

	Γ						
1. COMPONENT		FY 200	6 PROJE	CT D	ATA		2. DATE
AIR FORCE	AIR FORCE (computer generated)						
3. INSTALLATI	3. INSTALLATION AND LOCATION					ITLE	
HURLBURT FIEL	HURLBURT FIELD, FLORIDA				I-CLEAR/FI	LL WETLANDS,	HELO LANDING
				AP	RON		
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PRO	JEC:	NUMBER	8. PROJECT C	OST (\$000)
22176		911-146	١ _		31049		IC 529
22176							670.3
		9. COS1	ESTI	MIES	<u> </u>	UNIT	COST
{	ITEM			U/M	QUANTITY	UNIT	COST
HELICOPTER LAND	ING APR	OM.	-				527.3
CUT/CHIP MEDI	UM TREES	TO 12" DIAMETER		AC	5	-3,560	(17.8)
GRUB STUMPS A	ND REMOV	TE .		AC	5	2,000	(10.0)
COMMON FILL,	DELIVER	AND SPREAD		CY	78,200	6	(469.2)
SEEDING				AC	12	1,100	(13.2)
COMPACT FILL				SY	15,500	1	(17.1)
SUPPORTING FACT	LITIES						2.6
SILT FENCE				LF	2,600	1	(2.6)
SUBTOTAL						\	529.9
PROFIT AND OVERHEAD (26.5 %)							140.4
TOTAL FUNDED COST						1	670.3
UNFUNDED COST	(:	10 %)					67.0
TOTAL REQUEST							737.3

- 10. Description of Proposed Work: Clear, grub, and fill approximately 12 acres of high quality forested wetlands. A 10-year permit requires that a certified project drawings signed/sealed by a PE to the Corps of Engineers at project conclusion. Project will require a state storm water permit for construction greater than one acre and require the development of a storm water pollution prevention plan to address control of sediments. Project will require inspections by a state certified storm water inspector weekly and after .5 inches of rainfall. Silt screens and other measures must be installed prior to work and maintained until final stabilization. Project must provide for final stabilization of the area with a uniform perennial vegetative cover with a density of at least 70% for all unpaved areas.
- 11. Requirement: As Required.

<u>PROJECT:</u> Clear, grub, and fill wetlands north of Helicopter Landing Apron.

<u>REQUIREMENT:</u> Due to the increased emphasis being placed on Air Force Special

Operations, the 16th Special Operations Wing may plus up the number of aircraft assigned to the Wing. In addition, the conversion to the CV-22 aircraft requires the creation of a landing lane on the east apron to maintain flight safety. This will eliminate an existing Airfield Waiver.

<u>CURRENT SITUATION:</u> Current vegetation growth is in the aircraft flight clear zone and poses risk to aircraft and pilot. Also, all upland areas around the flight line have already been used for services that require quick access to the flight line.

IMPACT IF NOT PROVIDED: The increase in aircraft to support the special operations mission may result in a need for additional hanger space, an operations facility and an expansion of the flight line parking apron. Without this area, the mission will be severely impacted.

1. COMPONENT AIR FORCE	FY 20			CTION PROJECT	DATA	2. DATE
3. INSTALLATION HURLBURT FIELD,				4. PROJECT TI VEHICLE OPERA FACILITY	TLE TIONS ADMINIST	RATION
5. PROGRAM ELEM		TEGORY CODE	1	JECT NUMBER PEV033004	8. PROJECT CO	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,

9. COST ESTIMATES UNIT COST ITEM M/II CUANTITY VEHICLE OPERATIONS ADMINISTRATION FACILITY 1,824 1,289 VEHICLE OPERATIONS ADMIN FAC (13,870 SF) 1,341 (1,729) SM ANTITERRORISM/FORCE PROTECTION (0.5%) T.S (9) SUSTAINABILITY CONSTRUCTION (5%) LS (86) SUPPORTING FACILITIES 776 UTILITIES LS (115) PAVEMENTS LS (100) SITE IMPROVEMENTS LS (100) DEMOLITION 952 106 (101) SM COMMUNICATION SYSTEM (360) SUBTOTAL 2,600 CONTINGENCY 130 TOTAL CONTRACT COST 2,730 SUPERVISION, INSPECTION AND OVERHEAD (5.7 %) 156 TOTAL REQUEST 2,885 TOTAL REQUEST (ROUNDED) 2,900 EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD) (135.0)

10. Description of Proposed Construction: Concrete foundation and floor slab, masonry walls, and sloping metal roof. Functional areas include administrative areas, customer service, conference/training room, and driver's ready room/locker room. Includes utilities, parking, demolition of six buildings for a total of 952 SM and all other support. Includes minimum DoD interim force protection standards.

Air Conditioning: 35 Tons

11. REQUIREMENT: 1,289 SM ADEQUATE: 0 SM SUBSTANDARD: 952 SM

PROJECT: Construct an Administrative and Vehicle Operations Facility (Current Mission) REQUIREMENT: This project is required to provide an adequate facility to support the 16th Special Operations Wing at Hurlburt Field. The 16th Transportation Squadron is an essential element of aircraft support. The squadron's mission is to ensure the best transportation service to their customers through worldwide passenger and cargo movement, while maintaining equipment and readiness. Force protection will comply with minimum DoD standards.

CURRENT SITUATION: The location of existing facilities does not follow a logical plan that accounts for the efficient operation of the larger transportation complex. These buildings are set at odd angles and do not relate well to adjacent facilities. Lack of a governing grid or siting guidelines has resulted in a lack of consistency. Several facilities have had piecemeal additions which interfere with the function of the paved area. Throughout the site several outdoor storage areas have given the complex a cluttered look. The clutter in some cases also interferes with the efficient use of

1. COMPONENT AIR FORCE		FY 2010 MILITARY		CTION PROJECT nerated)	DATA	2. DATE
3. INSTALLATION HURLBURT FIELD				4. PROJECT TI VEHICLE OPERA FACILITY	TLE TIONS ADMINIST	RATION
5. PROGRAM ELI	ement	MENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT CO				ST (\$000)
27596		610-121 FTEV033004 2,				00

available space. Adequate space for administrative and vehicle operations exists within the complex, however, this space is not fully utilized and not organized for maximum efficiency. These functions are spread within seven small buildings varying in age from 18 to 43 years. The squadron commander is located in a metal building, 90205, which is outside the complex and not functionally located in close proximity to the vehicle operations functions. Six buildings will be demolished as a result of this project for total of 952 SM.

IMPACT IF NOT PROVIDED: The Administrative and Vehicle Operations will continue to be housed in inadequate facilities which will affect the morale and productivity of the personnel and thereby affect the efficient support of the mission of the 16th Special Operations Wing.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Engineer: Jeffrey L. Pitchford, Lt Col, 850-884-7701. Vehicle Operations Administration Facility: 1289 SM = 13,870 SF.

JOINT USE CERTIFICATION: This facility can be used by other components on an "as available" basis; however, the scope of the project is based on Air Force requirements.

							
1. COMPONENT		FY 2010 MILIT	ary cons	TRUCT	ION PROJECT	DATA	2. DATE
AIR FORCE		(c	omputer	gener	ated)		
3. INSTALLATION	ON AND LO	OCATION		\	4. PROJECT T	TITLE	
HURLBURT FIEL	D, FLORI	DA			VEHICLE OPER FACILITY	RATIONS ADMINI	STRATION
5. PROGRAM EL	EMENT	6. CATEGORY	CODE 7.	PROJ	ect number	8. PROJECT CO	ST (\$000)
27596		610-121	l <u>`</u>	FTI	V033004	2,	900
12. SUPPLEMEN	TAL DATA	:					
a. Estimate	ed Design	Data:					
(1) Statu	ıs:						
(b) Pa * (c) Pa * (d) Da (e) D	arametric ercent Co ate 35% l ate Desig	gn Complete	1 JAN 2	2009	_		YES
(f) E	nergy St	udy/Life-Cycle	analysis	was/	will be perf	ormed	ио
1 ' '	tandard (or Definitive D ign Was Most Re	-	Jsed •	•		ио
(a) P (b) A (c) T (d) C	roductio 11 Other	c) = (a) + (b) n of Plans and Design Costs					(\$000)
(4) Cons	truction	Contract Award					
(5) Cons	truction	Start					
(6) Cons	truction	Completion					
which	is compa	letion of Proje rable to tradit tability.					
b. Equipme	ent assoc	ciated with this	projec	t pro	vided from o	ther appropria	tions:
EQUIPME	NT NOMENO	CLATURE		OCURII OPRIA	ig appr	CAL YEAR COPRIATED REQUESTED	COST (\$000)
PREWIRE	D WORKST	ations		3400		2008	135

1. COMPONENT	FY 2010 MILITARY	CONSTRUCTION PROJEC	T DATA	2. DATE
AIR FORCE	(comp	uter generated)		
3. INSTALLATION AND	LOCATION	4. PROJECT T	ITLE	
HURLBURT FIELD, FLO	RIDA	VISITING OFF	TICERS QUARTERS	
5. PROGRAM ELEMENT	6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT C	OST (\$000)
27596	724-417	FTEV033006	4,	100
	9. cos	T ESTIMATES		
				000m

9. COST ESTI	MATES			
TTEM	П/М	QUANTITY	UNIT	COST
VISITING OFFICER QUARTERS (40 PM)				3,080
VOQ (21,000 SF)	SM	1,950	1,497	(2,919)
ANTITERRORISM/FORCE PROTECTION (0.5%)	LS	}	-	(15)
SUSTAINABILITY (5.0%)	LS	ļļ	1	(146)
SUPPORTING FACILITIES	}			636
UTILITIES	LS	1	1	(195)
PAVEMENTS	LS		į	(212)
SITE IMPROVEMENTS	LS)	(201)
COMMUNICATION SYSTEM	LS	1		(28)
SUBTOTAL				3,716
CONTINGENCY (5.0 %)	ł	1 1		186
TOTAL CONTRACT COST	-		ľ	3,901
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %)				222
TOTAL REQUEST		1		4,124
TOTAL REQUEST (ROUNDED)]	4,100
EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)				(220)

10. Description of Proposed Construction: Concrete foundation and floor slab, masonry walls and sloped metal roof. Rooms to have combination living/bedroom with bath and support space for housekeeping equipment and storage. Includes utilities, parking and all other necessary support. Includes minimum DoD interim force protection standards.

Air Conditioning: 48 Tons

11. REQUIREMENT: 320 PN ADEQUATE: 277 PN SUBSTANDARD: 108 PN

PROJECT: Construct Visiting Quarters (Current Mission).

REQUIREMENT: This project is required to provide adequate living quarters to accommodate TDY personnel at Hurlburt Field. HQ AFSOC is located at Hurlburt Field drawing large numbers of officers, NCO's and civilian visitors to the installation. Additionally, the installation is home for the 16th Special Operations Wing, the Air Force Command and Control and Innovation Group (AFC2TIG) and the Special Operations School that conduct numerous training exercises and host numerous mission rehearsals. These schools and mission rehearsals bring a tremendous volume of transient personnel to the installation, generating a significant demand for temporary quarters. Force protection measures will comply with minimum DoD standards.

CURRENT SITUATION: Hurlburt Field has a severe shortage of adequate transient quarters available to accommodate visiting officers and non-commissioned officers. The lack of adequate on-base quarters forces transient personnel to find lodging off base. The availability and cost of off-base quarters fluctuates dramatically because of the local tourist based economy. During the tourist season adequate off-base quarters, at reasonable prices, are difficult or impossible to find within reasonable travel distance. The problem is further compounded by the increasing AFSOC air crew training

1. COMPONENT	FY 2010 MILITARY	DATA 2. DATE				
AIR FORCE	(computer generated)					
3. INSTALLATIO	ON AND LOCATION 4. PROJECT TITLE					
HURLBURT FIELD), FLORIDA	VISITING OFFI	CERS QUARTERS			
5. PROGRAM ELE	MENT 6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)			
27596	724-417	FTEV033006 4,100				

requirements as new weapons systems are received.

IMPACT IF NOT PROVIDED: Large numbers of transient personnel, averaging 156 per night, will continue to be housed off-base, at a cost exceeding \$1 million per year for contract quarters. Forced use of off-base quarters will have an adverse affect on training and mission rehearsal activities and will degrade morale, productivity and career satisfaction of transient personnel.

ADDITIONAL: This project does meet the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements". A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates there is only one option that will meet operational requirements. A certificate of exception has been prepared.

Base Civil Engineer: Lt Col Jeffrey L. Pitchford, Phone 850-884-7701. Visiting Officers Quarters: 1950 SM = 21,000SF.

JOINT USE CERTIFICATION: This facility can be used by other components on an "as available" basis; however, the scope of the project is based on Air Force requirements.

						(
1. COMPONENT AIR FORCE		FY 2010 MILITARY Compute	ONSTRUCTION PR er generated)	ROJECT DATA	1	2. DATE			
3. INSTALLATIO	AI DNA NO	CATION	4 PROJ	ECT TITLE					
HURLBURT FIEL			l l	G OFFICERS	QUARTERS				
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PROJECT N	OMBER 8.	PROJECT CO	ST (\$000)			
27596	·	724-417	FTEV0330	06	4,	100			
	ed Design ct to be		sign-build pro	ocedures					
,	tandard o	or Definitive Design ign Was Most Recentl				МО			
(3) All C	ther Des	ign Costs				O			
(4) Const	ruction	Contract Award							
(5) Const	ruction	Start							
(6) Const	ruction	Completion							
(7) Energ	(7) Energy Study/Life-Cycle analysis was/will be performed NO								
b. Equipme	nt assoc	iated with this proj	ect provided	from other	appropria	tions:			
equipmen	COST (\$000)								
FURNISHI	ngs/appl	IANCES	3400 2008			220			

			1 1
			1
			1
			1 1
			1 1
			1 1
			1 1 1
			1
			,
		,	

							DRAFT	1	
1. COMPONENT		FY 2012 MILITARY CONSTRUCTION PROJECT DATA 2. DATE						2. DATE	
AIR FORCE		(computer generated)						·	
3. INSTALLATION AND LOCATION					4. PI	ROJECT TI	TLR		
HURLBURT FIELD, FLORIDA				WIDE	INDEPEN	DENCE ROAD			
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PRO			7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)		
		851-147		FI	EV033	013	20		
		9.	COS!	r ESTI	MATES			· · · · · · · · · · · · · · · · · · ·	
							UNIT	COST	
		ITEM			IU/M	QUANTITY	<u> </u>		
PRIMARY FACILITI	ES							0	
ROAD					SM] 1	. 37	(0)	
SUPPORTING FACIL	LITIES					Į		15	
UTILITIES					LS		İ	(5)	
PAVEMENTS					LS		ļ	(5)	
SITE IMPROVEME	nts				LS	·	ł	(5)	
SUBTOTAL					1	ļ	1	15	
TOTAL CONTRACT (COST					İ		15	
SUPERVISION, INS	SPECTION ;	AND OVERHEAD	t	6.5 %)	1	1	}	1	
TOTAL REQUEST								16	
TOTAL REQUEST (1	ROUNDED)			_		1		20	

10. Description of Proposed Construction: Project extends the four-lane improvements to beyond the Credit Union/1980S intersection.

11. REQUIREMENT:

ADEQUATE:

SUBSTANDARD:

PROJECT: Project extends the four-lane improvements to beyond the Credit Union/19SOS intersection.

REQUIREMENT: Project extends the four-lane improvements to beyond the Credit Union/1980S intersection.

					DRAFT 1		
1. COMPONENT		FY 2012 MILITARY CONSTRUCTION PROJECT DATA 2. DATE					
AIR FORCE	1	(comput	er gene:	rated)			
3. INSTALLATI	ON AND L	CATION		4. PROJECT 1	TITLE		
HURLBURT FIEI	D, FLORI	D A		WIDEN INDEP			
5. PROGRAM EI	LEMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)	
		851-147	FTEV033013			20	
12. SUPPLEME	NTAL DATA	:					
a. Estimat	ed Design	Data:					
(1) Stat	us:				•		
(a) D	ate Desig	n Started					
(b) P	arametrio	Cost Estimates used	d to dev	velop costs		YES	
* (c) P	ercent Co	omplete as of 01 JAN	2011				
* (d) D	ate 35% I	Designed					
(e) D	ate Desig	gn Complete					
(f) E	nergy St	udy/Life-Cycle analy:	sis was,	/will be perf	ormed	МО	
(2) Basi	s:						
(a) S	tandard o	or Definitive Design	-			NO	
(b) W	here Des	ign Was Most Recently	y Used	-			
(3) Tota	1 Cost (d	c) = (a) + (b) or (d)) + (e)	:		(\$000)	
(a) E	Production	n of Plans and Speci	ficatio	ns		0	
(b) A	11 Other	Design Costs				0	
(c) I	otal					0	
• •	Contract					0	
(e) 1	In-house					0	
(4) Cons	truction	Contract Award					
(5) Cons	truction	Start					
(6) Cons	struction	Completion					
which	is compa	letion of Project De rable to traditional tability.					

b. Equipment associated with this project provided from other appropriations: N/A

1. COMPONENT	FY 2007 MILITARY CONSTRUCTION PROJECT DATA						2. DATE	
AIR FORCE			(compu	ter ge	erate	d)		
3. INSTALLATIO	N AND LO	CATION		,	4. PF	OJECT TI	TLE	
HURLBURT FIELD, FLORIDA					REALI	GN CRUZ	avenue	
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PRO-				JECT 1	NUMBER	8. PROJECT C	OST (\$000)	
27596 851-147 F				F.	EV033	014	2,	400
			9. COS	T ESTI	MATES			
		TTEM			77 /M	OUANTITY	UNIT	COST
					1			
REALIGN CRUZ AVE	NUE						1	1,150
REALIGN CRUZ A	VENUE				IM	460	2,500	(1,150)
SUPPORTING FACI	LITIES					}		1,011
UTILITIES					LS			(450)
SITE IMPROVEME	NTS				LS			(250)
DEMO BLDG 9060	4				SM	9	9 110	(11)
PARKING PAVEME	nts				LS			(300)
SUBTOTAL								2,161
CONTINGENCY	(5.0	€)			1			108
TOTAL CONTRACT	COST					1		2,269
SUPERVISION, IN	SPECTION	AND OVE	RHEAD (5.7 %)				129
TOTAL REQUEST								2,398
TOTAL REQUEST (ROUNDED)					1		2,400

10. Description of Proposed Construction: Demolish road and parking pavements, demolish curbs and sidewalks. Construct two lane asphalt road, including fill and compaction, culverts and retaining walls along existing ditch, curbs and sidewalks, sodding and striping. Includes relocation of electrical and water lines, 200 parking spaces and site improvements/mitigation as required.

11. REQUIREMENT: 460 LM ADEQUATE: 0 LM SUBSTANDARD: 460 LM

PROJECT: Realign Cruz Avenue. (Current Mission)

REQUIREMENT: This project is required to realign Cruz Avenue to provide adequate standoff distances from existing and future planned facilities in support of the FY09 beddown of additional C-130 aircraft at Hurlburt Field. This project will provide better access and adequate parking spaces to facilities located on the north-west side of the flight line.

CURRENT SITUATION: Existing road and parking areas have deteriorated from age, poor drainage, and heavy traffic. Cruz Avenue is within 30 feet of existing and newly planned facilities and is too close to provide adequate force protection. Over 200 personnel and five existing facilities are at risk to include the Aerial Delivery facility, Base Photo Lab, Wing Operations Plans Flight, Air Intelligence Service facility, and the Maintenance Group Headquarters. In support of the C-130 beddown, a new C-130 hangar and squadron operations facility are scheduled to be constructed in FY09 between the flightline and Cruz Avenue and will be impacted unless this road is realigned.

IMPACT IF NOT PROVIDED: Existing road and parking areas will continue to deteriorate due to age, poor storm water runoff, and heavy traffic. Military and civilian personnel will continue to be exposed to inadequate force protection stand-off distances. Newly constructed facilities will also be impacted by the close proximity of Cruz Avenue.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-

1. COMPONENT	FY 2007 MILITARY	DATA 2. DATE			
AIR FORCE	(compu				
3. INSTALLATION	Tie .				
HURLBURT FIELD,	T FIELD, FLORIDA REALIGN CRUZ AVENUE				
5. PROGRAM ELEME	ENT 6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)		
27596	851-147 FTEV033014 2,400				

1084, "Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Supporting facilities costs exceed 25% of the programmed amount due to the amount of pavement required to construct new parking areas and the relocation of above ground utilities underground. Base Civil Engineer: William A. Kolakowski, Lt Col, 850-884-7701. (Realign Cruz Avenue - 460 LM = 1,501 LF)

JOINT USE CERTIFICATION: This is an installation utility/infrastructure project, and does not qualify for joint use at this installation. However, all tenants on this installation are benefited by this project.

COMPONENT	FY 2007 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)					
3. INSTALLATIO	ON AND LO			4. PROJECT T	TTTE	J
HURLBURT FIEL	ודאותדים ח) <u>A</u>		REALIGN CRUZ		
	, 110141		l		1	
5. PROGRAM EL	PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COS					ST (\$000)
27596		851-147	FTEV033014 2,400			
12. SUPPLEMEN	TAL DATA	:				
a. Estimate	d Design	Data:				
(1) Statu	_					
• • • •	-	m Started			1:	5-APR-05
• •	-	: Cost Estimates use	d to de	velop costs		YES
* (c) Pe	ercent Co	amplete as of 01 JAN	2006			15%
* (d) Date 35% Designed						5~SEP-05
(e) Da	ate Desig	n Complete			1	5-SEP-06
(f) E	nergy Stu	ndy/Life-Cycle analy	sis was,	/will be perf	ormed	NO
(2) Basis						
• •		or Definitive Design				NO
(p) M	here Desi	ign Was Most Recentl	y Used	-		
(3) Total	l Cost (d	(a) = (a) + (b) or (d)) + (e)	:		(\$000)
(a) P	roduction	n of Plans and Speci	ficatio	ns		144
(b) A	11 Other	Design Costs				72
(c) T	ota1					216
• •	ontract		•			180
(e) I	n-house					36
(4) Cons	truction	Contract Award				06 DEC
(5) Cons	truction	Start				07 JAN
(6) Cons	truction	Completion				07 DEC
which	is compa	letion of Project De rable to traditional tability.				

- b. Equipment associated with this project provided from other appropriations:

								
1. COMPONENT	1. COMPONENT FY 2010 MILITARY CONSTRUCTION PROJECT DATA							
AIR FORCE		(comp	ıter ger	erate	:d)	 _		
3. INSTALLATION	3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
HURLBURT FIELD, FLORIDA				REALI	GN CRUZ	AVENUE, PH 2		
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJ				JECT 1	NUMBER	8. PROJECT	COST (\$000)	
27596		851-147	FI	EV033	015	2	, 650	
		9. cos	T ESTI	MATES				
						UNIT	COST	
	ITEN			JU/M	QUANTITY		 	
REALIGN CRUE AVENUE	E, PH2						674	
REALIGN CRUZ AVEN	ÜE			LM	550	1,225	(674)	
SUPPORTING FACILITY	ies			}	}	}	1,720	
UTILITIES				LS	ĺ	-	(350)	
SITE IMPROVEMENTS				LS			(200)	
CULVERTS				LS	\	1	(90)	
RETAINING WALLS				LS	ĺ		(480)	
PAVEMENTS/CURBS/S	IDEWALKS			LS			(600)	
SUBTOTAL				1	1	1	2,394	
CONTINGENCY (5.0 %)					ŀ		120	
TOTAL CONTRACT COST							2,513	
SUPERVISION, INSPE	SUPERVISION, INSPECTION AND OVERHEAD (5.7 %)						143	
TOTAL REQUEST				1	1	}	2,657	
TOTAL REQUEST (ROUNDED) 2,65							2,650	

10. Description of Proposed Construction: Demolish road and parking pavements, demolish curbs and sidewalks, install culverts and retaining walls. Construct a two lane asphalt road and parking, including fill and compaction, curbs and sidewalks, sodding and striping. Includes relocation of electrical and water lines and site inprovements/mitigation as required.

11. REQUIREMENT: 1,010 LM ADEQUATE: 460 LM SUBSTANDARD: 550 LM

PROJECT: Realign Cruz Avenue, Phase 2 (Current Mission).

REQUIREMENT: This project is required to relocate Cruz Avenue to provide adequate stand-off distances from existing and future planned facilities and to provide better access to facilities located on the north-west side of the flight line.

CURRENT SITUATION: Existing road and parking have deteriorated and are too close (30 FT) from existing and future planned facilities to afford adequate force protection.

IMPACT IF NOT PROVIDED: Existing road and parking will continue to deteriorate due to heavy traffic and poor storm water runoff. Personnel in existing and future planned facilities will be exposed to inadequate force protection stand-off distances.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850-884-7701.

JOINT USE CERTIFICATION: This is an installation utility/infrastructure project, and does not qualify for joint use at this installation. However, all tenants on this installation are benefited by this project.

1. COMPONENT AIR FORCE		FY 2010 MILITARY CO	ONSTRUCT:		DATA	2. DATE		
	L					L		
3. INSTALLATIO	ON AND L	OCATION	Į.	4. PROJECT T	ITLE			
HURLBURT FIEL	D, FLORI	DA		REALIGN CRUZ	AVENUE, PH 2			
5. PROGRAM EL	ement	6. CATEGORY CODE	1	ect number	8. PROJECT CO			
27596		851-147	FTE	v033015	2,	650		
12. SUPPLEMEN	d Design							
(b) Pa * (c) Pa * (d) Da (e) Da	ate Designarametric ercent Co ate 35% l ate Designar	yn Started : Cost Estimates usec complete as of 01 JAN Designed yn Complete udy/Life-Cycle analy	2009		ormed	YES NO		
(2) Basis: (a) Standard or Definitive Design - NO (b) Where Design Was Most Recently Used -								
<pre>(3) Total Cost (c) = (a) + (b) or (d) + (e): (a) Production of Plans and Specifications (b) All Other Design Costs (c) Total (d) Contract (e) In-house</pre>								
(4) Cons	truction	Contract Award						
(5) Cons	truction	Start						
(6) Cons	truction	Completion						
which	is compa	letion of Project De rable to traditional tability.						
b. Equipme	nt assoc	iated with this proj	ject prov	rided from of	ther appropria	tions:		
				-				
,								

1. COMPONENT AIR FORCE	FY 2009 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)					
3. INSTALLATION AND HURLBURT FIELD, FLOR	LOCATION	4. PROJECT TITLE SOF SPECIAL TACTICS GROUP FACILITY				
5. PROGRAM ELEMENT	6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)			
11830	610-243	FTEV033017	6,500			

9. COST ESTIMATES

			UNIT	COST
ITEM	II/M	QUANTITY		
SOF 720 STG HQ FACILITY				4,778
SPECIAL TACTICS GROUP FACILITY (29.650 SF)	SM	2,754	1,248	(3,437)
ADD FOR SCIF/VAULT (4728 SF)	SM	439	2,500	(1,098)
FORCE PROTECTION/ANTITERRORISM 0.5%	LS			(17)
SUSTAINABILITY @ 5%	LS	1	į	(227)
-	LS	į į	Į	(0)
SUPPORTING FACILITIES				1,050
UTILITIES	LS	İ	j	(200)
PAVEMENTS	LS	1	1	(200)
SITE IMPROVEMENTS	ıs		Ì	(200)
COMMUNICATION SYSTEM	LS		}	(200)
DESIGN-BUILD DESIGN COST	LS.		1	(250)
SUBTOTAL			\	5,828
CONTINGENCY (5.0 %)		Į į	1	291
TOTAL CONTRACT COST])	}	6,120
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %	,	1		349
TOTAL REQUEST				6,469
TOTAL REQUEST (ROUNDED)				6,500
EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)	ļ			(726)

10. Description of Proposed Construction: Concrete foundation and floor slab, steel frame, masonry walls and sloping metal roof. Functional areas include command section, logistics, operations, intelligence and plans. Includes utilities, parking, SCIF and vault areas with secure computer stations and all necessary support. Force protection includes structural reinforcement of exterior walls and fully tempered insulated glass windows.

Air Conditioning: 74 Tons

11. REQUIREMENT: 13,899 SM ADEQUATE: 10,706 SM SUBSTANDARD: 1,632 SM

<u>PROJECT:</u> Construct a Special Tactics Group Facility (Current Mission).

REQUIREMENT: This project is required to provide an adequate facility for the 720th Special Tactics Group (STG). The 720th STG has grown from an authorization of 40 to over 60 personnel and now includes the 720th Operations Support Squadron (OSS). Additional missions have been tasked to the Group to include Air Force Combat Control, Air Force Combat Weather, and the Advanced Skills Training school. Expanded support requirements associated with this growth have resulted in USSOCOM increasing Special Tactics personnel authorizations. This supplemental manpower generates an immediate need for additional operations space and supporting administrative areas. Additional space is also required for a SCIF, Operations Center, locker room, and mobility bay.

<u>CURRENT SITUATION:</u> The existing facility (a former clinic) is inadequately sized and poorly configured to support the units mission growth. Its mechanical and electrical

1. COMPONENT	FY 2009 MILITARY CONSTRUCTION PROJECT DATA 2. DATE				
AIR FORCE	(computer generated)				
3. INSTALLATION HURLBURT FIELD	TION AND LOCATION 4. PROJECT TITLE ELD, FLORIDA SOF SPECIAL TACTICS GROUP FACILITY				
5. PROGRAM ELE	MENT 6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)		
11830	610-243	FTEV033017	6,500		

systems are antiquated and cannot be economically upgraded. Vehicle access to the current loading dock was cut off due to base Force Protection measures after 9-11. The SCIF/Operations Center cannot support the large number of personnel assigned who oversee the tasking of 8 Special Tactics Squadrons (based in six geographically separated locations) directly supporting the ongoing Global War on Terrorism. The facility also has no secure auditorium/conference room to sufficiently meet the Group;s requirements.

IMPACT IF NOT PROVIDED: Special Tactics Forces will continue to operate in a poorly configured and inadequately sized facility with deteriorating mechanical and electrical systems. This will impact the morale and performance of these mission essential personnel working under such conditions.

ADDITIONAL: This project does meet the criteria/scope specified in Part II of Military Bandbook 1190, "Facility Planning and Design Guide" and Air Force Handbook 32-1084, "Facility Requirements." Anti-terrorism/force protection measures will be included in accordance with the Unified Facilities Criteria (UFC) 4-010-01, DoD Minimum Anti-Terrorism Standards for Buildings, dated 8 October 2003, and updates as applicable. This project will comply with U.S. Army Corps of Engineers Technical Instruction 800-01, dated 20 July 1998 or later, and the Installation Design Guide. All known alternative options were considered during the development of this project. No other option could meet the mission requirement; therefore, no economic analysis was needed or performed. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701.

JOINT USE CERTIFICATION: N/A. USSOCOM budgets only for those facilities specifically for SOF use. Common support facilities are budgeted by the military departments. Reference Title 10, Section 165.

1. COMPONENT AIR FORCE	FY 2009 MILITARY CONSTRUCTION PROJECT DATA (computer generated)					
3. INSTALLATION AND LOCATION 4. PROJECT TITLE HURLBURT FIELD, FLORIDA SOF SPECIAL TACTICS GROUP F						
5. PROGRAM ELEMENT 11830	6. CATEGORY CODE	7. PROJECT NUMBER FTEV033017	8. PROJECT COST (\$000) 6,500			

12. SUPPLEMENTAL DATA:

- a. Estimated Design Data:
 - (1) Project to be accomplished by design-build procedures
 - (2) Basis:
 - (a) Standard or Definitive Design -

(b) Where Design Was Most Recently Used ~

(3) All Other Design Costs

174

NO

- (4) Construction Contract Award
- (5) Construction Start
- (6) Construction Completion
- (7) Energy Study/Life-Cycle analysis was/will be performed

NO

b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPRO	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
COLLATERAL EQUIPMENT	3400	2010	488
COMMUNICATIONS EQUIPMENT	3400	2010	238

						DRAFT	1
1. COMPONENT		FY 2012 MILITARY CONSTRUCTION PROJECT DATA 2. DATE					
AIR FORCE		(comp	uter ge	erate	ed)		İ
3. INSTALLATIO	N AND L	OCATION		4. P	ROJECT TI	TLE	
HURLBURT FIELI	, FLORI	DA .		AFLD	WAIVER,	ALTER INDEPE	NDENCE ROAD
5. PROGRAM ELI			7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)
							,,,,,,,
		851-147	F	EV033	018		20
		9. 008	T ESTI	MATES		- 	<u></u>
_		ITEM		U/M	OUANTITY	UNIT	COST
PRIMARY FACILITI	ES					-	0
ROAD				SM	1	37	(0.
SUPPORTING FACII	lities			ļ	}		15
UTILITIES				LS			(5)
PAVEMENTS				LS			(5)
SITE IMPROVEME	nts			LS			(5)
SUBTOTAL					l		15
TOTAL CONTRACT	COST			1			15
SUPERVISION, IN	SPECTION	AND OVERHEAD (6.5 %)	1			1
TOTAL REQUEST				}		}	16
TOTAL REQUEST (ROUNDED)				L		20
-		roposed Constructio outside Primary Sur		ocate	s Indepen	dence Road,	at south east
11. REQUIREMEN		ADEOUATE:	SUBS	TANDA	RD:		

PROJECT: Relocates Independence Road, at south east corner of runway, to outside Primary Surface.

REQUIREMENT: Relocates Independence Road, at south east corner of runway, to outside Primary Surface.

1. COMPONENT		FY 2012 MILITARY C	ONSTRUC!	TION PROJECT	DATA	2. DATE		
AIR FORCE	FORCE (computer generated)							
3. INSTALLATIO	ON AND LO	CATION		4. PROJECT 1	ITLE:			
HURLBURT FIELD, FLORIDA AFID WAIVER, ALTER INDEPENDENCE ROAD								
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)		
		851~147	FT	EV033018) :	20		
12. SUPPLEMEN	TAL DATA	:						
a. Estimate	d Design	Data:						
(1) Statu	s:					,		
, , ,		m Started						
(b) Pa	rametrio	: Cost Estimates used	d to dev	relop costs		YES		
		emplete as of 01 JAN						
* (d) Da	ite 35% D	esigned						
(e) Da	ate Desig	n Complete		•				
(f) Er	ergy Stu	dy/Life-Cycle analy	sis was,	/will be perf	ormed	NO		
(2) Basis	::							
(a) S1	tandard o	or Definitive Design	-			NO		
(b) W	nere Desi	ign Was Most Recently	y Used ·	-				
(3) Total	Cost (c	:) = (a) + (b) or (d)	+ (e):	:		(\$000)		
(a) P:	roduction	of Plans and Speci	fication	ns		0		
(b) A	ll Other	Design Costs				0		
(c) To	otal					0		
, , ,	ontract					0		
(e) In	n-house	•				0		
(4) Const	ruction	Contract Award						
(5) Const	truction	Start						
(6) Const	truction	Completion						
which:	is compar	letion of Project De rable to traditional tability.						
b. Equipment N/A	nt associ	iated with this proj	ect pro	vided from ot	ther appropria	tions:		

1. COMPONENT	FY 2006 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE	(computer generated)					
3. INSTALLATION HURLBURT FIELD	LATION AND LOCATION 4. PROJECT TITLE FIELD, FLORIDA SOUNDSIDE VISITING QUARTERS					
5. PROGRAM ELE	MENT		7. PROJECT NUMBER 8. PROJECT CO		8. PROJECT CO	
NAF		724-417	FT	EV033020	14	, 683

9. COST EST	MATE	s		
ITEM	U/M	QUANTITY	UNIT	COST
SOUNDSIDE BILLETING (120 PN)		,		10,314
120 PN BILLETING FACILITY (63,540 SF)	SM	5,903	1,730	(10,212
FORCE PROTECTION	LS			(102
SUPPORTING FACILITIES				2,981
UTILITIES	LS			(850
PAVEMENTS	LS			(850
SITE IMPROVEMENTS	LS			(850
COMMUNICATION SYSTEM	LS			(431
SUBTOTAL		Ì		13,295
CONTINGENCY (4.6 %)				612
TOTAL CONTRACT COST	ļ			13,907
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %)	Ì			793
TOTAL REQUEST	1	1		14,700
TOTAL REQUEST (ROUNDED)				14,683
UNFUNDED DESIGN		[(1,250
UNFUNDED FF&E	{	1		(1,200
Design management				(250
			1	3

10. Description of Proposed Work: Concrete foundation and floor slab, steel frame, masonry and siding walls with sloped metal roof. Rooms to have combination living/bedroom with bath and support space for housekeeping equipment and storage. Includes utilities, parking and all other necessary support. Force protection includes structural reinforcment of exterior walls, landscaping, and tempered insulated glass windows.

11. REQUIREMENT: 165 PN ADEQUATE: 45 PN SUBSTANDARD: 108 PN

PROJECT: Construct 120 PN (63,540 SF) Soundside Billeting Facility

REQUIREMENT: This project is required to provide adequate living quarters to accommodate TDY personnel at Hurlburt Field. HQ AFSOC is located at Hurlburt Field drawing large numbers of officers, NCO's and civilian visitors to the installation. Additionally, the installation is home for the 16th Special Operations Wing, the 505th Command and Control Wing and the Special Operations School that conduct numerous training exercises and host numerous mission rehearsals. These schools and mission rehearsals bring a tremendous volume of transient personnel to the installation, generating a significant demand for temporary quarters. Force protection measures will be incorporated IAW Installation Force Protection Guide. This proposed project will provide lodging for 120 persons.

<u>CURRENT SITUATION:</u> Hurlburt Field has a severe shortage of adequate transient quarters available to accommodate visiting officers and non-commissioned officers. The lack of

Air Conditioning: 140 Tons

1. COMPONENT AIR FORCE	FY 2006 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)					
3. INSTALLATION HURLBURT FIELD	TION AND LOCATION 4. PROJECT TITLE ELD, FLORIDA SOUNDSIDE VISITING QUARTERS					RS
5. PROGRAM ELE	MENT 6.	CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	OST (\$000)
NAF		724-417	FT	,683		

adequate on-base quarters forces transient personnel to find lodging off base. The availability and cost of off-base quarters fluctuates dramatically because of the local tourist based economy. During the tourist season adequate off-base quarters, at reasonable prices, are difficult or impossible to find within reasonable travel distance. The problem is further compounded by the increasing AFSOC air crew training requirements as new weapons systems are received.

IMPACT IF NOT PROVIDED: Large numbers of transient personnel, averaging 156 per night, will continue to be housed off-base, at a cost exceeding \$1 million per year for contract quarters. Forced use of off-base quarters will have an adverse affect on training and mission rehearsal activities and will degrade morale, productivity and career satisfaction of transient personnel.

ADDITIONAL: A Project Validation Analysis has been prepared comparing alternatives for new construction, revitalization, leasing and status quo operations. Based on the present values and benefits of the respective alternative, new construction was found to be cost effective over the life of the project. Although Appropriated Funds (APF) is the normal fund source for Visiting Quarters a waiver to fund source has been granted, which allows the use of Non-Appropriated Funds (NAF).

Key Milestones: Design Start - 24 Jun 04; 65% Design - 1 Jul 05; 100% Design - Sep 05; Award - Mar 06; Construction Complete - Sep 07

I have reviewed this document and certify it is complete and accurate. I have validated the project's primary classification. It has been coordinated with the user and other appropriate agencies and approved by the Installation Commander.

WILLIAM A. KOLAKOWSKI, Lt Col, USAF Base Civil Engineer (850) 884-7701

						DRAFT	*	
1. COMPONENT	FY 2011 MILITARY CONSTRUCTION PROJECT DATA 2. DATE							
AIR FORCE (computer generated)								
3. INSTALLATIO	N AND L	OCATION		4. PI	ROJECT TI	CLE		
HURLBURT FIELD	, FLORI	DA		16TH	CONTRACT	ing squadron	FACILITY	
5. PROGRAM ELI	EMENT	6. CATEGORY CODE	7. PRO	DECT 1	NUMBER	8. PROJECT	COST (\$000)	
27596		610-243	FI	EV 033	021	2	,500	
		9. cos	T ESTI	MATES				
						UNIT	COST	
				11/M	QUANTITY		 	
CONTRACTING SQUA	ADRON FAC	ILITY					1,804	
CONTRACTING SQ	UADRON			SM	1,200	1,425	(1,710)	
FORCE PROTECTI	on/antiti	ERRORISM (0.5%)		LS			(9)	
SUSTAINABILITY	CONSTRU	CTION (5.0%)		LS	ļ		(86)	
SUPPORTING FACI	LITIES			1	j	l	457	
UTILITIES				LS			(100)	
PAVEMENTS				LS	į		(110)	
SITE IMPROVEME	nts			LS	1.	ł	(100)	
COMMUNICATION	System			LS	ļ	1	(70)	
DEMOLITION				SM	841	92	(77)	
SUBTOTAL				1	1	1	2,261	
CONTINGENCY	(5.0	%)		Į.			113	
TOTAL CONTRACT COST							2,374	
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %)							135	
TOTAL REQUEST							2,510	
TOTAL REQUEST (ROUNDED)						2,500	
EQUIPMENT FROM	OTHER AP	PROPRIATIONS (NON-ADD)					(2,0.0)	
								

10. Description of Proposed Construction: Concrete foundation and floor slab, steel structure, masonry walls and sloping metal roof. Fundational are a lacked and section, discount and programs and commodities sections. Includes utilities, pavements, demolition of one building and other necessary support. Includes minimum DoD force protection standards.

Air Conditioning: 32 Tons

11. REQUIREMENT: 11,989 SM

ADEQUATE: 10,229 SM

SUBSTANDARD: 1,549 SM

PROJECT: Construct a Contracting Squadron Facility.

REQUIREMENT: This project is required to provide an adequate facility for the 16th Contracting Squadron. This facility will provide separate areas for base personnel support and customer service/contractor areas.

CURRENT SITUATION: The existing contracting squadron facility is over 40 years old and is totally inadequate to support the contracting functions at Hurlburt Field. There are no facilities on base that could be used or modified for this requirement.

IMPACT IF NOT PROVIDED: The contracting squadron will continue to be housed in an inadequate facility which will affect the morale and productivity of personnel and thereby affect the efficient support of the mission of the 16th Special Operations Wing. ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options to accomplish this project (status quo, renovation, upgrade/removal, new construction) was

DRAFT 1

1. COMPONENT	FY 2011 MILITARY CONSTRUCTION PROJECT DATA					2. DATE	
AIR FORCE	(computer generated)						
3. INSTALLATION AND LOCATION 4. PROJECT TITLE					TLE		
HURLBURT FIELD, FLORIDA				16TH CONTRACTING SQUADRON FACILITY			
5. PROGRAM ELI	EMENT 6.	CATEGORY CODE	7. PROJECT NUMBER 8. PRO		8. PROJECT CO	ST (\$000)	
27596		610-243	F.	EV033021 2,		00	
					·	_	

done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Enginner: William A. Kolakowski, Lt Col, USAF, 850-884-7701. Contracting Squadron Facility: 1200 SM = 12,831 SF.

JOINT USE CERTIFICATION: This facility can be used by other components on an "as available" basis; however, the scope of the project is based on Air Force requirements.

				DRAFT	+	
. COMPONENT		FY 2011 MILITARY	CONSTRUCTION P	ROJECT DATA	2. DATE	
IR FORCE	(computer generated)					
3. INSTALLATIO	N AND LOC	ATION	4. PR	OJECT TITLE		
HURLBURT FIELD	, FLORIDA		16TH	CONTRACTING SQUADR	ON FACILITY	
5. PROGRAM ELE	ement	6. CATEGORY CODI	E 7. PROJECT N	UMBER 8. PROJECT	COST (\$000)	
27596	27596 610-243 FTEV033021					
12. SUPPLEMENT	TAL DATA:		······································			
a. Estimate	d Design D	Data:				
(1) Status	s:					
• •	te Design	Started				
(b) Pa	rametric (Cost Estimates us	sed to develop	costs	YES	
	-	plete as of 01 J	AN 2010			
· •	te 35% De	-				
• •	te Design	•	locais uss <i>tall</i> l	ha mamfames	390	
(I) En	ergy stud	y/Life-Cycle ana	TASTS MGS/MITT	pe berrormed	NO	
(2) Basis						
		Definitive Design Nas Most Recen	•		МО	
(D) Wi	mere besig	n was most Recen	cry osed -			
		= (a) + (b) or			(\$000)	
		of Plans and Spe	cifications		0	
• •		esign Costs			0	
(c) To					0	
• •	ontract n-house				0	
• •		ontract Award				
, ,	truction S					
• •		Completion				
-		•				
				Parametric Cost T		
	_		ial 350 design t	o encore valid	~ 11	
cost ar	nd executa	bility.				
b. Equipmen	nt associa	ted with this pr	oject provided	from other appropr	riations:	
				FISCAL YEAR		
		ATTRE	PROCURING APPROPRIATION	APPROPRIATED OR REQUESTED	COST (\$000	
ROTTDWEN	THE NOMENCE.			An Total Tan		
	T NOMENCI.		3400	0010	••	
-	T NOMENCL WORKSTAT		3400	2012	240	
			3400	2012	••	

					,		. ,		
1. COMPONENT FY 2007 MILITARY CONSTRUCTION PROJECT DATA						2. DATE			
AIR FORCE (computer generated)									
3. INSTALLATION AND LOCATION				4. PI	4. PROJECT TITLE				
					AT/FP MAIN GATE/SOUNDSIDE ACCESS CONTROL				
5. FROGRAM ELEMENT 6. CATEGORY CODE 7. PRO-				JECT 1	JECT NUMBER 8. PROJECT COST (\$000)				
28047 730-832 F			TEV033022 6,:			,500			
		9. COS	T EST	MATES					
		TEM		II/M	OUANTITY	UNIT	COST		
MAIN GATE/SOUNDSIDE	ACCESS	CONTROL FACILITIES					2,946		
GATE HOUSES/ID CHECK/OVERWATCH AREA				SM	342	3,362	(1,150)		
ENTRY CONTROL/VEHICLE INSPECTION CENTER				SM	170	3,362	(572)		
ACCESS GATES/BARRI	er systi	ems		LS	Į	ļ	(980)		
SECURITY SYSTEM				LS	1		(245)		
SUPPORTING FACILITIES						1	2,909		
UTILITIES					}		(750)		
PAVEMENTS				LS			(1,750)		
SITE IMPROVEMENTS				LS		į	(400)		
DEMOLITION				SM	7	3 120	(9)		
SUBTOTAL							5,855		
CONTINGENCY (5.0 %)							293		
TOTAL CONTRACT COST							6,147		
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %))			350		
TOTAL REQUEST							6,498		
TOTAL REQUEST (ROUNDED)				{	}	{	6,500		

10. Description of Proposed Construction: Concrete foundation and floor slab, masonry walls and sloping metal roof for an entry control/vehicle inspection center, ID check gate houses, a metal canopy over 3 lanes of traffic, guard booths, an overwatch area with shelter and a K-9 facility. Includes security system, utilities, pavements, crash beams, barriers, perimeter walls and all other necessary support. Demolish four buildings (73 SM).

Air Conditioning: 15 Tons

11. REQUIREMENT: 512 SM ADEQUATE: 0 SM SUBSTANDARD: 73 SM

PROJECT: AT/FP Main Gate/Soundside Entry Control Facilities. (Current Mission)
REQUIREMENT: This project is required to provide adequate vehicle entry control lanes and facilities for security personnel to properly conduct routine ID checks, visitor identification, and commercial vehicle inspection. The objective of the main gate and the soundside gate is to prevent unauthorized access to the base and maximize vehicular traffic flow both on-base and on US Highway 98; a 4-lane East-West thoroughfare that divides the main base from the soundside area located south of the main gate. This project is also required to support the increase of over 900 personnel associated with the beddown of additional C-130 aircraft at Hurlburt Field in FY06 and FY10.

CURRENT SITUATION: The existing entry control gates do not meet current DoD
Antiterrorism/Force Protection Standards and Air Force Installation Entry Control
Facility Design Guide criteria. Insufficient approach/queuing lanes and inadequate
commercial vehicle inspection/holding areas at the main gate create 10-20 minute traffic
delays and in some instances actual gridlock situations on US Highway 98. The soundside

1. COMPONENT	FY 2007 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE	(computer generated)					
3. INSTALLATION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELD, FLORIDA AT/FP MAIN GATE/SOUNDSIDE A						CCESS
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PROJECT NUMBER 8. PROJECT COST (\$00			ST (\$000)
28047		730-832	FTEV033022 6			00

gate which currently guards the base marina and military family housing area is

improperly configured to protect the consolidated club, mission planning facility, and lodging complex. A Hurlburt Field Main Gate Force Protection Study conducted in April 2003 determined the current gate configuration can only support 14,000 vehicles per day or 1,358 vehicles per hour. According to the report, the increase of personnel associated with the C-130 beddown and the growth in the surrounding area will require the main gate to support approximately 16,000 per day or 1,528 vehicles per hour. This project will meet this requirement. There are no alternate gate locations that can be accessed from US Highway 98 without creating more traffic problems. IMPACT IF NOT PROVIDED: The increase of over 900 personnel will escalate the traffic congestion at the main gate and cause delays in excess of 10-20 minutes on US Highway 98. The risk of vehicular accidents will also increase. Existing and future facilities planned for the soundside area will remain unprotected and vulnerable to attack. Personnel near the gate and security personnel may be exposed to terrorist attacks. ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicated there is only one option that will meet the operational requirement; therefore, no economic analysis was needed or performed. A certificate of exception is being prepared for this project. The supporting facilities cost exceeds 25% of the programmed amount due to the realignment of over 20,000 SM of pavement and the reconfiguration of the existing street lighting and electrical service distribution. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701. (Gate House -328 SM = 3,529 SF; Vehicle Inspection Center - 170 SM = 1,829 SF) JOINT USE CERTIFICATION: This is an installation utility/infrastructure project, and does not qualify for joint use at this location. However, all tenents on this

installation are benefited by this project.

1. COMPONENT	COMPONENT FY 2007 MILITARY CONSTRUCTION PROJECT DATA 2. DATE						
AIR FORCE		(compute	er gene	rated)		_	
3. INSTALLATIO	ON AND LO	CATION		4. PROJECT I	ITLE		
HURLBURT FIELD	, FLORII)A		AT/FP MAIN G	ATE/SOUNDSIDE	ACCESS	
				CONTROL			
5. PROGRAM EL	PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (
28047		730-832	FT	EV033022	6,	500	
12. SUPPLEMEN	TAL DATA	:					
a. Estimate	d Design	Data:					
(1) Statu							
	-	m Started		•	10)-APR-05	
(b) Parametric Cost Estimates used to develop costs						YES	
• •		emplete as of 01 JAN	2006		•	15%	
(-,)-SEP-05	
• •	-	•		/mill be made		5-AUG-06	
(I) EI	ergy st	dy/Life-Cycle analy	sis was	/will be peri	Ormed	NO	
(2) Basis							
• •		or Definitive Design				NO	
(b) W	here Desi	ign Was Most Recentl	y Used	_			
(3) Total	L Cost (c	a(a) = (a) + (b) or (d)) + (e)	:		(\$000)	
(a) P:	roduction	of Plans and Speci	ficatio	ns		390	
(b) A	ll Other	Design Costs				195	
(c) T	otal					585	
(d) C	ontract				•	520	
(e) I	n-house					65	
(4) Const	truction	Contract Award				06 DEC	
(5) Cons	truction	Start				07 JAN .	
(6) Cons	truction	Completion				08 FEB	
	-	letion of Project De rable to traditional					

- cost and executability.
- b. Equipment associated with this project provided from other appropriations: N/A

		·

1. COMPONENT		FY 200		2. DATE					
AIR FORCE	(computer generated)						ŀ		
3. INSTALLATION AND LOCATION 4. PROJ						. PROJECT TITLE			
HURLBURT FIELD, FLORIDA				AD	D TO FITNE	ESS CENTER, 90	517		
5. PROGRAM EL	EMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJE			8. PROJECT CO	JECT COST (\$000)				
22176		740-674	F	EV04	11072		C 529 /32.4		
9. COST ESTIMATES									
					QUANTITY	UNIT	COST		
ADD TO FITNESS	CENTER,	90517					552.0		
FITNESS CENTER	3.			SF	6,000	92	(552.0)		
SUPPORTING FACI	LITIES					1	27.0		
CONTINGENCY (5%)			LS]	}	(27.0)		
SUBTOTAL				Ì			579.0		
PROFIT AND OVER	HEAD	(26.5 %)					153.4		
TOTAL FUNDED COST						1	732.4		
UNFUNDED COST (10 %)				1		}	73.2		
TOTAL REQUEST							805.7		

10. Description of Proposed Work: Construct a 6000 SF addition of concrete masonry walls, steel frame, concrete footings and slab and sloping metal roof. Functional areas include group exercise room, locker rooms and child play area.

Air Conditioning: 15 Tons

11. Requirement: 36940 SF Adequate: 30940 SF Substandard: 39249 SF

PROJECT: Construct Addition to Fitness Center, 90517.

REQUIREMENT: Because of the mission at Hurlburt Field, physical fitness is a top priority for active duty personnel. Hurlburt also hosts four ACC flag exercises throughout the year and students at the Joint Special Operations University and the USAF Special Operations School. Consequently the fitness centers are heavily utilized and at times overcrowded. The hours of operation for these facilities have been increased to 20 hours per day to help alleviate the overcrowded conditions.

CURRENT SITUATION: The current fitness centers do not have adequate group exercise rooms, locker rooms and lack a child play area. The fitness centers are not adequate to support the number of military, dependent and retired personnel and cannot support the CSAF directed physical training program.

IMPACT IF NOT PROVIDED: Personnel at Hurlburt Field will be forced to use overcrowded fitness facilities, productivity will be lost, disrupting mission essential work accomplishment. This will adversely impact morale, welfare and retention of personnel which play a vital role in sustaining overall mission readiness.

	(
·			

							<u> </u>
1. COMPONENT AIR FORCE	FY 2010 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)						
3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
			ļ			-	
HURLBURT FIELD, FLORIDA						ICLE MAINTE	NANCE
 					JITY		
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	ROJECT NUMBER 8. PROJECT COST (\$000)			
27596		214-467	F	EV043	000	1	,700
		9. Cos	T ESTI	MATES			
						UNIT	COST
		ITEM		U/M	QUANTITY	·	
REFUELING VEHICL	e mainte	NANCE FACILITY					1,090
REFUELING VEHIC	LE SHOP			SM	395	2,615	(1,033)
FORCE PROTECTION	n/antite	RRORISM (0.5%)		LS	1		(5)
SUSTAINABILITY	CONSTRUC	TION (5.0%)		ITS			(52)
SUPPORTING FACIL	ITIES			1	1		420
UTILITIES				LS	ļ		(100)
PAVEMENTS				LS			(115)
SITE IMPROVEMEN	TS			LS		į	(100 }
COMMUNICATION S	YSTEM			LS			(75)
DEMOLITION				SM	28'	7 105	(30)
SUBTOTAL.							1,510
CONTINGENCY	(5.0	%)		1	1	1	75
TOTAL CONTRACT COST							1,585
SUPERVISION, INS	PECTION	AND OVERHEAD	5.7 %)		1	1	90
TOTAL REQUEST						1	1,676
TOTAL REQUEST (ROUNDED)				1		-	1,700
EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)							(25)

10. Description of Proposed Construction: Concrete foundation and floor slab, steel structure, masonry walls and sloping metal roof. Functional areas include maintenance work area, mechanical and ventilation rooms, office, supplies and parts storage, toilet and tool storage. Includes utilities, pavements, demolition of one metal building and all other necessary support. Includes minimum DoD force protection standards.

Air Conditioning: 12 Tons

11. REQUIREMENT: 395 SM ADEQUATE: 0 SM SUBSTANDARD: 287 SM

FROJECT: Construct a Refueling Vehicle Maintenance Facility.

REQUIREMENT: This project is required to provide an adequate facility to service and repair refueling vehicles. AFOSH STD 127-20 prohibits servicing and repairing fuel servicing tank units and hydrant hose trucks in maintenance shops with other vehicles; therefore, regulations require a separately sited maintenance and repair facility.

CURRENT SITUATION: The existing refueling vehicle maintenance facility is over 40 years old and is totally inadequate to support the refueler fleet at Hurlburt Field. There are no facilities on base that could be used or modified for this requirement.

IMPACT IF NOT PROVIDED: The refueling vehicle maintenance shop will continue to be housed in an inadequate facility which will affect the morale and productivity of the personnel and thereby affect the efficient support of the mission of the 16th Special Operations Wing.

<u>ADDITIONAL:</u> This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options to

					DRAFT 1			
1. COMPONENT		FY 2010 MILITARY	CONSTRU	JCTION PROJECT	DATA	2. DATE		
AIR FORCE		(comp	ıter ge	nerated)	·			
3. INSTALLATIO	AI CINA NO	OCATION		4. PROJECT TI	TLE	į		
HURLBURT FIELI	o, FLORI	DA		REFUELING VEHICLE MAINTENANCE FACILITY				
5. PROGRAM ELI	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	ST (\$000)			
27596	<u> </u>	214-467	F	FTEV043000 1,700				
accomplish this project (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850-884-7701. Refueling Vehicle Maintenance Facility: 395 SM = 4250 SF. JOINT USE CERTIFICATION: This facility can be used by other components on an "as								
avallable bas	sis; now	ever, the scope of	tne pro	ject is based	on air Force r	equirements.		
						•		
				•				
•								

						DRAF	T 1	
. COMPONENT		FY 2010 MILI	TARY CO	NSTRUCTION PR	OJECT	DATA	1	2. DATE
AIR FORCE			compute	r generated)				
3. INSTALLATIO	ON AND LO	CATION		4. PROJE	CT TIT	LE	-	
HURLBURT FIEL	D, FLORII	DA		REFUELII FACILIT		CLE MAINT	ENANC	E
5. PROGRAM EL	EMENT	6. CATEGORY	CODE	7. PROJECT NO	MBER	8. PROJECT	COST	(\$000)
27596		214-46	7	FTEV04300	0		1,70	0
12. SUPPLEMEN	TAL DATA	:						
a. Estimate	d Design	Data:						
(1) Proje	ct to be	accomplished	by des	ign-build pro	cedures	3		
(2) Basis								
		or Definitive .gn Was Most R	_					МО
		_	-cocust)	r oseu -				0
• •		ign Costs						U
(4) Const	TUCTION	Contract Award						
	_		-					
(5) Const	ruction	Start	•					
• •		Start Completion	•					
(6) Const	ruction			was/will be p	erform	ed		NO
(6) Const	ruction y Study/	Completion	alysis '	_			riatio	
(6) Const	ruction y Study/	Completion Life-Cycle and	alysis s proje	_	FISC APPRO		riatio	
(6) Const (7) Energ b. Equipmen	ruction y Study/ nt associ	Completion Life-Cycle and ated with thi	alysis s proje	ect provided i	FISC APPRO	her appropo AL YEAR OPRIATED	riatio	ons: COST

			1
			1
			ı

						DAREL	•
1. COMPONENT USSOCOM		FY 2009 MILITARY	CONSTRU			DATA	2. DATE
			ruer ger				
3. INSTALLATIO	N AND L	OCATION		4. PI	ROJECT TI	TLE	
HURLBURT FIELD, FLORIDA SOF C-						CRAFT APRON	
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PRO					NUMBER	8. PROJECT	COST (\$000)
11205 113-321 FTEV0				EV043	004	6	,200
		9. COS	T ESTI	MATES			
TTEM					OUANTITY	UNIT	Cost
C-130 AIRCRAFT F	PRON						4,718
AIRCRAFT APRON				SM	45,470	. 70	(3,183)
PAVED SHOULDER				SM	1,170	34	(40)
BASE FOR CONCR	ETE HDD 2	ONE A		SM	45,470	32	(1,455)
AIRFIELD MARKI	NGS			LS	l		(40)
SUPPORTING FACIL	ITIES			1	1	1	835
CLEAR/EXCAVATE				SM	45,470	17	(773)
WATER LINE				LS			(62)
SUBTOTAL				1	1	1	5,553
CONTINGENCY	(5.0	%)			1		278
TOTAL CONTRACT (COST			1			5,830
SUPERVISION, IN	SPECTION	AND OVERHEAD (5.7 %)		\	\	332
TOTAL REQUEST						1	6,163
TOTAL REQUEST (ROUNDED)						6,200
EQUIPMENT FROM	OTHER API	PROPRIATIONS (NON-ADD))				(399.0)

10. Description of Proposed Construction: Clear, excavate, place base material and 12 inch concrete pavement. Includes asphalt shoulder, water line for fire protection and all other necessary support.

11. REQUIREMENT: 546,420 SM ADEQUATE: 490,950 SM SUBSTANDARD: 0 SM

PROJECT: Construct C-130 Aircraft Parking Apron.

REQUIREMENT: This project is required to provide additional parking for C-130 aircraft that are scheduled to be based at Hurlburt Field within the next five years. Space is required for loading, unloading, servicing and fueling.

CURRENT SITUATION: Existing aircraft parking apron is not adequate for the beddown of additional AC-130 and MC-130 aircraft scheduled for Hurlburt Field. There is no aircraft pavement that could be used or converted for this requirement.

IMPACT IF NOT PROVIDED: Without this project there will be inadequate space on Hurlburt Field to accept future aircraft. Physical separation will adversely affect mission preparation and execution because of impacts on communications and logistic support.

ADDITIONAL: There is no criteria/scope for this project in Part II of Military Handbook 1190, "Planning Planning and Design Guide." However, this project does meet the criteria/scope specified in Air Force Handbook 32-1084, "Standard Facility Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicated there is only one option that will meet operational requirements. A certificate of exception has been prepared. Base Civil Engineer: William A. Polakowski, Lt Col, USAF, 850/884-7701.

JOINT USE CERTIFICATION: This is an installation utility/infrastructure project, and does not qualify for joint use at this location. However, all tenants on this

					DRAFT 1	
1. COMPONENT		FY 2009 MILITARY C			DATA	2. DATE
USSOCOM		(comput	er gene	rated)		<u> </u>
3. INSTALLATIO	ON AND LO	CATION		4. PROJECT 1	!ITLE	
HURLBURT FIELD	D, FLORII	DA.		SOF C-130 A	IRCRAFT APRON	
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
11205	Ì	6,	200			
12. SUPPLEMEN	TAL DATA	<u></u> :	<u> </u>		•	
a. Estimate	d Design	Data:				
	-					
(1) Statu		m Started				
* *	_	: Cost Estimates use	d to de	velop costs		YES
-		emplete as of 01 JAN		, c_op		120
	ate 35% I	-				
• •		n Complete				
• •	_	dy/Life-Cycle analy	sis was	/will be perf	formed	NO
				_		
(2) Basis						
• •		or Definitive Design				NO
(b) W	here Desi	ign Was Most Recentl	y Used	-		
(3) Total	l Cost (c	a(a) + (b) or (d)) + (e)	:		(\$000)
• •	-	n of Plans and Speci				0
(b) A	ll Other	Design Costs				0
(c) T	otal					0
(d) C	ontract					0 .
(e) I	n-house					0
(4) Cons	truction	Contract Award	-			
(5) Cons	truction	Start				
(6) Cons	truction	Completion				
* Indica	tes comp	letion of Project De	efinitio	n with Param	etric Cost Est	:imate
which	is compa	rable to traditional	L 35% de	sign to ensu	re valid scope	·,
cost a	nd execu	tability.				
b. Equipme	ent assoc	iated with this pro	ject pro	ovided from o	ther appropria	ntions:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
COLLATERAL EQUIPMENT	3400	2010	98
COMMUNICATIONS	3400	2010	301

DRAFT 1

SSOCOM		(Computer (generated)		
. INSTALLATION			4. PROJECT T		
URLBURT FIELD,		In 5		RCRAFT APRON	(4000)
. PROGRAM ELEME	INT 6. CATEGORY	CODE /. P	ROJECT NUMBER	8. PROJECT C	OST (\$000)
11205	113-321	·	FTEV043004	6,	200
nstallation are	benefited by this	project.			
			,		

1. COMPONENT USSOCOM	NT FY 2007 MILITARY CONSTRUCTION PROJECT DATA (computer generated)					2. DATE	
3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
HURLBURT FIELD	, FLORI	DA		SOF S	QUADRON	OPERATIONS,	TALON II
5. PROGRAM ELI	MENT	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)
11205		141-753	FT	EV043	005	5	,982
		9. COS	T ESTI	MATES			
		ITEM		77 /M	OUANTITY	UNIT	COST
SOF SQUADRON OP	erations,	TALON II		1			4,149
SQUADRON OPERA	TIONS			SM	3,000	1,376	(4,128)
FORCE PROTECTI	ON 0 0.54	STRUCTURE COST		LS	ļ	Į į	(21)
SUPPORTING FACE	LITIES			1	1		1,241
UTILITIES				LS		ı	(350)
PAVEMENTS				LS			(364)
COMMUNICATION SYSTEM			LS	Į		(232)	
SITE IMPROVEME	nts			LS			(295)
SUBTOTAL				ł			5,390
CONTINGENCY	(5.0	%)					269
TOTAL CONTRACT	COST			1			5,659
SUPERVISION, IN	SPECTION	AND OVERHEAD	(5.7 %)			1	323
TOTAL REQUEST						-	5,982

10. Description of Proposed Construction: Concrete foundation and floor slab, steel frame, masonry walls and sloped metal roof. Functional areas include administration, planning and briefing areas and storage areas for flying equipment for each crew member. Includes utilities, pavements and all other necessary support. Force protection includes structural reinforcement of exterior walls and fully tempered insulated glass windows.

Air Conditioning: 80 Tons

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

TOTAL REQUEST (ROUNDED)

11. REQUIREMENT: 19,814 SM ADEQUATE: 16,814 SM SUBSTANDARD: 2,107 SM

PROJECT: Construct a Squadron Operations Facility, Talon II.

<u>REQUIREMENT:</u> An adequate facility is required to plan, brief and critique combat crews and direct flight operations. Administrative space is required for the commander and his staff to program and conduct mission briefings and other related command activities. Space is also required to care for, store and issue organizational gear and flying equipment. The size of this facility is based on 10 PAA aircraft. Force protection measures will be incorporated IAW Installation Force Protection Guide.

<u>CURRENT SITUATION:</u> The squadron operations facilities currently being used are inadequate for the additional Talon II aircraft and crews scheduled for Hurlburt Field. There are no facilities on base that could be used or converted for this requirement. Existing facilities only provide 85 percent of the required space.

<u>IMPACT IF NOT PROVIDED:</u> Lack of an adequate squadron operations facility will adversely impact the MC-130 operations and war readiness at Hurlburt Field.

<u>ADDITIONAL:</u> There is no criteria/scope for this project in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, this project does meet the criteria/scope specified in Air Force Handbook 32-1084, "Standard Facility

5,982

(726)

1. COMPONENT USSOCOM	FY 2007 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)					2. DATE
	on AND LOCATION 4. PROJECT TITLE					
HURLBURT FIELD	D, FLORIDA SOF SQUADRON OPERATIONS, TALON II					LON II
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
11205		141-753	F.	PEV043005	5,9	82

Requirements." A preliminary analysis of reasonable options for accomplishing this project (status quo, renovation, upgrade/removal, new construction) was done. It indicated there is only one option that will meet operational requirements. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701.

JOINT USE CERTIFICATION: IAW DoD Financial Management Regulation 7000.14-r, Vol 2B, Chapter 6, Joint Use has been considered. Unilateral construction is recommended based on the special operations mission to be performed in this facility.

1. COMPONENT USSOCOM	FY 2007 MILITARY CONSTRUCTION PROJECT DATA 2. DATE (computer generated)					
3. INSTALLATION AND LOCATION 4. PROJECT TITLE HURLBURT FIELD, FLORIDA SOF SQUADRON OPERATIONS, TALON II					LON II	
5. PROGRAM EL	ement	6. CATEGORY CODE	7. PI	PROJECT NUMBER 8. PROJECT COST (\$00		
11205		141-753	1	FTEV043005	5,	982
12. SUPPLEMENTAL DATA: a. Estimated Design Data: (1) Project to be accomplished by design-build procedures (2) Basis: (a) Standard or Definitive Design ~ NO (b) Where Design Was Most Recently Used ~						
(3) All Other Design Costs					300	
(4) Construction Contract Award					06 DEC	
(5) Const	ruction	Start				07 FEB
(6) Const	ruction	Completion				08 MAY

b. Equipment associated with this project provided from other appropriations:

(7) Energy Study/Life-Cycle analysis was/will be performed

EQUIPMENT NOMENCLATURE	PROCURING APPRO	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
COLLATERAL EQUIPMENT	3400	2008	289
COMMUNICATIONS EQUIPMENT	3400	2008	437

NO

1. COMPONENT	ENT FY 2008 MILITARY CONSTRUCTION PROJECT DATA					2. DATE	
AIR FORCE	AIR FORCE (computer generated)						
3. INSTALLATIO	N AND L	OCATION		4. PI	OJECT TI	TLE	
HURLBURT FIEL	, FLORI	DA		SOF W	veapons r	ELEASE FACILI	TY:
5. PROGRAM ELI	MENT	6. CATEGORY CODE	7. PRO	JECT 1	TUMBER	8. PROJECT (OST (\$000)
11205		215-552	FT	EV043	006	2,	,500
		9. cos	T ESTI	MATES			
ITEM			17/14	OUANTITY	UNIT	COST	
SOF WEAPONS & RELEASE SYSTEM SHOP WEAPONS & RELEASE SYSTEM SHOP (17,500 SF)			SM	1,626	951	1,554 (1,546)	
FORCE PROTECTION @ 0.5% STRUCTURE COST SUPPORTING FACILITIES			LS			(8) 698	
UTILITIES				LS		1	(150)
PAVEMENTS			LS			(140)	
SITE IMPROVEMENTS			LS	1		(130)	
COMMUNICATION SYSTEM			LS			(100)	
DEMOLITION (13,030 SF)			SM	1,211	147	(178)	
SUBTOTAL							2,252
CONTINGENCY	(5.0	%)		1		1	113

10. Description of Proposed Construction: Concrete foundation and floor slab, steel frame, masonry walls and sloping metal roof. Functional areas include gun and ejector unit cleaning room, maintenance offices, dispatch office, bench stock room and storage space for test equipment, spare gun systems and mobility equipment storage in addition to normal shop space. Includes utilities, pavements, demolition of one building and all necessary support. Force protection includes structural reinforcement of exterior walls and fully tempered insulated glass windows.

(5.7 %)

Air Conditioning: 44 Tons

TOTAL CONTRACT COST

TOTAL REQUEST (ROUNDED)

TOTAL REQUEST

SUPERVISION, INSPECTION AND OVERHEAD

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

11. REQUIREMENT: 1,858 SM ADEQUATE: 232 SM SUBSTANDARD: 1,211 SM

PROJECT: Construct a Weapons and Release System Shop.

REQUIREMENT: This project is required to provide an adequate facility for cleaning, overhaul and repair of aircraft weapons release and gun systems. Adequate space is also required for maintenance and dispatch offices, bench stock and test equipment storage, and mobility equipment storage. Force protection measures will be incorporated IAW Installation Force Protection Guide.

CURRENT SITUATION: The existing weapons and release systems shop currently being used is inadequate for the additional aircraft scheduled for Hurlburt Field. There are no facilities on base that could be used or converted for this requirement.

IMPACT IF NOT PROVIDED: Lack of an adequate weapons and release facility will adversely impact the AC-130 operations and war readiness at Hurlburt Field.

ADDITIONAL: There is no criteria/scope for this project in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, this project does meet the criteria/scope specified in Air Force Handbook 32-1084, "Standard Facility

2,365

2,499

2,500

(312.0)

135

1. COMPONENT	FY 2008 MILITARY CONSTRUCTION PROJECT DATA					2. DATE	
AIR FORCE	(computer generated)						
3. INSTALLATION HURLBURT FIELD			4. PROJECT TITLE SOF WEAPONS RELEASE FACILITY				
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)	
11205		215-552	FTEV043006		2,5	00	

Requirements." All known alternative options were considered during the development of this project. No other option could meet the mission requirement; therefore, no economic analysis was needed or performed. A certificate of exception has been prepared. Base Civil Engineer: Jeffery L. Pitchford, Lt Col, USAF, 850/884-7701.

JOINT USE CERTIFICATION: IAW DoD Financial Management Regulation 7000.14-R, Vol 2B, Chapter 6, Joint Use has been considered. Unilateral construction is recommended based on the special operations mission to be performed in this facility.

FY 2008 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
(computer generated)					
ON AND LOCATION 4. PROJECT TITLE					
LD, FLORIDA SOF WEAPONS RELEASE FACILITY					ITY
MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
l l	215-552	FT	EV043006	2,	500
	N AND LOCE	(comput N AND LOCATION , FLORIDA MENT 6. CATEGORY CODE	(computer general name of the computer genera	(computer generated) N AND LOCATION , FLORIDA SOF WEAPONS MENT 6. CATEGORY CODE 7. PROJECT NUMBER	(computer generated) N AND LOCATION 4. PROJECT TITLE SOF WEAPONS RELEASE FACIL MENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT CO

12. SUPPLEMENTAL DATA:

a. Estimated Design Data:

- (1) Status:
 - (a) Date Design Started
 - (b) Parametric Cost Estimates used to develop costs
- * (c) Percent Complete as of 01 JAN 2007
- * (d) Date 35% Designed
 - (e) Date Design Complete
 - (f) Energy Study/Life-Cycle analysis was/will be performed

NO

YES

(2) Basis:

(a) Standard or Definitive Design -

МO

- (b) Where Design Was Most Recently Used -
- (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000)

 (a) Production of Plans and Specifications 0

 (b) All Other Design Costs 0

 (c) Total 0

 (d) Contract 0

 (e) In-house 0
- (4) Construction Contract Award
- (5) Construction Start
- (6) Construction Completion
- * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability.
- b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
COMMUNICATIONS	3400	2009	216
SYSTEMS FURNITURE	3400	2009	96

							
1. COMPONENT	PONENT FY 2009 MILITARY CONSTRUCTION PROJECT DATA						
USSOCOM (computer generated)							
3. INSTALLATIO	I GNA NO	OCATION		4. PF	OJECT TI	TLE	-
HURLBURT FIELI	, FLORI	DA		SOF S	URVIVAL	EQUIPMENT SHO)P
5. PROGRAM ELI	EMENT	6. CATEGORY CODE	7. PRO	JECT N	TUMBER	8. PROJECT C	OST (\$000)
11205		218-852	F	EV043	007	2,	, 900
		9. cos:	T ESTI	MATES			
						UNIT	COST
		TTEM		U/M	QUANTITY		
SOF - CONSTRUCT	SURVIVAL	EQUIPMENT SHOP					2,067
SURVIVAL EQUIP	MENT SHO	•		SM	1,460	1,409	(2,057)
FORCE PROTECTI	ON@ 0.5%	STRUCTURE COST		LS		1	(10)
SUPPORTING FACI	LITIES			-	ļ		524
UTILITIES				LS			(125)
PAVEMENTS				LS			(75)
SITE IMPROVEME	nts			LS	1		(75)
COMMUNICATIONS	}			LS			(130)
DEMOLITION				М2	929	128	(119)
SUBTOTAL					ļ		2,591
CONTINGENCY (5.0 %)				1			130
TOTAL CONTRACT COST				-	1	1	2,721
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %)					1		155
TOTAL REQUEST							2,876
TOTAL REQUEST (ROUNDED)				1	1	(2,900
EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)							(356.0)

10. Description of Proposed Construction: Concrete foundation and floor slab, steel frame, masonry walls and sloping metal roof. Functional areas include personnel parachute inspection and packing room, parachute washing room and drying tower, sewing room, storage areas for survival equipment and flotation equipment, flotation room for inspection, inflation and repacking rubberized survival equipment, and chemical use room for cleaning components, repairing anti-exposure suites and gluing rubberized items. Includes utilities, pavements, site improvements, communications, force protection, and demolition of one building and all necessary support.

Air Conditioning: 40 Tons

11. REQUIREMENT: 1,460 SM ADEQUATE: 0 SM SUBSTANDARD: 929 SM

PROJECT: Construct Survival Equipment Shop

REQUIREMENT: This project is required to provide an adequate facility for packing, inspecting, washing, and drying personnel parachutes. Adequate space is also required for a sewing room, storage areas for survival equipment and flotation equipment, inspection, inflation and repacking of rubberized survival equipment and a chemical use room. Force protection measures will be incorporated IAW Installation Force Protection Guide.

CURRENT SITUATION: The current facility is over 50 years old and is to small to accommodate current and future mission requirements. There are no facilities on base that could be used or converted for this requirement.

IMPACT IF NOT PROVIDED: Lack of an adequate survival equipment shop will adversely impact the wings capability to supply aircraft crews with appropriate gear to do their mission. Thus, negatively impacting the readiness at Hurlburt Field.

1. COMPONENT	FY 2009 MILITA	F DATA 2. DATE				
USSOCOM	(computer generated)					
3. INSTALLATION	ITLE					
HURLBURT FIELD	RLBURT FIELD, FLORIDA SOF SURVIVAL EQUIPMENT SHOP					
5. PROGRAM ELE	MENT 6. CATEGORY COL	E 7. PROJECT NUMBER	8. PROJECT COST (\$000)			
11205	218-852	FTEV043007	2,900			

ADDITIONAL: There is no criteria/scope for this project in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, this project does meet the criteria/scope specified in Air Force Handbook 32-1084, "Standard Facility Requirements." All known alternative options were considered during the development of this project. No other option could meet the mission requirement; therefore, no economic analysis was needed or performed. A certificate of exception has been prepared. Base Civil Engineer: William a. Kolakowski, Lt Col USAF, 850/884-7701.

JOINT USE CERTIFICATION: IAW DOD Financial Management Regulation 7000.14-R, Vol 2B, Chapter 6 Joint Use has been considered. Unilateral construction is recommended based on the special operations mission to be performed in this facility.

1. COMPONENT USSOCOM	FY 2009 MILITARY CONSTRUCTION PROJECT DATA (computer generated)					2. DATE
3. INSTALLATIO HURLBURT FIELD				4. PROJECT S	PITLE L EQUIPMENT S	нор
5. PROGRAM ELI 11205	MENT	6. CATEGORY CODE 218-852		JECT NUMBER EV043007	8. PROJECT C	COST (\$000)
12. SUPPLEMENT		-				
(b) Pa	te Desig rametri	n Started Cost Estimates used Complete as of 01 JAN		velop costs		YES

- * (d) Date 35% Designed
 - (e) Date Design Complete
 - (f) Energy Study/Life-Cycle analysis was/will be performed

NO

- (2) Basis:
 - (a) Standard or Definitive Design -

NO

(b) Where Design Was Most Recently Used -

(3) Total Cost (c) = (a) + (b) or (d) + (e):	(\$000)
(a) Production of Plans and Specifications	0
(b) All Other Design Costs	0
(c) Total	0
(d) Contract	0
(e) In-house	0

- (4) Construction Contract Award
- (5) Construction Start
- (6) Construction Completion
- * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability.
- b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
PREWIRED WORKSTATIONS	3400	2010	258
COMMUNICATIONS	3400	2010	98

1. COMPONENT FY 2010 MILITARY CONSTRUCTION PROJECT DATA USSOCOM (computer generated)							2. DATE
3. INSTALLATIO	3. INSTALLATION AND LOCATION 4. PROJECT TITLE						_
HURLBURT FIELD				SOF I	ASH-21 M	AINTENANCE FA	CTLTTY
5. PROGRAM ELE	<u> </u>	6. CATEGORY CODE	7 000			8. PROJECT C	
J. PROGRAM ELE	HALLA I	6. CATEGORI CODE	, FEC	OECI 1	NOMBER	6. PRODECT C	031 (\$000)
11205		211-154	F:	rev043	800	3,	250
		9. cos	T ESTI	MATES			
			•			UNIT	COST
		<u>ITEM</u>		U/M	QUANTITY	<u> </u>	
DASH-21 MAINTENA	NACE SHO	P		1			2,099
AIRCRAFT SUPPOI	RT SHOP			SM	1,394	1,427	(1,989)
FORCE PROTECTION	ON/ANTITI	ERRORISM (0.5%)		LS	İ	1	(10)
SUSTAINABILITY	CONSTRUC	CTION		LS		1	(99)
SUPPORTING FACII	ITIES			-	1		834
UTILITIES				LS	İ		(200)
PAVEMENTS				LS		i i	(215)
SITE IMPROVEME	nts			LS		1	(200)
COMMUNICATION	System			LS			(80)
DEMOLITION				SM	1,392	100	(139)
SUBTOTAL					Ī		2,933
CONTINGENCY (5.0 %)					1	1	147
TOTAL CONTRACT COST				1			3,079
SUPERVISION, INSPECTION AND OVERHEAD (5.7 %)				1			176
TOTAL REQUEST						Į į	3,255
TOTAL REQUEST (ROUNDED)							3,250

10. Description of Proposed Construction: Concrete foundation and floor slab, steel structure, masonry walls and sloping metal roof. Functional areas include flight line assigned Dash-21 equipment, flight line vehicle parking, tool kit, tool room and bench stock, maintenance and storage of non-powered support equipment and locker space. Includes utilities, pavements, demolition of one metal building (1392 SM) and all other necessary support. Includes minimum DoD force protection standards.

Air Conditioning: 15 Tons

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

11. REQUIREMENT: 5,596 SM ADEQUATE: 4,202 SM SUBSTANDARD: 0 SM

PROJECT: Construct a Dash-21 Maintenance Facility.

REQUIREMENT: This project is required to provide an adequate facility for maintenance and storage of flight line assigned Dash-21 equipment and non-powered support equipment, including tool and bench stock storage and locker space. Force protection measures will be incorporated IAW Installation Force Protection Standards.

CURRENT SITUATION: The existing Dash-21 facility is over 40 years old and inadequate to support the mission of the 16th Special Operations Wing. The existing building, sited on the flight line, is also in the way of construction of a new, much needed C-130 maintenance hangar. There are no facilities on base that could be used or modified for this requirement.

IMPACT IF NOT PROVIDED: Without this project the base will not be able to adequately support the flying mission of the 16th SOW.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-

(470.0)

1. COMPONENT USSOCOM	FY 2010 MILITARY CONSTRUCTION PROJECT DATA (computer generated)					2. DATE
3. INSTALLATION AND LOCATION 4. PROJECT TITLE HURLBURT FIELD, FLORIDA SOF DASH-21 MAINTENANCE FACILITY						ILITY
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	ST (\$000)
11205		211-154	F.	TEV043008	3,2	50

1084, "Facility Requirements." A preliminary analysis of reasonable options (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850-884-7701. Dash-21 Maintenance Facility: 1394 SM = 15000 SF.

JOINT USE CERTIFICATION: Mission requirement, operational considerations, and location are incompatible with use by other components.

1. COMPONENT USSOCOM	FY 2010 MILITARY CONSTRUCTION PROJECT DATA (computer generated)					
3. INSTALLATION AND LOCATION 4. PROJECT TITLE HURLBURT FIELD, FLORIDA SOF DASH-21 MAINTENANCE I					acility	
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	OST (\$000)
11205	Ì	211~154	FTEV043008		3,250	

12. SUPPLEMENTAL DATA:

- a. Estimated Design Data:
 - (1) Status:
 - (a) Date Design Started
 - (b) Parametric Cost Estimates used to develop costs

YES

- * (c) Percent Complete as of 01 JAN 2009
- * (d) Date 35% Designed
 - (e) Date Design Complete
 - (f) Energy Study/Life-Cycle analysis was/will be performed

NO

(2) Basis:

(a) Standard or Definitive Design -

NO

- (b) Where Design Was Most Recently Used -
- (3) Total Cost (c) = (a) + (b) or (d) + (e):
 (a) Production of Plans and Specifications
 (b) All Other Design Costs

(\$000) 0

(b) All Other Design Costs(c) Total

0

(d) Contract

0

(e) In-house

0

- (4) Construction Contract Award
- (5) Construction Start
- (6) Construction Completion
- * Indicates completion of Project Definition with Parametric Cost Estimate which is comparable to traditional 35% design to ensure valid scope, cost and executability.
- b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	Cost (\$000)
COLLATERAL EQUIPMENT	3400	2011	200
COMMUNICATIONS	3400	2011	270

,		

							
1. COMPONENT		FY 2010 MILITARY	CONSTRU	CTION	PROJECT	DATA	2. DATE
AIR FORCE (computer generated)							
3. INSTALLATIO	N AND L	OCATION		4. PI	ROJECT TI	TLE	
HURLBURT FIELD	, FLORI	DA .		SOF 1	aintenan	CE STORAGE FI	ACILITY
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	JECT 1	TUMBER	8. PROJECT	COST (\$000)
11205		442-758	F	EV043	009	1	,100
		9. cos	T ESTI	MATES			
		TTEM		17/M	OUANTITY	UNIT	COST
AIRCRAFT MAINTENANCE STORAGE FACILITY MAINTENANACE STORAGE FORCE PROTECTION/ANTITERRORISM (0.5%)			SM	870	800	699 (696) (3)	
SUPPORTING FACILITIES UTILITIES				LS			287 (60) (60)
PAVEMENTS SITE IMPROVEMENTS COMMUNICATION SYSTEM				LS			(50)
DEMOLITION SISTEM				SM	870	100	(87)
SUBTOTAL							. 986
CONTINGENCY (5.0 %)							49
TOTAL CONTRACT COST					}	1	1,036
SUPERVISION, INSPECTION AND OVERHEAD . (5.7 %)							59
TOTAL REQUEST							1,095

10. Description of Proposed Construction: Concrete foundation and floor slab, steel structure, masonry walls and sloping metal roof. Functional areas include storage of aircraft maintenance parts and materials, office space and bathroom for illities. Includes utilities, pavements, demolition of one materials (270 34) and all other necessary support. Includes minimum DoD force protection standards.

Air Conditioning: 6 Tons

TOTAL REQUEST (ROUNDED)

11. REQUIREMENT: 23,784 SM

EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)

ADEQUATE: 22,914 SM

SUBSTANDARD: 870 SM

PROJECT: Construct an Aircraft Maintenance Storage Facility.

REQUIREMENT: This project is required to provide an adequate facility for storage and issue of parts and materials located near where aircraft maintenanace is being performed. Force protection measures will be incorporated IAW Installation Force Protection Standards.

CURRENT SITUATION: The existing maintenanace storage facility is in the way of construction of a new, much needed C-130 maintenance hangar. There are no facilities on base that could be used or modified for this requirement.

IMPACT IF NOT PROVIDED: Without this project the base will not be able to adequately support the flying mission of the 16th Special Operations Wing.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850-884-7701. Maintenance Storage Facility: 870 SM = 9360 SF.

1,100

(150.0)

1. COMPONENT	COMPONENT FY 2010 MILITARY CONSTRUCTION PROJECT DATA					
AIR FORCE	IR FORCE (computer generated)					
3. INSTALLATIO	3. INSTALLATION AND LOCATION 4. PROJECT TITLE					
HURLBURT FIELD	HURLBURT FIELD, FLORIDA SOF MAINTENANCE STORAGE FACILITY					
5. PROGRAM EL	5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000)					ST (\$000)
11205	\	442-758	FTEV043009 1,100			
12. SUPPLEMEN	TAL DATA:	1				
a. Estimate	d Design	Data:				
(1) Statu	s:					
(a) Da	ite Desig	n Started				
(b) Pa	rametric	Cost Estimates used	d to dev	relop costs		YES
* (c) Pe	ercent Co	mplete as of 01 JAN	2009			
* (d) Da	ate 35% D	esigned				

- (2) Basis:
 - (a) Standard or Definitive Design -

NO

NO

- (b) Where Design Was Most Recently Used -
- (3) Total Cost (c) = (a) + (b) or (d) + (e): (\$000)

 (a) Production of Plans and Specifications 0

 (b) All Other Design Costs 0

 (c) Total 0

 (d) Contract 0

 (e) In-house 0

(f) Energy Study/Life-Cycle analysis was/will be performed

(4) Construction Contract Award

(e) Date Design Complete

- (5) Construction Start
- (6) Construction Completion
- * Indicates completion of Project Definition with Parametric Cost Ently to which is comparable to traditional 35% design to ensure valid shape, cost and executability.
- b. Equipment associated with this project provided from other appropriations:

EQUIPMENT NOMENCLATURE	PROCURING APPROPRIATION	FISCAL YEAR APPROPRIATED OR REQUESTED	COST (\$000)
COLLATERAL EQUIPMENT	3400	2011	100
COMMUNICATIONS	3400	2011	50

							<u>-</u>
1. COMPONENT AIR FORCE		FY 2011 MILITARY				DATA	2. DATE
AIR FURCE	L	(Comb.	iter gei	erate	<u></u>		
3. INSTALLATIO	I DNA NO	OCATION		4. PI	ROJECT TI	LTE	
HURLBURT FIELD	, FLORI	DA		SOF	C-130 MAIN	NTENANCE HAN	GAR
5. PROGRAM ELE	OGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT			JECT 1	NUMBER	8. PROJECT	COST (\$000)
11205	11205 211-111 FTEV043010 9,			,100			
		9. cos	T ESTI	MATES		 	
				$\overline{1}$		UNIT	COST
		ITEM		_U/M	QUANTITY	·	
SOF C-130 MAINTE	ENANCE HA	MGAR					6,636
HIGH BAY HANGA	R			SM	2,415	1,970	(4,758)
AIRCRAFT MAINT	ENANCE U	NIT		SM	1,115	1,655	(1,845)
FORCE PROTECTI	on/antiti	ERRORISM (0.05%)		LS		ļ	(33)
SUPPORTING FACI	LITIES			-			1,520
UTILITIES				rs			(390)
PAVEMENTS				LS	1	1	(425)
SITE IMPROVEME	nts			LS	Ì	1	(420)
COMMUNICATION	System			IS	ł		(285)
SUBTOTAL							8,156
CONTINGENCY	(5.0	%)		})		408
TOTAL CONTRACT COST			1	1		8,564	
SUPERVISION, IN	SPECTION	AND OVERHEAD (5.7 %)		1	1	488
TOTAL REQUEST							9,052
TOTAL REQUEST (ROUNDED)						9,100
EQUIPMENT FROM	OTHER AP	PROPRIMMIONS (NON-ADD)	+		1	1	(85)
10 Banadas					- 1		

10. Description of Proposed Construction: Reinforced constitute footings, for dation and floor slab, structural steel frame, insulated metal walls and roof, fire protection, ramp and taxivay improvements, utilizing the other name. Includes minimum DoD force products a standard in.

Air Conditioning: 30 Tons

11. REQUIREMENT: SM ADEQUATE: SM

SUBSTANDARD: SM

PROJECT: Construct a C-130 Aircraft Maintenance Hangar.

REQUIREMENT: An adequate facility, properly sized and configured, for aircraft maintenance, individually unique aircraft test and evaluation of aircraft systems, weapon systems and high-priority test programs. This facility will provide indoor aircraft jacking, flight control replacement, rigging and other required heavy maintenance. This hangar will also house support sections which include bench stock, tools, precision maintenance equipment lab (FMEL), avionics maintenance and a dedicated supply support unit. Mobility taskings necessitate the storage of war readiness kits close to the aircraft and maintenance area. Force protection measures will be incorporated IAW Installation Force Protection Standards.

CURRENT SITUATION: Individual aircraft maintenance facilities are adequate but too few. Specifically, there are only 2 aircraft maintenance hangars on base for 31 C-130 aircraft. An additional 7 C-130 aircraft are scheduled to be bedded down at Hurlburt Field by 2010. With these additional aircraft there will not be adequate hangar space on base to perform required periodic maintenance.

IMPACT IF NOT PROVIDED: Without this project the 16th Special Operations Wing's mission readiness will be degraded if there is not an adequate maintenance capability for C-130

DRAFT 1

1. COMPONENT	FY 2011 MILITARY CONSTRUCTION PROJECT DATA					2. DATE	
AIR FORCE		(computer generated)					
3. INSTALLATION	3. INSTALLATION AND LOCATION 4. PROJECT TITLE						
HURLBURT FIELD	, FLORIDA	A	1	SOF C-130 MA	INTENANCE HANGAI	R	
5. PROGRAM ELE	MENT	6. CATEGORY CODE	7. PRO	ST (\$000)			
11205		211-111	FTEV043010 9,100				

aircraft.

ADDITIONAL: There is no criteria/scope for this project in Part II of Military Handbook 1190, "Facility Planning and Design Guide." However, this project does meet the criteria/scope in Air Force Handbook 32-1084, "Facility Requirements." A preliminary analysis of reasonable options (status quo, renovation, upgrade/removal, new construction) was done. It indicates that there is only one option that will meet the operational requirement. A certificate of exception has been prepared. Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701. C-130 Aircraft Maintenance Hangar: 3530 SM = 38,000 SF.

JOINT USE CERTIFICATION: Mission requirement, operational considerations, and location are incompatible with use by other components.

1. COMPONENT		FY 2011 MILITAR	Y CONSTRUCTION	N PROJECT	DATA	2. DATE
AIR FORCE		(com	puter generat	ed)		
3. INSTALLATIO	ON AND LOC	CATION	4.	PROJECT 1	PITLE	
HURLBURT FIEL	D, FLORIDA	1	so	F C-130 M	AINTENANCE HAN	IGAR
5. PROGRAM EL	EMENT	6. CATEGORY CO	DE 7. PROJEC	T NUMBER	8. PROJECT CO	ST (\$000)
11205	<u>j</u>	211-111	FTEV0	43010	9,	,100
12. SUPPLEMEN	TAL DATA:		-,, <u></u> ,-	, 	<u> </u>	
a. Estimate	ed Design	Data:				*
(1) Statu	_					
• •	ate Design	Started				
	_	Cost Estimates	used to devel	op costs		YES
* (c) Pe	ercent Com	plete as of 01	JAN 2010			
* (d) D:	ate 35% De	esigned				
	ate Design				_	
(f) E	nergy Stud	ly/Life-Cycle an	alysis was/wi	ll be perf	cormed	NO
(2) Basis	s:					
(a) S	tandard or	: Definitive Des	ign -		•	NO
(b) W	here Desig	yn Was Most Rece	ently Used -			
(3) Total	l Cost (c)	= (a) + (b) or	(d) + (e):			(\$000)
•		of Plans and Sp				0
* -		Design Costs	•			0
(c) T	otal	_				0
• •	contract				ā	0
(e) I	n-house					0
(4) Cons	truction C	Contract Award				
(5) Cons	truction 8	Start				
(6) Cons	truction (Completion				
* Indica	tes comple	etion of Project	- Definition :	dith Darom	at it hast has	·*n
		this to tradi				
	ind executi				,	•
		-				
		ated with this	reject provid	dod from a	than appropri	tions:
D ROLLING	anc assuct	area with mits	brolege broate	ver truit o	mier abbrohtre	z ULUMA.
b. Equipme				FIS	CAL YEAR	
b. Equipme						
			PROCURING		ROPRIATED	COST
	NT NOMENCI	ATURE	PROCURING APPROPRIATION		ROPRIATED REQUESTED	COST (\$000)
EQUIPME	nt nomenci Ral equipm				_	_

			1
			1
			1
			1
			1
			1
	,		I
			ı
			'
			1
			1
			1

SUPPORTING FACILITIES UTILITIES LS (5) PAVEMENTS LS (5)								<u> </u>
3. INSTALLATION AND LOCATION HURLBURT FIELD, FLORIDA 5. PROGRAM ELEMENT 6. CATEGORY CODE 9. COST FIEVO43016 9. COST U/M QUANTITY FRIMARY FACILITIES WHSE SUPACQUIP BSE UTILITIES UTILITIES EAVEMENTS SUBTOTAL TOTAL CONTRACT COST SUPERVISION, INSPECTION AND OVERHEAD 4. PROJECT TITLE SUPPLY WAREHOUSE SUPPLY WAREHOUSE 8. PROJECT COST (\$000) 20 UNIT COST UNIT COST UNIT COST IS SM 1 70 (0) 15 (5) 15 (5) 15 15 15 15 15 16			-		_		DATA	2. DATE
SUPPLY WAREHOUSE SUPPLY WARE	AIR FORCE	L	(comt	outer ge	nerate	ed)		
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000) 27596 442-758 FTEV043016 20 9. COST ESTIMATES U/M QUANTITY UNIT COST PRIMARY FACILITIES 0 WHSE SUPECUIP BSE SM 1 70 (0) SUPPORTING FACILITIES 15 UTILITIES 15 PAVEMENTS 15 SITE IMPROVEMENTS 15 SUBTOTAL CONTRACT COST 15 SUPERVISION, INSPECTION AND OVERHEAD (6.5 %) 1 TOTAL REQUEST 16	3. INSTALLATIO	ON AND LA	CATION		4. PI	ROJECT TI	PLE	
27596 442-758 FTEV043016 20	HURLBURT FIELD	, FLORI	DA		SUPPI	LY WAREHOU	JSE	
9. COST ESTIMATES ITEM	5. PROGRAM ELI	MENT	6. CATEGORY CODE	7. PRO	JECT 1	NUMBER	8. PROJECT	COST (\$000)
TOTAL REQUEST D/M QUANTITY UNIT COST UNIT COST UNIT COST UNIT COST UNIT COST UNIT COST UNIT COST UNIT COST UNIT COST UNIT COST UNIT COST INIT O (0) (0) (0) (0) (0) (0) (0)	27596		442-758	F	FEV043	016		20
TITEM U/M QUANTITY PRIMARY FACILITIES WHSE SUPSEQUIP BSE SM 1 70 (0) SUPPORTING FACILITIES UTILITIES LS (5) PAVEMENTS SITE IMPROVEMENTS SUBTOTAL TOTAL CONTRACT COST SUPPRIMARY FACILITIES 15 (5) 15 15 15 15 16			9. co	ST ESTI	MATES			
PRIMARY FACILITIES WHSE SUPSEQUIP BSE SM 1 70 (0) SUPPORTING FACILITIES UTILITIES LS (5) PAVEMENTS SITE IMPROVEMENTS SUBTOTAL TOTAL CONTRACT COST SUPPRISION, INSPECTION AND OVERHEAD (6.5%) TOTAL REQUEST O (0) SM 1 70 (0) (5) 15 (5)			TREM		77 /M	OTTANISTINA		COST
WHSE SUPAREQUIP RSE SIMPORTING FACILITIES UTILITIES LS PAVEMENTS SITE IMPROVEMENTS LS SUBTOTAL TOTAL CONTRACT COST SUPERVISION, INSPECTION AND OVERHEAD TOTAL REQUEST SM 1 70 (0) (5) (5) (5) (5) 15					10/10	WOOD TE		
SUPPORTING FACILITIES UTILITIES PAVEMENTS SITE IMPROVEMENTS SUBTOTAL TOTAL CONTRACT COST SUPERVISION, INSPECTION AND OVERHEAD (6.5 %) TOTAL REQUEST 15	PRIMARY FACILITY	TES						0
UTILITIES PAVEMENTS LS SITE IMPROVEMENTS LS SUBTOTAL TOTAL CONTRACT COST SUPERVISION, INSPECTION AND OVERHEAD (6.5%) TOTAL REQUEST LS (5) (5) (5) (5) (5) (5) (1) (6.5%)	WHSE SUP&EQUIP	BSE			SM	1	70	(0)
PAVEMENTS SITE IMPROVEMENTS LS (5) SUBTOTAL TOTAL CONTRACT COST SUPERVISION, INSPECTION AND OVERHEAD (6.5 %) TOTAL REQUEST LS (5) 15 15	SUPPORTING FACI	LITIES						15
SITE IMPROVEMENTS SUBTOTAL TOTAL CONTRACT COST SUPERVISION, INSPECTION AND OVERHEAD (6.5 %) TOTAL REQUEST LS (5) 15 16	UTILITIES				LS			(5)
SUBTOTAL TOTAL CONTRACT COST SUPERVISION, INSPECTION AND OVERHEAD (6.5 %) TOTAL REQUEST 15 16	PAVEMENTS				LS		1	(5)
TOTAL CONTRACT COST SUPERVISION, INSPECTION AND OVERHEAD (6.5 %) TOTAL REQUEST 15 16	SITE IMPROVEME	nts			LS	1		(5)
SUPERVISION, INSPECTION AND OVERHEAD (6.5 %) TOTAL REQUEST 16	SUBTOTAL							15
TOTAL REQUEST 16	TOTAL CONTRACT	COST				}		15
	SUPERVISION, IN	SPECTION	AND OVERHEAD	(6.5 %)	-	1		1
TOTAL REQUEST (ROUNDED)	TOTAL REQUEST				}	}		16
	TOTAL REQUEST (ROUNDED)			<u> </u>			20

10. Description of Proposed Construction: Construct new 20,158 SM supply warehouse.

11. REQUIREMENT:

ADEQUATE:

SUBSTANDARD:

PROJECT: Construct new 20,158 SM supply warehouse.

REQUIREMENT: Construct new 20,158 SM supply warehouse.

1. COMPONENT		FY 2010 MILITARY CO	ONSTRUCT	ION PROJECT	DATA	2. DATE	
AIR FORCE	<u> </u>	(compute	er gener	ated)		<u> </u>	
3. INSTALLATI	ON AND LO	OCATION		4. PROJECT T	TITLE		
HURLBURT FIEL	D, FLORI	DA		SUPPLY WAREH	IOUSE		
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PROJ	ect number	8. PROJECT CO	ST (\$000)	
27596		442-758	FTE	W043016	:	20	
12. SUPPLEMEN	TAL DATA	·:					
a. Estimate	ed Design	Data:			-		
(1) Statu	15:						
,	(a) Date Design Started						
1		c Cost Estimates used complete as of 01 JAN		erob costs		YES	
1	ate 35% I	_	2003				
1		gn Complete					
(f) E	nergy St	udy/Life-Cycle analy:	sis was/	will be perf	ormed	NO	
(2) Basi	s:						
1		or Definitive Design			•	NO	
(a) W	nere bes	ign Was Most Recentl	y usea -	•			
1	-	c) = (a) + (b) or (d)				(\$000)	
1		n of Plans and Speci Design Costs	fication	ıs		0	
(B) A		besign Costs				0	
1	Contract					0	
,	n-house					0	
(4) Cons	truction	Contract Award					
(5) Cons	truction	Start					
(6) Cons	truction	Completion					
* Indica	ites comp	oletion of Project De	finition	with Parame	etric Cost Est	imate	
1	_	rable to traditional	. 35% des	sign to ensua	re valid scope	,	
cost a	and execu	tability.					
b. Equipme	ent assoc	ciated with this proj	ect pro	vided from of	ther appropria	tions:	
	٠.						
}						-	
\							
1							
1							
\							
1							

						DRAFI I					
1. COMPONENT AIR FORCE											
				1							
3. INSTALLATIO				ł	1. PROJECT T		į				
HURLBURT FIELD	D, FLORID	A	·	1	FAMILY CAMP	ING FACILITY	·				
5. PROGRAM EL	. PROGRAM ELEMENT 6. CATEGORY CODE 7. PRO				CT NUMBER	8. PROJECT	COST (\$000)				
NAF	i	750-611	F	ľE	V045003	ļ	600				
		9. COST	ESTIMA:	re:							
		ITEM	ַ ע	м	QUANTITY	UNIT	COST				
FAMILY CAMPING I	FACILITY, 1	РН 3 ·					215				
FAMCAMP			V ₁	۱,	24	2,922	(70)				
SERVICE BUILDI	ng		S	4	50	2,600	(130)				
PICNIC PAVILIC)N		E	A	1	15,000	(15)				
SUPPORTING FACI	LITIES						320				
SITE IMPROVEME	nts/enviro	NMENTAL IMPACT	} L	s Į			(85)				
ELECTRIC, WATE	er & Sewer	SERVICE	L	s		'	(95)				
PAVEMENTS			s	м	2,200	34	(75 }				
UPGRADE ELECTI	RIC SITE OF	ITLETS	L	s			(50)				
RELOCATE SITE	SEWER CON	TECTIONS	r	s			(15)				
SUBTOTAL			1				535				
CONTINGENCY	(5.0 %)		- 1				27				
TOTAL CONTRACT	COST					1	562				
SUPERVISION, IN	SPECTION A	ND OVERHEAD (6.	.0 %}			{	34				
TOTAL REQUEST	TOTAL REQUEST						595				
TOTAL REQUEST ((ROUNDED)						600				
UNFUNDED DESIGN	r					\	(60)				
MANAGEMENT FEES	(2.5%)		1			1	(15)				
EQUIPMENT FROM	OTHER APPR	ROPRIATIONS (NON-ADD)					(49)				

10. Description of Proposed Work: Concrete pads with water, sewer and electrical connections for each camping vehicle parking space. Includes a service building with toilets, lavatories, showers, service sink, washers and dryers and picnic pavilion. Pave access road, upgrade electrical site outlets at 19 sites and relocate site sewer connections at 26 sites of phase 1 of the FAMCAMP.

11. REQUIREMENT: 74 VP ADEQUATE: 50 VP SUBSTANDARD: 0 VP

PROJECT: Construct a 24 station Family Camping Facility.

REQUIREMENT: An adequate facility is required that will accommodate 24 recreational vehicles (RVs) with water, electricity, sewage disposal, a service building and a congreation (picnic) area. Individual sites must be selected and developed so as to retain the natural environment yet permit managerial observation and control. Selected sites of phase 1 of the FAMCAMP need to be upgraded to current standards.

CURRENT SITUATION: Hurlburt Field is located on US Highway 98 which is the major coastal route between the Texas gulf coast and the Florida peninsula. This, coupled with the warm southern climate, makes this area a prime location for vacationers who are in transit or desire to remain in the area for a few days. Only two similar government owned facilities exist within several hours of Hurlburt Field, therefore this project is needed to provide a connecting link with facilities outside this area. Utilization of

1. COMPONENT	FY 2005 MILITARY CONSTRUCTION PROJECT DATA 2. DATE						
AIR FORCE	(computer generated)						
3. INSTALLATION AND HURLBURT FIELD, FLO		4. PROJECT ADAL COMMAN					
5. PROGRAM ELEMENT	6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)				
27596	610-913 FTEV043020 1,358						

9. COST ESTIMATES

9. COST ESTIM	MIED			
ITEM	U/M	QUANTITY	UNIT	COST
ADAL COMMAND POST				1,049
ALTER COMMAND POST (5,527 SF)	SM	513	200	(103)
SRC ADDITION (3,115 SF)	SM	290	3,245	(941)
FORCE PROTECTION/ANTITERRORISM (0.5%)	LS			(5)
SUPPORTING FACILITIES			İ	175
PAVEMENTS	LS			(36)
SITE IMPROVEMENTS	LS			(24)
UTILITIES	LS	1		(46)
GENERATOR/UPS SYSTEM	LS	1		(69)
SUBTOTAL				1,224
CONTINGENCY (5.0%)				61
TOTAL CONTRACT COST		\ \	l	1,285
SUPERVISION, INSPECTION AND OVERHEAD (5.7%)			<u> </u> _	73
TOTAL REQUEST		1		1,358
EQUIPMENT FROM OTHER APPROPRIATIONS (NON-ADD)			1	(100.0)

10. Description of Proposed Construction: Reinforced concrete foundation, masonry walls, concrete inner roof and sloping metal roof. Functional areas include Survival Recovery Center (SRC), Security Forces Control Center (SFCC) and Fire Station Control Center (FSCC). Alter exterior walls and roof of Command Post. Includes utilities, parking, communication system, back-up generator, UPS system and all necessary support. Comply with DoD force protection requirements per unified facilities criteria.

Air Conditioning: 20 KW.

11. Requirement: 1027 SM Adequate: 737 SM Substandard: 0 SM PROJECT: Add/Alter Command Post. (Current Mission).

REQUIREMENT: This project is required to consolidate command and control operations of the 16th Special Operations Wing (SOW). As a result of Hurricane Ivan and its Category 4 winds (135+ mph), it was clearly evident the 16 SOW does not have adequate command and control ride-out facilities capable of withstanding a Category 4 Hurricane. Due to the structural limitations of the existing Command Post and other control centers, the Wing Commander was forced to relocate his senior staff to 4 separate facilities for Hurricane Ivan. This relocation placed 50 senior staff at personal risk and made command and control of preparatory/recovery efforts extremely difficult. Consolidating all these operations into the Command Post will significantly enhance the Battle Staff's ability to respond to crisis activities as they occur. It will provide the Wing Commander with immediate unrestricted access to his "on-call" Special Operations Command aircraft, emergency responders, 41 Unit Control Centers, higher headquarters, and local/state officials. This project was not included in a prior year MILCON program because this is the first time Hurlburt Field was directly impacted by such a significant natural disaster.

1. COMPONENT	FY 2005 MILITARY	DATA 2. DATE				
AIR FORCE	(computer generated)					
3. INSTALLATION A			4. PROJECT TITLE ADAL COMMAND POST			
5. PROGRAM ELEMEN	T 6. CATEGORY CODE	7. PROJECT NUMBER	8. PROJECT COST (\$000)			
27596	610-913	FTEV043020	1,358			

CURRENT SITUATION: The existing Command Post was designed to sustain Category 3 hurricane winds (110 mph) and is inadequately sized to support additional operations. The other three operation centers (SRC, SFCC, FSCC) are currently located in geographically separated facilities that are only rated for Category 2 winds (90 mph). Collocation of these functions in a facility rated for 150+ mph winds will provide the Wing Commander and Battle Staff with instant access to these important resources, and allow them to more efficiently sustain and utilize the 16 SOW's full mission capabilities.

IMPACT IF NOT PROVIDED: Reduced communication capabilities between vital operation centers will continue to negatively impact response times to emergency situations and create potential risks to personnel and resources. If not provided, an opportunity to consolidate command and control of all organizations critical to maintaining the 16 SOW mission capability will be lost.

ADDITIONAL: This project meets the criteria/scope specified in Air Force Handbook 32-1084, "Facility Requirements" and is urgently required as evidenced by Hurricane Ivan's substantial damage to Hurlburt Field (\$45M). Base Civil Engineer: William A. Kolakowski, Lt Col, USAF, 850/884-7701. Addition: 290 SM (3,115SF); Alterations: 513 SM (5,527SF).

<u>JOINT USE CERTIFICATION:</u> This facility not only manages AF Special Operation aircraft, but also U.S. Special Operations Command's (SOCOM) mission critical "on-call" assets.

1. COMPONENT FY 2005 MILITARY CONSTRUCTION PROJECT DATA 2. DATE AIR FORCE (computer generated) 3. INSTALLATION AND LOCATION 4. PROJECT TITLE HURLBURT FIELD, FLORIDA CONSTRUCT WORK BAYS AUTO HOBBY SHOP 5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000) EEIC 529 740-665 FTEV045002 230 9. COST ESTIMATES								
3. INSTALLATION AND LOCATION HURLBURT FIELD, FLORIDA CONSTRUCT WORK BAYS AUTO HOBBY SHOP 5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000) EEIC 529 740-665 FTEV045002 230	1. COMPONENT		2. DATE					
HURLBURT FIELD, FLORIDA 5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000) EEIC 529 740-665 FTEV045002 230 9. COST ESTIMATES	AIR FORCE (computer generated)							
5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PROJECT NUMBER 8. PROJECT COST (\$000)	3. INSTALLATION AND LOCATION 4. PROJECT TITLE							
740-665 FTEV045002 EEIC 529 9. COST ESTIMATES	HURLBURT FIEL	A	CONSTRUCT WORK BAYS AUTO HOBBY SHOP					
740-665 FTEV045002 230 9. COST ESTIMATES	5. PROGRAM ELEMENT 6. CATEGORY CODE 7. PR				1			
9. COST ESTIMATES						EEIC 529		
	740-665 FTEN				EV045002	2 230		
INIT	9. COST ESTIMATES							
ITEM U/M QUANTITY	COST							
PRIMARY FACILITIES 23-	PRIMARY FACILIT	IES					234	
AUTO HOBBY SHOP MAINT. BAYS SF 1,800 130 (23	AUTO HOBBY SHOP MAINT. BAYS				1,800	130	(234)	
SUPPORTING FACILITIES	SUPPORTING FACILITIES						0	
SUBTOTAL 23	SUBTOTAL						234	
TOTAL CONTRACT COST 23	TOTAL CONTRACT COST						234	
TOTAL REQUEST 23	TOTAL REQUEST						234	
TOTAL REQUEST (ROUNDED) 23								

- 10. Description of Proposed Work: Construct new 1800 SF building to provide six additional auto hobby shop bays. The building will be located adjacent to existing auto hobby shop maintenance bays. The building will be a corrugated metal building with standing seam metal roof. The proposed structure shall have electrical outlets, lighting, six overhead doors, two personel doors and an HVAC system.
- 11. Requirement: Adequate: Substandard:

PROJECT: Construct Work Bays Auto Hobby Shop

<u>REQUIREMENT:</u> The proposed sructure will be an 1800 SF building to provide six additional auto hobby shop bays. The proposed structure shall have electrical outlets, lighting, six overhead doors, two personel doors and an HVAC system

CURRENT SITUATION: The existing auto hobby shop size is inadequate for the base population. There are long customer lines both during the week as well as the weekend.

IMPACT IF NOT PROVIDED: If not provided, the quality of life for base personel will be impacted. Especially the younger enlisted troops who depend on the use of the shop to help cut down on auto maintenance costs.

				,
		,		1
				1
				1 1
				1 1 1
				1 1 1
				1
				1
				1 1 1
				1 1 1
,				1

1. COMPONENT	FY 2008 MILITARY CONSTRUCTION PROJECT DATA					2. DATE
AIR FORCE	(computer generated)					
3. INSTALLATION AND LOCATION 4. PROJECT TITLE HURLBURT FIELD, FLORIDA FAMILY CAMPING FACILITY						
5. PROGRAM EL	EMENT	6. CATEGORY CODE	7. PRO	JECT NUMBER	8. PROJECT CO	OST (\$000)
NAF		750-611	FTEV045003			500

privately owned facilities in this area is extermely high from April through September, with demand far exceeding availability. The existing FAMCAMP is often filled to capacity and campers are turned away on a daily basis resulting in loss of income.

IMPACT IF NOT PROVIDED: Failure to provide this facility would omit a most important link in the network of RV accommodations which the Air Force is now constructing throughout the United States. Without question this location would be used to the maximum extent throughout the year and provide a valuable service to our transit and vacationing Air Force families. The military community will continue to be denied recreational activities offered at other military installations of comparable size, thus affecting morale and retention of quality personnel.

,		









